

① Test Specifications Fuel Injection Pumps and Governors

①

WPP 001/4 SAV 5,2 f

En

6. Edition

PES 6 MW 100/320 RS 1009
RQV 300...1400 MW 15 R
Komb. Nr. 0 403 446 113
1 - 5 - 3 - 6 - 2 - 4 = - 60 - 120 - 180 - 240 - 300 ± 0,5 (0,75)°

supersedes 11.80
company: SAVIEM
engine MIDR 06.02-12

All test specifications are valid for Bosch Fuel Injection Pump Test Benches and Testers

A. Fuel Injection Pump Settings

Port closing at prestroke		3,00 - 3,10 (2,95 - 3,15) mm (from BDC)		Control rod travel = 9,0 - 12,0 mm		
Rotational speed	Control rod travel	Fuel delivery	Difference	Control rod travel	Fuel delivery	Spring pre-tensioning (torque-control valve)
rev/min	mm	cm ³ /100 strokes	cm ³ /100 strokes	mm	cm ³ /100 strokes	mm
1	2	3	4	2	3	6
1400	11,6 ^{+0,1}	9,4 - 9,6	0,35 (0,6)			
300	6,0 - 6,2	0,95 - 1,35	0,35 (0,55)			
900	See	sect. C!	0,5 (0,7)			
500	"	"	0,35 (0,6)			

Adjust the fuel delivery from each outlet according to the values in

Testoil-ISO 4113

B. Governor Settings

Upper rated speed			Intermediate rated speed			Lower rated speed			Sliding sleeve travel ①	
Degree of deflection of control lever	rev/min Control rod travel mm	Control rod travel mm ①a rev/min ①b	Degree of deflection of control lever	rev/min	Control rod travel mm ①c	Degree of deflection of control lever	rev/min	Control rod travel mm ①d	rev/min	mm
1	2	3	4	5	6	7	8	9	10	11
ca. 68	1400 1700	15,2 - 17,8 0,0 - 1,0				ca. 12	100	min. 8,0	1440 - 1450	= 8,2
ca. 64	10,7	1440-1450					300	6,0 - 6,2	380 - 430	= 2,5
	4,0	1570-1600					480 - 540 = 2,0		300	1,2-1,3

Torque control travel a = mm

C. Settings for Fuel Injection Pump with Fitted Governor

Full-load delivery Control-rod stop Test oil temp. 40°C (104°F)		Rotational-speed limitation ② intermediate speed ④a	Fuel delivery characteristics high idle speed ⑤a intermediate speed ⑤b		Starting fuel delivery ⑥ idle switching point		Torque-control travel ⑤ Control rod travel	
rev/min	cm ³ /1000 strokes	rev/min	rev/min	cm ³ /1000 strokes	rev/min	cm ³ /1000 strokes	rev/min	mm
1	2	3	4	5	6	7	8	9
LDA 1400	0,67 bar 94,0 - 96,0 (92,0 - 98,0)	1440-1450*	LDA 900	0,67 bar 84,0 - 88,0 (82,0 - 90,0)	100 300	80,0 - 90,0 9,5 - 13,5 (7,0 - 16,0)		
			LDA 500	0 bar 63,0 - 65,0 (61,0 - 67,0)	100 - 230 (80 - 250)			

Checking values in brackets

* 1 mm less control rod travel than col. 2

BOSCH

Geschäftsbereich KH Kundendienst. Kfz-Ausrüstung
© by Robert Bosch GmbH, D-7 Stuttgart 1, Postfach 50 Printed in the Federal Republic of Germany
Imprimé en République Fédérale d'Allemagne par Robert Bosch GmbH

A1

D. Adjustment Test for Manifold Pressure Compensator

En

Test at n = 500 rev/min decreasing pressure - in bar gauge pressure
g

Pump/governor	Setting Gauge pressure = bar	Measurement Gauge pressure = bar	Control rod travel- diminution difference mm (1)
RS 1009/MW 15	0,67	0 0,25	11,6 - 11,7 11,0 - 11,1 11,3 - 11,4

Notes:

(1) when n =

rev/min and gauge pressure =

bar (= maximum full-load control rod travel)

Testoil-ISO 4113

② Test Specifications Fuel Injection Pumps and Governors

②

WPP 001/4 MB 14,6 g

En

4. Edition

PE 8 P 120 A 320 LS 3807

RQ 30C/1150 PA 546

Komb. Nr. 0 401 848 733

1 - 8 - 7 - 2 - 6 - 3 - 5 - 4 je 45° ± 0,5° (± 0,75°)

Values only apply to test nozzle-and-holder assembly 1 688 901 019 and fuel-injection test tubing 1 680 750 067.

supersedes

4.83

company:

Daimler-Benz

engine

OM 422 A

243 kw (330 PS)

All test specifications are valid for Bosch Fuel Injection Pump Test Benches and Testers

A. Fuel Injection Pump Settings

4,0 - 4,1

Port closing at prestroke (3,95 - 4,15) mm (from BDC)

Rotational speed rev/min 1	Control rod travel mm 2	Fuel delivery cm ³ /100 strokes 3	Difference cm ³ / 100 strokes 4	Control rod travel mm 2	Fuel delivery cm ³ /100 strokes 3	Spring pre-tensioning (torque-control valve) mm 6
1150	10,7 ^{+0,1}	15,6 - 15,8	0,5 (0,9)			
300	5,2 - 5,4	1,2 - 1,8	0,8 (1,2)			
750/500	---	C, 4 u. 5	0,7 (1,1)			

Adjust the fuel delivery from each outlet according to the values in

B. Governor Settings

Checking of slider PRG-check ①		Full-load speed regulation Setting point				Idle speed regulation Setting point		Test specifications ⑤		Torque control ③	
rev/min 1	Control rod travel mm 2	rev/min 3	Control rod travel mm 4	Control rod travel mm 5	rev/min 6	rev/min 7	Control rod travel mm 8	rev/min 9	Control rod travel mm 10	rev/min 11	Control rod travel mm 12
600	19,2 - 20,8	600	20,0	9,7 4,0	1200 - 1215 1235 - 1270	300	4,5	100 300 340 - 380 = 2,0	min. 6,0 4,4 - 4,6	1150 750 900	10,7 - 10,3 11,0 - 11,3 10,9 - 11,3
VH = max. 46°											

Torque-control travel on flyweight assembly dimension a = 0,2 mm

Speed regulation: At 1200 - 1215 min⁻¹

1 mm less control rod travel

C. Settings for Fuel Injection Pump with Fitted Governor

Full-loadet delivery on governor control lever Test oil temp. 40°C (104°F) ②		Control rod stop ③a	Fuel delivery characteristics ③b		Starting fuel delivery idle speed ⑥	
rev/min 1	cm ³ /1000 strokes 2	rev/min 3	rev/min 4	cm ³ /1000 strokes 5	rev/min 6	cm ³ /1000 strokes / mm 7
LDA 1150	0,7 bar 156,0 - 158,0 (153,0 - 161,0)		LDA 750	0,7 bar 172,0 - 174,0 (169,0 - 177,0)	100	140,0 - 160,0 (136,0 - 164,0)
			LDA 500	0 bar 135,0 - 137,0 (132,0 - 140,0)		

Checking values in brackets

6.83

BOSCH

Geschäftsbereich KH. Kundendienst Kfz-Ausrüstung

© by Robert Bosch GmbH, D-7 Stuttgart 1, Postfach 50 Printed in the Federal Republic of Germany

Imprimé en République Fédérale d'Allemagne par Robert Bosch GmbH

A3

D. Adjustment Test for Manifold Pressure Compensator

MB 14,6 g - 2 - En

Test at n = 500 rev/min **decreasing** pressure - in bar gauge pressure
g

Pump/governor	Setting Gauge pressure = bar	Measurement Gauge pressure = bar	Control rod travel- diminution difference mm (1)
PE 8 P..LS 3807 + ..PA 546	0,47	0 0,40	10,9 - 11,3 10,2 - 10,4 10,3 - 10,6

Notes:

(1) when n =

rev/min and gauge pressure =

bar (= maximum full-load control rod travel)

Testoil-ISO 4113

① Test Specifications Fuel Injection Pumps and Governors

40

①

WPP 001/4 MB 3,8 a

En

3. Edition

PES 4 A 80 C 410	RS 2094	RQV 300-1425 AB 564 D, 579 D	supersedes	12.74
	RS 2206	RQV 300-1300 AB 564 D	company:	Daimler-Benz
RS 2094,	RS 2244	RQV 300-1000/1425 AB 578 D,	engine	OM 314
.. D ..	RS 2244 A	RQV 300-1425 AB 623 DL, 624 D		

All test specifications are valid for Bosch Fuel Injection Pump Test Benches and Testers

A. Fuel Injection Pump Settings

Port closing at prestroke **2,15 - 0,1** mm (from BDC)

Rotational speed rev/min 1	Control rod travel mm 2	Fuel delivery cm ³ /100 strokes 3	Difference cm ³ / 100 strokes 4	Control rod travel mm 2	Fuel delivery cm ³ /100 strokes 3	Spring pre-tensioning (torque-control valve) mm 6
1000	9	5,5 - 6,0	0,4			
	6	2,2 - 3,0				
200	15	11,5 - 12,8				
	6	1,3 - 2,2				

Adjust the fuel delivery from each outlet according to the values in

B. Governor Settings

RQV 300 - 1425 AB 564 D

Upper rated speed			Intermediate rated speed			Lower rated speed			Sliding sleeve travel Torque-control travel	
Degree of deflection of control lever 1	rev/min Control rod travel mm 2	Control rod travel mm rev/min 3	Degree of deflection of control lever 4	rev/min 5	Control rod travel mm 6	Degree of deflection of control lever 7	rev/min 8	Control rod travel mm 9	rev/min 10	mm 11
ca. 66	1425	16,0 - 19,3				ca. 10	100	7,0 - 8,0	1425	8,3
	1450	14,6 - 18,2					250	5,5 - 7,0	--	--
	1550	8,2 - 13,3					400	3,5 - 5,2	1400	
	1650	1,3 - 8,0					500	2,5 - 3,7	600	0,35-0,45
	1750	0 - 2,5					600	1,4 - 2,8		
	1800	0					770	0		

Torque control travel a = 0,35 mm

C. Settings for Fuel Injection Pump with Fitted Governor

Full-load delivery Control-rod stop Test oil temp. 40°C (104°F)		Rotational-speed limitation	Fuel delivery characteristics		Starting fuel delivery idle switching point		Intermediate rotational speed Torque-control travel	
rev/min 1	cm ³ /1000 strokes 2	rev/min 3	rev/min 4	cm ³ /1000 strokes 5	rev/min 6	cm ³ /1000 strokes 7	rev/min 8	mm 9
1400	58,0 - 60,0	1460-1470*	1000	51,5 - 54,5	100	7,3 - 8,3		
			800	49,0 - 52,0				
			500	45,5 - 48,5				
(increase by ± 3 cm ³)								

Checking values in brackets

* 1 mm less control rod travel than col. 2

Testoil-ISO 4113

BOSCH

Geschäftsbereich KH Kundendienst Kfz-Ausrüstung
© by Robert Bosch GmbH, D-7 Stuttgart 1, Postfach 50 Printed in the Federal Republic of Germany
Imprimé en République Fédérale d'Allemagne par Robert Bosch GmbH

10.75

A5

B. Governor Settings

300 - 1000/1425 AB 578 D

MB 3,8 a

Upper rated speed			Intermediate rated speed			Lower rated speed			Sliding sleeve travel ^①	
Degree of deflection of control lever	rev/min Control rod travel mm	Control rod travel mm ^{①a} rev/min ^{②a}	Degree of deflection of control lever	rev/min	Control rod travel mm ^④	Degree of deflection of control lever	rev/min	Control rod travel mm ^③	rev/min	mm
1	2	3	4	5	6	7	8	9	10	11
ca. 68	1400 1450 1500 1550 1660	12,0 - 15,4 8,0 - 12,5 03,4 - 9,6 0 - 6,6 0	ca. 62	1000 1100 1200 1400 1490	12,0 - 14,6 5,2 - 8,2 5,2 - 5,6 1,7 - 4,8 0	ca. 10	200 300 350 400 740	7,8 - 8,0 6,0 - 6,8 5,0 3,2 - 3,9 0	300 800 1130-1350 1400	0,5 - 0,9 4,3 - 4,7 7,4 - 7,6 7,9 --
						③a			--	--

Torque control travel a = 0 mm

C. Settings for Fuel Injection Pump with Fitted Governor

Full-load delivery Control-rod stop Test oil temp. 40°C (104°F)		Rotational-speed limitation intermediate speed ^{②b} speed ^{④a}	Fuel delivery characteristics ^{⑤a} high idle speed ^{⑤b}		Starting fuel delivery ^⑥ idle switching point		Torque-control travel	
rev/min	cm ³ /1000 strokes	rev/min	rev/min	cm ³ /1000 strokes	rev/min	cm ³ /1000 strokes	rev/min	Control rod travel mm
1	2	3	4	5	6	7	8	9
800	47,0 - 49,0	1460-1470*	1400 500	56,5 - 59,5 41,5 - 44,5	100	7,3 - 8,3	700	
		(increase by ± 0.5 cm ³)			Change-over point 230 - 300 U/min			

Checking values in brackets

* 1 mm less control rod travel than col. 2

Testoil-ISO 4113

B. Governor Settings

RQV 300 - 1425 AB 579 D

Upper rated speed			Intermediate rated speed			Lower rated speed			Sliding sleeve travel Torque-control travel	
Degree of deflection of control lever	rev/min Control rod travel mm	Control rod travel mm ^{①a} rev/min ^{②a}	Degree of deflection of control lever	rev/min	Control rod travel mm ^④	Degree of deflection of control lever	rev/min	Control rod travel mm ^③	rev/min	mm ^①
1	2	3	4	5	6	7	8	9	10	11
ca. 66	1425 1450 1550 1650 1800	16,0 - 19,3 14,6 - 18,2 8,2 - 13,3 1,3 - 8,0 0				ca. 10	100 250 400 550 770	7,0 - 8,0 5,5 - 7,0 3,5 - 5,2 2,0 - 3,3 0	1425 --	8,3 --
						③a			--	--

Torque control travel a = 0 mm

C. Settings for Fuel Injection Pump with Fitted Governor

Full-load delivery Control-rod stop Test oil temp. 40°C (104°F)		Rotational-speed limitation intermediate speed ^{②b} speed ^{④a}	Fuel delivery characteristics ^{⑤a} high idle speed ^{⑤b}		Starting fuel delivery ^⑥ idle switching point		Torque-control travel	
rev/min	cm ³ /1000 strokes	rev/min	rev/min	cm ³ /1000 strokes	rev/min	cm ³ /1000 strokes	rev/min	Control rod travel mm
1	2	3	4	5	6	7	8	9
800	47,0 - 49,0	1460-1470*	1400 500	56,5 - 59,5 41,5 - 44,5	100	7,3 - 8,3	1300	
		(increase by ± 0.5 cm ³)			Change-over point 230 - 300 U/min			

Checking values in brackets

* 1 mm less control rod travel than col. 2

B. Governor Settings

300 - 1300 AB 564 D MB 3,8 a

- 3 -

Upper rated speed			Intermediate rate J speed			Lower rated speed			Sliding sleeve travel Torque-control travel	
Degree of deflection of control lever	rev/min Control rod travel mm	Control rod travel mm rev/min	Degree of deflection of control lever	rev/min	Control rod travel mm	Degree of deflection of control lever	rev/min	Control rod travel mm	rev/min	mm
1	2	3	4	5	6	7	8	9	10	11
ca. 66	1300	15,0 - 17,8				ca. 10	200	5,7 - 7,2	1300	8,3
	1350	10,5 - 14,5					350	3,8 - 5,3	1300	0
	1420	7,7 - 11,1					500	1,9 - 3,2	550	0,25-0,45
	1490	0 - 7,0					640	0 - 1,3		
	1600	0					700	0		

Torque control travel a = 0,35 mm

C. Settings for Fuel Injection Pump with Fitted Governor

Full-load delivery Control-rod stop Test oil temp. 40°C (104°F)		Rotational-speed limitation intermediate speed	Fuel delivery characteristics high idle speed		Starting fuel delivery idle switching point		Torque-control travel	
rev/min	cm ³ /1000 strokes	rev/min	rev/min	cm ³ /1000 strokes	rev/min	cm ³ /1000 strokes	rev/min	Control rod travel mm
1	2	3	4	5	6	7	8	9
1280	46,5 - 48,5	1320-1330*	1000	44,5 - 47,5	100	7,3 - 8,3		
			500	36,0 - 39,0	Change-over point 230 - 300 U/min			

Checking values in brackets

* 1 mm less control rod travel than col. 2

Testoil-ISO 4113

B. Governor Settings

300 - 1425 AB 623 D, .. 624 D

Upper rated speed			Intermediate rated speed			Lower rated speed			Sliding sleeve travel	
Degree of deflection of control lever	rev/min Control rod travel mm	Control rod travel mm rev/min	Degree of deflection of control lever	rev/min	Control rod travel mm	Degree of deflection of control lever	rev/min	Control rod travel mm	rev/min	mm
1	2	3	4	5	6	7	8	9	10	11
ca. 68	1425	16,0 - 19,0				ca. 10	200	6,0 - 7,4	1425	8,3
	1500	10,8 - 15,3					300	4,9 - 6,6	--	--
	1600	3,3 - 10,0					400	3,5 - 5,1	1400	0
	1650	0 - 7,4					500	2,5 - 3,7	600	0,35-0,45
	1770	0					770	0		

Torque control travel a = 0,35 mm

C. Settings for Fuel Injection Pump with Fitted Governor

Full-load delivery Control-rod stop Test oil temp. 40°C (104°F)		Rotational-speed limitation intermediate speed	Fuel delivery characteristics high idle speed		Starting fuel delivery idle switching point		Torque-control travel	
rev/min	cm ³ /1000 strokes	rev/min	rev/min	cm ³ /1000 strokes	rev/min	cm ³ /1000 strokes	rev/min	Control rod travel mm
1	2	3	4	5	6	7	8	9
1400	58,0 - 60,0	1460-1470*	1000	51,5 - 54,5	100	7,3 - 8,3	623 D = 1300	
			800	49,0 - 52,0	Change-over point 230 - 300 U/min		624 D = 700	
			500	45,5 - 48,5				

Checking values in brackets

* 1 mm less control rod travel than col. 2

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 320 RS 3207
 Regulator: RE 24
 IP-ASSEMBLY: 0 401 996 700

TEST SHEET : VOL 12,2 f
 Edition : 06.93 (4) EN
 Type number : 0 411 826 772
 Type number : 0 421 890 008
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO
 Engine: TD 122
 Output kW: 283
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature °C 38 42
 Overflow valve 2 417 413 064
 Inlet pressure bar 1.5 1.6
 Overflow 1) 1/h 100 120
 Calibrating nozzle-holder assembly 1 688 901 019
 Opening pressure bar 207 210
 Perforated plate diameter mm 0.8
 Test pressure line 1 680 750 075
 Dimensions:
 Outer diameter. mm 8.0
 x wall thickness mm 2.5
 x length mm 1000

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl. 1
 Test pressure ba 25 27
 Prestroke (from BDC) mm 3.60 3.70
 P Prestroke (from BDC) mm 3.55 4.75
 Control-rod travel mm 10.0 11.0
 Cam sequence 1 - 5 - 3 - 6 - 2 - 4
 PC difference °CS 60 each
 tolerance +/-°CS 0.50
 P tolerance +/-°CS 0.75

Min Max
 PC mark Cyl.-No. - 2)
 Pulse wheel position (PC cam) °CS 0 3)
 Tolerance +/-°CS 0.20
 P Tolerance +/-°CS 0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed 1/min 0
 Setting value U/actual V 3.100
 Control-rod travel mm 12.95 13.05
 P Control-rod travel mm 12.90 13.10

Check value

U/actual V 1.700
 Control-rod travel mm 5.90 6.40
 P Control-rod travel mm 5.85 6.45

Stop position

U/actual V mind. 4)
 Control-rod travel mm 0.5 1.0
 P Control-rod travel mm 0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	700	
U/actual	V	3.100	
Fuel			
delivery	cm3/1000str	248.0	250.0
P Fuel			
delivery	cm3/1000str	245.0	253.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	250	
U/actual	V	1.240	1.360
Fuel			
delivery	cm3/1000str	20.0	26.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

REMARKS

VOLVO-No.:

Dimension "Y"
(Adjustment flange) - -

- 1) = Setting of overflow at full load (refer to measurement point V1)
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 720 RS 7178
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 796 800

TEST SHEET : MAC 12.0 g
 Edition : 06.93 (5) EN
 Type number : 0 412 726 822
 Type number : 0 421 890 009
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: MACK
 Engine: E 7 - 400
 Output kW: - -
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature °C 38 42
 Overflow valve 2 417 413 011
 Inlet pressure bar 1.9 2.0
 Overflow 1) 1/h 160 170
 Calibrating nozzle-holder assembly 1 688 901 101
 Opening pressure bar 207 210
 Perforated plate diameter mm 0.6
 Test pressure line 1 680 750 008
 Dimensions:
 Outer diameter. mm 6.0
 x wall thickness mm 2.0
 x length mm 600

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl. 6
 Test pressure bar 22 24
 Prestroke (from BDC) mm 2.75 2.85
 P Prestroke (from BDC) mm 2.70 2.90
 Control-rod travel mm 10.3 10.7
 Cam sequence 6 - 2 - 4 - 1 - 5 - 3
 PC difference °CS 60 each
 tolerance +/-°CS 0.50
 P tolerance +/-°CS 0.75

Min Max
 PC mark Cyl.-No. - 2)
 Pulse wheel position (PC cam) °CS 0 3)
 Tolerance +/-°CS 0.20
 P Tolerance +/-°CS 0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed 1/min 0
 Setting value U/actual V 3.100
 Control-rod travel mm 12.95 13.05
 P Control-rod travel mm 12.90 13.10

Check value

U/actual V 1.700
 Control-rod travel mm 5.90 6.40
 P Control-rod travel mm 5.85 6.45

Stop position

U/actual V mind. 4)
 Control-rod travel mm 0.5 1.0
 P Control-rod travel mm 0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.400	
Fuel			
delivery	cm3/1000str	269.0	271.0
P Fuel			
delivery	cm3/1000str	266.0	274.0
Dispersion	cm3/1000str		7.0
P Dispersion	cm3/1000str		11.0

Test point L1

Speed	1/min	325	
U/actual	V	1.290	1.410
Fuel			
delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MACK-No.: 313 GC 5183-P6

Dimension "Y"
 (Adjustment flange) 15.6 15.9
 (If provided;
 adjustment flange was
 introduced in the course
 of series production)

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 6.
- 4) = U/actual value min:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PE 6 P 120 A 320 RS 3239
 Regulator: RE 24
 IP-ASSEMBLY 0 401 996 701

TEST SHEET : VOL 12,2 g
 Edition : 06.93 (4) EN
 Type number : 0 411 826 785
 Type number : 0 421 890 008
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO
 Engine: TD 122 (USA)
 Output kW: 268
 at 1/min:

	Min	Max
Test PREREQUISITES		

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 064	
Inlet pressure bar	1.5	1.6
Overflow 1) 1/h	-	-
Calibrating nozzle-holder assembly	1 688 901 019	
Opening pressure bar	207	210
Perforated plate diameter mm	0.8	
Test pressure line	1 680 750 075	
Dimensions:		
Outer diameter. mm	8.0	
x wall thickness mm	2.5	
x length mm	1000	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC) mm	2.60	2.70
P Prestroke (from BDC) mm	2.55	2.75
Control-rod travel mm	10.0	11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference °CS	60 each	
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel mm	12.95	13.05
P Control-rod travel mm	12.90	13.10
Check value U/actual	V	1.70
Control-rod travel mm	5.90	6.40
P Control-rod travel mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel mm	0.5	1.0	
P Control-rod travel mm	0.4	1.1	

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V	0.8	2.0
P pos.amplitude V	0.6	3.0
Speed	1/min	600
Difference Amplitude to Amplitude V	max.	1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	700	
U/actual	V	3.380	
Fuel			
delivery	cm3/1000str	251.0	254.0
P Fuel			
delivery	cm3/1000str	248.0	257.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	250	
U/actual	V	1.290	1.410
Fuel			
delivery	cm3/1000str	23.0	29.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

REMARKS

Dimension "Y"
(Adjustment flange) - -

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 110 A 720 RS 3231
 Regulator: RE 24
 IP-ASSEMBLY 0 402 196 701

TEST SHEET : DEE 10.1 k
 Edition : 06.93 (5) EN
 Type number : 0 412 016 729
 Type number : 0 421 890 006
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: JOHN DEERE
 Engine: 6101 HRW 02 (Tractor)
 Output kW: 224
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 057	
Inlet pressure bar	1.5	1.6
Overflow l/h	-	-
Calibrating nozzle-holder assembly	0 681 343 009	
Opening pressure bar	172	175
Perforated plate diameter mm	-	-
Test pressure line	1 680 750 015	
Dimensions:		
Outer diameter mm	6.0	
x wall thickness mm	1.5	
x length mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC) mm	3.35	3.45
P Prestroke (from BDC) mm	3.30	3.50
Control-rod travel mm	9.0	12.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference °CS	60 each	
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. 1 2)		
Pulse wheel position (PC cam) °CS	10.5	3)
Tolerance +/-°CS		1.70
P Tolerance +/-°CS		2.25

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed 1/min	0	
Setting value U/actual	V	3.100
Control-rod travel mm	12.95	13.05
P Control-rod travel mm	12.90	13.10
Check value U/actual	V	1.700
Control-rod travel mm	5.90	6.40
P Control-rod travel mm	5.85	6.45
Stop position U/actual	V	mind. 4)
Control-rod travel mm	0.5	1.0
P Control-rod travel mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1100	
U/actual	V	2.706	
Fuel			
delivery	cm3/1000str	176.0	178.0
P Fuel			
delivery	cm3/1000str	173.0	181.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	425	
U/actual	V	1.340	1.460
Fuel			
delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

REMARKS

- Dimension "Y"
(Adjustment flange) - -
- 2) = Port-closing mark 10.5° camshaft after port closing of cylinder 1.
 - 3) = Pulse wheel position 10.5° camshaft after port closing of cylinder 1.
 - 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 720 RS 3184
 Regulator: RE 24
 IP-ASSEMBLY: 0 402 196 700

TEST SHEET : DEE 7,7 1
 Edition : 06.93 (4) EN
 Type number : 0 412 026 727
 Type number : 0 421 890 006
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: JOHN DEERE
 Engine: 6.466 A
 Output kW: 161
 at 1/min:

	Min	Max
Test PREREQUISITES		

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 057	
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 101	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.6	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	3.55 3.65
P Prestroke (from BDC)	mm	3.50 3.70
Control-rod travel	mm	9.0 12.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	10.5 3)
Tolerance +/-°CS		1.70
P Tolerance +/-°CS		2.25

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

Min Max

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1100	
U/actual	V	2.710	
Fuel			
delivery	cm3/1000str	140.0	142.0
P Fuel			
delivery	cm3/1000str	137.0	145.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	425	
U/actual	V	1.340	1.460
Fuel			
delivery	cm3/1000str	18.0	24.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

REMARKS

Dimension "Y"
(Adjustment flange)

- 2) = Port-closing mark 10.5° camshaft after port closing of cylinder 1.
- 3) = Pulse wheel position 10.5° camshaft after port closing of cylinder No. 1.
- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PE 8 P 120 A 920/4 LS 7149
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 698 802

TEST SHEET : SCA 14.2 k
 Edition : 06.93 (6) EN
 Type number : 0 412 628 826
 Type number : 0 421 890 007
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: SCANIA
 Engine: DSC 1404
 Output kW: 347
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 025	
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 019	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	5.00 5.10
P Prestroke (from BDC)	mm	4.95 5.15
Control-rod travel	mm	9.0 12.0
Cam sequence	1-2-7-3-4-5-6-8	
PC difference	°CS	45 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, RPM actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value		
RPM actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10

Check value

RPM actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

RPM actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude	V	0.8 2.0
P pos.amplitude	V	0.6 3.0
Speed	1/min	600
Difference		
Amplitude to		
Amplitude	V	max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator
 - Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
 (Observe "Remarks" Point 5))

Test point V1

Speed	1/min	700	
RPM actual	V	3.180	
Fuel delivery	cm3/1000str	226.0	228.0
P Fuel delivery	cm3/1000str	223.0	231.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	225	
RPM actual	V	1.540	1.660
Fuel delivery	cm3/1000str	15.0	21.0
Dispersion	cm3/1000str		3.0
P Dispersion	cm3/1000str		6.0

REMARKS

SCANIA No.:

Dimension "Y"
 (Adjustment flange) 15.6 16.1
 (If provided;
 adjustment flange was
 introduced in the course
 of series production)

- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = RPM actual value min.:
 RPM actual minimum value with deenergized servo magnet and control rod in shutoff position.

REMARKS (Continued)

- 5) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm:
 Pump page 2, front.

Delivery-valve holder:

- * Valve spring pre-tension: mm 3.2 3.4
- * Allowed variation: mm 3.0 3.5
- * Required setting for new delivery-valve holders due to flattening: mm 2.9 3.1

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 8007
 Regulator: RE 30
 IP-ASSEMBLY 0 402 996 298

TEST SHEET : MAC 12.0 1
 Edition : 06.93 (4) EN
 Type number : 0 412 926 015
 Type number : 0 421 890 009
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MACK
 Engine: E 7 - 400
 Output kW: - -
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 011	
Inlet pressure bar	-	-
Overflow 1) l/h	100	110
Calibrating nozzle-holder assembly	1 688 901 101	
Opening pressure bar	207	210
Perforated plate diameter mm	0.6	
Test pressure line	1 680 750 008	
Dimensions:		
Outer diameter. mm	6.0	
x wall thickness mm	2.0	
x length mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING 2)

PC setting cyl.	6	
Test pressure bar	22	24
Prestroke (from BDC) mm	3.55	3.65
P Prestroke (from BDC) mm	3.50	3.70
Control-rod travel mm	10.3	10.7
Cam sequence	6 - 2 - 4 - 1 - 5 - 3	
PC difference °CS	60 each	
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. - 3)		
Pulse wheel position (PC cam) °CS	0	4)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value			
U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value			
U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position			
U/actual	V	mind.	5)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60	
pos.amplitude V		0.8	2.0
P pos.amplitude V		0.6	3.0
Speed	1/min	600	
Difference Amplitude to Amplitude	V	max.	1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	2.930	
Fuel delivery	cm3/1000str	274.0	276.0
P Fuel delivery	cm3/1000str	271.0	279.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	325	
U/actual	V	1.080	1.200
Fuel delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MACK-No.: 313 GC 5193-P1

Dimension "Y"
(Adjustment flange) 15.6 15.9

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = Note additional test "Start-of-delivery difference":
Between CRT mm 10.5
and CRT mm 20.0
Difference °CS 0.7 0.8
- 3) = No start-of-delivery mark.
- 4) = Setting of pulse-wheel position at start of delivery of cylinder No. 6.

REMARKS (Continued)

- 5) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 7204
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 796 802

TEST SHEET : MAC 12.0 k
 Edition : 06.93 (7) EN
 Type number : 0 412 726 836
 Type number : 0 421 890 014
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MACK
 Engine: EM 7 - 250...E 7-350
 Output kW: - -
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 011	
Inlet pressure	bar	1.9	2.0
Overflow 1)	l/h	160	170
Calibrating nozzle-holder assembly		1 688 901 101	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.6	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	6	
Test pressure bar	22	24
Prestroke (from BDC)	mm	3.25 3.35
P Prestroke (from BDC)	mm	3.20 3.40
Control-rod travel	mm	10.3 10.7
Cam sequence	6 - 2 - 4 - 1 - 5 - 3	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. - 2)		
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Version 1 5)

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.100	
Fuel delivery	cm3/1000str	247.0	249.0
P Fuel delivery	cm3/1000str	244.0	252.0
Dispersion	cm3/1000str		7.0
P Dispersion	cm3/1000str		11.0

Test point L1

Speed	1/min	325	
U/actual	V	1.230	1.350
Fuel delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Section C -

Version 2 5)

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.100	
Fuel delivery	cm3/1000str	244.0	246.0
P Fuel delivery	cm3/1000str	241.0	249.0
Dispersion	cm3/1000str		7.0
P Dispersion	cm3/1000str		11.0

	Min	Max
--	-----	-----

Test point L1

Speed	1/min	325	
U/actual	V	1.230	1.350
Fuel delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MACK-No.: 313 GC 5191-P1

Dimension "Y"
(Adjustment flange) 15.6 15.9
(If provided;
adjustment flange was
introduced in the course
of series production).

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 6.
- 4) = U/actual value min:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.
- 5) = Test values of version 1 only apply to fuel-injection pumps with constant-pressure valve 2 418 559 013.

Test values of version 2 only apply to fuel-injection pumps with constant-pressure valve 2 418 559 029.

The last three digits of the order number are stamped on the top collar of the constant-pressure valve.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 320 RS 8014
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 005

TEST SHEET : VOL 10.3 b
 Edition : 06.93 (3) EN
 Type number : 0 412 826 015
 Type number : 0 421 890 010
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO (BUS 8885)
 Engine: THD 103 KB, KF, TD 103 KB, KF
 Output kW: 180, 210
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 064	
Inlet pressure	bar	2.5	2.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 103	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	2.95 3.05
P Prestroke (from BDC)	mm	2.90 3.10
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. - 2)		
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value U/actual	V	1.70
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude	V	0.8 2.0
P pos.amplitude	V	0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	650	
U/actual	V	2.800	
Fuel			
delivery	cm3/1000str	295.0	297.0
P Fuel			
delivery	cm3/1000str	292.0	300.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	300	
U/actual	V	1.340	1.460
Fuel			
delivery	cm3/1000str	23.0	29.0
Dispersion	cm3/1000str		7.0
P Dispersion	cm3/1000str		11.0

REMARKS

VOLVO-No.: 425 100

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 720 RS 7259
 Regulator: RE 30
 IP-ASSEMBLY 0 402 796 809

TEST SHEET: DEE
 Edition: 06.93 (1) EN
 Type number: 0 412 726 863
 Type number: 0 421 890 014
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: JOHN DEERE
 Engine: 6101 HRW 11
 Output kW: 233
 at 1/min: 2100

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413	077
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901	103
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750	015
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING 1)

PC setting cyl.	1	
Test pressure	bar	25 27
Prestroke (from BDC)	mm	3.55 3.65
P Prestroke (from BDC)	mm	3.50 3.70
Control-rod travel	mm	9.00 12.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value U/actual	V	1.70
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude	V	0.8 2.0
P pos.amplitude	V	0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1050	
U/actual	V	2.840	
Fuel			
delivery	cm3/1000str	212.0	214.0
P Fuel			
delivery	cm3/1000str	210.0	216.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	250	
U/actual	V	1.530	1.650
Fuel			
delivery	cm3/1000str	23.0	29.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

REMARKS

JOHN DEERE : RE 42 302

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = Flow begin-incipient fissure
 8.75 degrees NW after flow
 begin cylinder 1.
 Incipient fissure over clutch
 and indicator.
 Incipient fissure measured at
 62...68 degrees to vertical
 axis of pump.
- 3) = Setting of pulse-wheel
 position at flow begin
- 4) = U/actual value min:
 U/actual minimum value with
 deenergized servo magnet and
 control rod in shutoff
 position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 3184
 Regulator : RE 24
 IP-ASSEMBLY: 0 402 196 702

TEST SHEET : DEE 7.7 m
 Edition : 06.93 (2) EN
 Type number : 0 412 026 727
 Type number : 0 421 890 006
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: JOHN DEERE
 Engine: 6076 HH030, HRW30
 Output kW:
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 057	
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 101	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.6	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	3.55 3.65
P Prestroke (from BDC)	mm	3.50 3.70
Control-rod travel	mm	9.0 12.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS 10.5	3)
Tolerance +/-°CS		1.70
P Tolerance +/-°CS		2.25

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60	
pos.amplitude V		0.8	2.0
P pos.amplitude V		0.6	3.0
Speed	1/min	600	
Difference Amplitude to Amplitude	V	max.	1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1			
Speed	1/min	1100	
U/actual	V	2.710	
Fuel			
delivery	cm3/1000str	140.0	142.0
P Fuel			
delivery	cm3/1000str	137.0	145.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0
Test point L1			
Speed	1/min	425	
U/actual	V	1.340	1.460
delivery	cm3/1000str	18.0	24.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

REMARKS

- Dimension "Y"
(Adjustment flange)
- 2) = Port-closing mark 10.5° camshaft after port closing of cylinder 1.
 - 3) = Pulse wheel position 10.5° camshaft after port closing of cylinder 1.
 - 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 7240
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 796 806

TEST SHEET : UNI 9.5 j
 Edition : 06.93 (2) EN
 Type number : 0 412 726 855
 Type number : 0 421 890 013
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: IVECO - UNIC
 Engine: 8460.41.5020
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 025	
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	5.10 5.20
P Prestroke (from BDC)	mm	5.05 5.25
Control-rod travel	mm	9.0 12.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, RPM actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value		
RPM actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10

Check value

RPM actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

RPM actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude	V	0.8 2.0
P pos.amplitude	V	0.6 3.0
Speed	1/min	600
Difference		
Amplitude to Amplitude	V	max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1050	
RPM actual	V	2.900	
Fuel			
delivery	cm3/1000str	260.0	262.0
P Fuel			
delivery	cm3/1000str	257.0	265.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	275	
RPM actual	V	1.520	1.640
Fuel			
delivery	cm3/1000str	45.0	51.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

Dimension "Y"
(Adjustment flange) 15.6 16.1

2) = No start-of-delivery mark.

3) = Setting of pulse-wheel
position at start of delivery
of cylinder No. 1.

4) = RPM actual value min.:
RPM actual minimum value with
deenergized servo magnet and
control rod in shutoff
position.

BOSCH TEST SPECS. IP ASSEMBLY

Pump : PES 6 P 120 A 720/3 LS 7221
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 796 803

TEST SHEET : MAN 12.0 a
 Edition : 06.93 (2) EN
 Type number : 0 412 726 841
 Type number : 0 421 890 007
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MAN
 Engine: D 2866 LF 10
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413	025
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901	105
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750	015
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "p"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING 1)

PC setting cyl.		6	
Test pressure bar		25	27
Prestroke (from BDC)	mm	4.80	4.90
P Prestroke (from BDC)	mm	4.75	4.95
Control-rod travel	mm	15.0	16.0
Cam sequence		6 - 2 - 4 - 1 - 5 - 3	
PC difference tolerance +/-°CS		60 each	0.50
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "p"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

Min Max

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1000	
U/actual	V	3.120	
Fuel			
delivery	cm3/1000str	263.0	265.0
P Fuel			
delivery	cm3/1000str	260.0	268.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	300	
U/actual	V	1.330	1.450
Fuel			
delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MAN-No.: 3-7101

Dimension "Y"
(Adjustment flange) 15.6 16.1

- 1) = Note additional test "Start-of-delivery difference":

Between CRT mm	4.40	4.60
and CRT mm	15.0	16.0
Difference °CS	1.75	3.25
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 6.
- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY

Pump: PES 6 P 120 A 720/3 LS 7221
Regulator: RE 30
IP-ASSEMBLY 0 402 796 804

TEST SHEET: MAN 12.0 a 1
Edition: 06.93 (3) EN
Type number: 0 412 726 841
Type number: 0 421 890 012
CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MAN
Engine: D 2866 LF 10
Output kW:
at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature °C 38 42
Overflow valve 2 417 413 025
Inlet pressure bar 1.5 1.6
Overflow l/h - -
Calibrating nozzle-holder assembly 1 688 901 105
Opening pressure bar 207 210
Perforated plate diameter mm 0.8
Test pressure line 1 680 750 015
Dimensions:
Outer diameter. mm 6.0
x wall thickness mm 1.5
x length mm 600

TEST SPECIFICATIONS

Section A -
Setting values of injection pump
- Check values denoted by "P"
- No basic setting. Equal delivery setting under Section C.

PORT CLOSING 1)

PC setting cyl. 6
Test pressure bar 25 27
Prestroke (from BDC) mm 4.80 4.90
P Prestroke (from BDC) mm 4.75 4.95
Control-rod travel mm 15.0 16.0
Cam sequence 6 - 2 - 4 - 1 - 5 - 3
PC difference °CS 60 each
tolerance +/-°CS 0.50
P tolerance +/-°CS 0.75

Min Max

PC mark Cyl.-No. - 2)
Pulse wheel position (PC cam) °CS 0 3)
Tolerance +/-°CS 0.20
P Tolerance +/-°CS 0.75

Section B -

Actuator test
- Check values denoted by "P"
- Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed 1/min 0
Setting value U/actual V 3.100
Control-rod travel mm 12.95 13.05
P Control-rod travel mm 12.90 13.10

Check value

U/actual V 1.70
Control-rod travel mm 5.90 6.40
P Control-rod travel mm 5.85 6.45

Stop position

U/actual V mind. 4)
Control-rod travel mm 0.5 1.0
P Control-rod travel mm 0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
Speed 1/min 60
pos.amplitude V 0.8 2.0
P pos.amplitude V 0.6 3.0
Speed 1/min 600
Difference Amplitude to Amplitude V max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1000	
U/actual	V	3.120	
Fuel delivery	cm3/1000str	263.0	265.0
P Fuel delivery	cm3/1000str	260.0	268.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	300	
U/actual	V	1.380	1.500
Fuel delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MAN-NR.: 51.22203-7184

Dimension "Y"
(Adjustment flange) 15.6 16.1

- 1) = Note additional test "Start-of-delivery difference":

Between CRT mm	4.40	4.60
and CRT mm	15.0	16.0
Difference °CS	1.75	3.25
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 8 P 120 A 920/4 LS 7205
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 698 804

TEST SHEET : SCA 14.2 o
 Edition : 06,93 (5) EN
 Type number : 0 412 628 845
 Type number : 0 421 890 007
 CUSTOMER IDENT. NO.:

=====
 Customer-specific details
 Customer: SCANIA
 Engine: DSC 1409
 Output kW:
 at 1/min:
 =====

	Min	Max
=====		
T e s t P R E R E Q U I S I T E S		

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413	025
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901	104
Opening pressure	bar	250	253
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750	008
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

=====
 T E S T S P E C I F I C A T I O N S

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	5.00 5.10
P Prestroke (from BDC)	mm	4.95 5.15
Control-rod travel	mm	10.0 11.0
Cam sequence		1-2-7-3-4-5-6-8
PC difference	°CS	45 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
=====		
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, RPM actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value RPM actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10

Check value

RPM actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

RPM actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
(Observe "Remarks" Point 5))

Test point V1

Speed	1/min	700
RPM actual	V	3.000
Fuel delivery	cm3/1000str	247.0 249.0
P Fuel delivery	cm3/1000str	244.0 252.0
Dispersion	cm3/1000str	8.0
P Dispersion	cm3/1000str	12.0

Test point L1

Speed	1/min	250
RPM actual	V	1.350 1.470
Fuel delivery	cm3/1000str	10.0 16.0
Dispersion	cm3/1000str	4.0
P Dispersion	cm3/1000str	8.0

REMARKS

SCANIA-No.: 1 303 800

Dimension "Y"
(Adjustment flange) 15.6 16.1
(If provided;
adjustment flange was
introduced in the course
of series production)

- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = RPM actual value min.: RPM actual minimum value with deenergized servo magnet and control rod in shutoff position.

REMARKS (Continued)

- 5) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm: Pump page 2, front.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 7235
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 796 805

TEST SHEET : MAC 12.0 n
 Edition : 06.93 (5) EN
 Type number : 0 412 726 847
 Type number : 0 421 890 014
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: MACK
 Engine: E 7-350
 Output kW: - -
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 011	
Inlet pressure bar	1.9	2.0
Overflow 1) l/h	160	170
Calibrating nozzle-holder assembly	1 688 901 101	
Opening pressure bar	207	210
Perforated plate diameter mm	0.6	
Test pressure line	1 680 750 008	
Dimensions:		
Outer diameter. mm	6.0	
x wall thickness mm	2.0	
x length mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	6	
Test pressure bar	22	24
Prestroke (from BDC) mm	3.25	3.35
P Prestroke (from BDC) mm	3.20	3.40
Control-rod travel mm	10.3	10.7
Cam sequence	6 - 2 - 4 - 1 - 5 - 3	
PC difference °CS	60 each	
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. - 2)		
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section E -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min 0	
Setting value U/actual	V 3.100	
Control-rod travel	mm 12.95	13.05
P Control-rod travel	mm 12.90	13.10

Check value U/actual	V 1.700	
Control-rod travel	mm 5.90	6.40
P Control-rod travel	mm 5.85	6.45

Stop position U/actual	V mind.	4)
Control-rod travel	mm 0.5	1.0
P Control-rod travel	mm 0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.100	
Fuel delivery	cm3/1000str	244.0	246.0
P Fuel delivery	cm3/1000str	241.0	249.0
Dispersion	cm3/1000str		7.0
P Dispersion	cm3/1000str		11.0

Test point L1

Speed	1/min	325	
U/actual	V	1.230	1.350
Fuel delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MACK-No.: 313 GC 5201-P1

Dimension "Y"
(Adjustment flange) 15.6 15.9

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 6.
- 4) = U/actual value min:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 720 RS 7245
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 796 807

TEST SHEET : MAC
 Edition : 06.93 (5) EN
 Type number : 0 412 726 858
 Type number : 0 421 890 015
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: MACK
 Engine: E 7 - 350
 Output kW: - -
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 011	
Inlet pressure	bar	1.9	2.0
Overflow 1)	l/h	160	170
Calibrating nozzle-holder assembly		1 688 901 101	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.6	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	6	
Test pressure bar	22	24
Prestroke (from BDC)	mm	3.25 3.35
P Prestroke (from BDC)	mm	3.20 3.40
Control-rod travel	mm	10.3 10.7
Cam sequence	6 - 2 - 4 - 1 - 5 - 3	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. - 2)		
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.100	
Fuel			
delivery	cm3/1000str	244.0	246.0
P Fuel			
delivery	cm3/1000str	241.0	249.0
Dispersion	cm3/1000str		7.0
P Dispersion	cm3/1000str		11.0

Test point L1

Speed	1/min	325	
U/actual	V	1.230	1.350
Fuel			
delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MACK-No.: 313 GC 5204-P1

Dimension "Y"
 (Adjustment flange) 15.6 15.9
 (If provided;
 adjustment flange was
 introduced in the course
 of series production)

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 6.
- 4) = U/actual value min:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 720/3 LS 7252
 Regulator: RE 30
 IP-ASSEMBLY 0 402 796 808

TEST SHEET: MAN
 Edition: 06.93 (2) EN
 Type number: 0 412 726 861
 Type number: 0 421 890 012
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MAN
 Engine: D 2866 LF 10
 Output kW: 309
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 025	
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING 1)

PC setting cyl.		6	
Test pressure	bar	25	27
Prestroke (from BDC)	mm	4.80	4.90
P Prestroke (from BDC)	mm	4.75	4.95
Control-rod travel	mm	15.0	16.0
Cam sequence	6 - 2 - 4 - 1 - 5 - 3		
PC difference	°CS	60 each	
tolerance +/-°CS			0.50
P tolerance +/-°CS			0.75

Min Max

PC mark	Cyl.-No.	- 2)	
Pulse wheel position (PC cam)	°CS	0	3)
Tolerance +/-°CS			0.20
P Tolerance +/-°CS			0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10

Check value

U/actual	V	1.70	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60	
pos.amplitude V		0.8	2.0
P pos.amplitude V		0.6	3.0
Speed	1/min	600	
Difference Amplitude to Amplitude	V	max.	1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1000	
U/actual	V	3.120	
Fuel			
delivery	cm3/1000str	263.0	265.0
P Fuel			
delivery	cm3/1000str	260.0	268.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	300	
U/actual	V	1.380	1.500
Fuel			
delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MAN-NR.: 51.22203-7210

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Note additional test
 "Start-of-delivery
 difference":
 Between CRT mm 6.40 6.60
 and CRT mm 15.0 16.0
 Difference °CS 1.75 3.25
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel
 position at start of delivery
 of cylinder No. 6.
- 4) = U/actual value min:
 U/actual minimum value with
 deenergized servo magnet and
 control rod in shutoff
 position.

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : Audi
 Date of manufacture :
 Edition : 30.04.1992
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE5/11E2300L400
 Type No. : 0 460 415 998
 Customer Ident.No. :

Customer-specific details
 Customer : Audi

Engine : 180-02-TDI-C4

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0,30...0,40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6,00
 x wall thickness > : 2,20
 x length > mm : 350

Overflow valve : 2 467 413 006

Test line : 0 986 612 432
 (fuel-delivery
 actuator) : (KDEP 1865/3)

Test line : 0 986 612 435
 (solenoid valve start
 of injection) : (KDEP 1865/6)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0,4...1,0
 50°...70°C, ohms : 0,45...1,1

Connections 4 and
 ground, Mohms min. : 1,0
 Connections 7 and
 ground, Mohms min. : 1,0
 Connections 2 and 7
 Mohms min. : 1,0
 Connections 4 and 6
 Mohms min. : 1,0

Control-collar travel sensor
 Test temperature :
 15°...70°C
 Connections 2 and 3
 kohms : 1,0...3,0
 Connections 1 and 3
 kohms : 0,5...2,0

Connections 1 and
 ground, Mohms min. : 1,0
 Connections 2 and
 ground, Mohms min. : 1,0
 Connections 3 and
 ground, Mohms min. : 1,0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1,2...4,0
 50°...70°C, kohms : 0,3...1,2

Connections 5 and
 ground, Mohms min. : 1,0
 Connections 6 and
 ground Mohms min. : 1,0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14,3...17,3
 50°...70°C, ohms : 15,5...21,0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 750
Checkbk. volt. : 3900
mV : 3900
Setting value, bar : 6,2...7,2

Timing device travel:

Speed 1/min : 750
Checkbk. volt : 3900
mV : 3900
Setting value, mm : 9,70...9,90

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2125
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt : 2440
mV : 2440
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 39,3...39,7
Dispersion cm³/
> 1000s : 2,5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2125
Checkbk. volt : 3900
mV : 3900
Supply pump
pressure > bar : 8,1...9,1
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3900
Timing device
travel mm : 7,8...10,2
> mm : (7,5...11,5)

2nd speed 1/min : 750
Checkbk. volt. mV : 3900
Timing device
travel mm :
> mm : (9,4...11,2)

3rd speed 1/min : 1000
Checkbk. volt. mV : 1800
Timing device
travel mm : max. 0,3
> mm : (max. 1,0)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2125
Checkbk. volt. mV : 3900
Timing device
travel mm : 11,6...12,6
> mm : (11,5...12,7)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2125
Checkbk. volt. mV : 3900
Measuring
temperature °C : 53
Overflow : 40...60
> cm³/10 : (35...65)

Fuel delivery variations:

1st temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2125
 Checkbk. volt mV : 3900
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 54,2...56,8
 > 1000s : (53,0...58,0)
 Dispersion cm³/ : 3,0
 > 1000s : (5,0)

2nd temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 60
 Speed 1/min : 1000
 Checkbk. volt mV : 3200
 Measuring
 temperature °C : 56
 Fuel delivery cm³/ : 55,7...58,3
 > 1000s : (54,5...59,5)
 Dispersion cm³/ : 2,5
 > 1000s : (4,0)

3rd temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2440
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (37,5...41,5)
 Dispersion cm³/ :
 > 1000s :

4th temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2300
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 40,2...42,8
 > 1000s : (39,2...43,8)
 Dispersion cm³/ : 3,0
 > 1000s :

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 1570
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 7,2...12,2
 > 1000s : (5,2...14,2)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 3,5
 > 1000s : (5,0)

Starting fuel delivery:
 1st temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2900
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ :
 > 1000s : 74,0
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:
 Speed 1/min : 1100
 Checkbk. volt mV : 4125
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3,0
 Start of
 injection, volts : 12

Shutoff solenoid:
 Cut-in voltage
 min.> volts : 10,0
 Rated voltage,
 volts : 12,0

Notes:
 Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description		
K	mm	: 2.7...2.9
KF	mm	: 6,5...6,9
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 494

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 30.04.1992
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R440
 Type No. : 0 460 404 993
 Customer Ident.No. :

Customer-specific details
 Customer :VW

Engine : 028.C

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 006

Test line : 0 986 612 432
 (fuel-delivery : (KDEP 1865/3)
 actuator)

Test line : 0 986 611 983
 (solenoid valve : (KDEP 1190)
 start of injection)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

Control-collar travel sensor
 Test temperature :
 15°...70°C
 Connections 2 and 3
 kohms : 1.0...3.0
 Connections 1 and 3
 kohms : 0.5...2.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 2245
Setting value, bar : 6.5...7.1

Timing device travel:

Speed 1/min : 750
Checkbk. volt
mV : 3350
Setting value, mm : 10.7...10.9

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 38.8...39.2
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 3890
Supply pump
pressure > bar : 9.0...9.6
> bar :

1st speed 1/min : 150
Checkbk. volt
mV : 2230
Supply pump
pressure > bar :
> bar : min. 3.5

Timing device variations:

1st speed 1/min : 500
Checkbk. volt.
mV : 2245
Timing device
travel mm : 9.3...11.7
> mm : (8.0...13.0)

2nd speed 1/min : 750
Checkbk. volt.
mV : 3350
Timing device
travel mm :
> mm : (9.9...11.7)

3rd speed 1/min : 1000
Checkbk. volt.
mV : 1475
Timing device
travel mm : max. 0.3
> mm : (max. 0.5)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 1400
Checkbk. volt.
mV : 1475
Timing device
travel mm :
> mm : (max. 1.0)

Start of
injection, volts : 12

5.th speed 1/min : 2000
Checkbk. volt.
mV : 3890
Timing device
travel mm : 11.6...12.8
> mm : (11.4...13.0)

6.th speed 1/min : 150
Checkbk. volt.
mV : 2230
Timing device
travel mm : 2.0...7.0
> mm : (min. 1.5)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt.
mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt.
mV : 3890
Measuring
temperature °C : 53
Overflow : 40...60
> cm³/10 : (35...65)

Fuel delivery variations:

1st temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt : 2500
 mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2000
 Checkbk. volt : 3890
 mV : 3890
 Measuring
 temperature °C : 53
 Fuel delivery cm³/ : 47.7...50.3
 > 1000s : (46.5...51.5)
 Dispersion cm³/ : 4.0
 > 1000s : (5.0)

2nd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt : 2500
 mV : 2500
 Output
 temperature °C : 60
 Speed 1/min : 1000
 Checkbk. volt : 2860
 mV : 2860
 Measuring
 temperature °C : 56
 Fuel delivery cm³/ : 41.6...44.2
 > 1000s : (40.4...45.4)
 Dispersion cm³/ : 3.0
 > 1000s : (4.0)

3rd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt : 2500
 mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt : 2480
 mV : 2480
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 37.0...41.0
 > 1000s : (37.0...41.0)
 Dispersion cm³/ : 5.0
 > 1000s : (5.0)

4th temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt : 2500
 mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt : 2245
 mV : 2245
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 36.7...39.3
 > 1000s : (35.7...40.3)
 Dispersion cm³/ : 4.0
 > 1000s : (5.0)

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 1600
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 10.2...15.2
 > 1000s : (9.2...16.2)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 4.0
 > 1000s : (5.0)

Starting fuel delivery:
 1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2230
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 31.0
 > 1000s : 31.0
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:

Speed 1/min : 750
 Checkbk. volt mV : 2480
 ELAB volts : 0
 Fuel delivery cm³/ : 8.0
 max. 1000s : 8.0

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	: 5,8...6,2
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 376

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : Audi
 Date of manufacture :
 Edition : 13.04.1992
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE5/11E2400L323
 Type No. : 0 460 415 999
 Customer Ident.No. :

Customer-specific details
 Customer : Audi

Engine : 180-02-TDI-C3
 Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0,30...0,40
 Calibrating nozzle-holder assembly > : 1 688 901 114
 Opening pressure > bar : 207...210
 Test pressure line : 1 680 750 085
 Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350
 Overflow valve : 2 467 413 006
 Test line : KDEP 1865/3
 (fuel-delivery actuator)
 Test line : KDEP 1865/6
 (solenoid valve start of injection)

TEST PRECONDITIONS

Test oil return temp. > °C with thermometer : 55
 Test oil supply temperature > °C : 42...47
 Hold-up revolutions >1/min : 1200
 Feedback voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0,4...1,0
 50°...70°C, ohms : 0,45...1,1

Connections 4 and ground, Mohms min. : 1,0
 Connections 7 and ground, Mohms min. : 1,0
 Connections 2 and 7 Mohms min. : 1,0
 Connections 4 and 6 Mohms min. : 1,0

Control-collar travel sensor
 Test temperature : 15°...70°C
 Connections 2 and 3 kohms : 1,0...3,0
 Connections 1 and 3 kohms : 0,5...2,0

Connections 1 and ground, Mohms min. : 1,0
 Connections 2 and ground, Mohms min. : 1,0
 Connections 3 and ground, Mohms min. : 1,0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1,2...4,0
 50°...70°C, kohms : 0,3...1,2

Connections 5 and ground, Mohms min. : 1,0
 Connections 6 and ground Mohms min. : 1,0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14,3...17,3
 50°...70°C, ohms : 15,5...21,0

Starting stop mV : 4120...4650
 Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000
Checkbk. volt. : 3300
mV : 3300
Setting value, bar : 7,1...8,1

Timing device travel:

Speed 1/min : 1000
Checkbk. volt : 3300
mV : 3300
Setting value, mm : 10,4...10,6

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2125
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt : 2740
mV : 2740
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 38,3...38,7
Dispersion cm³/
> 1000s : 2,5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2125
Checkbk. volt : 3900
mV : 3900
Supply pump
pressure > bar : 8,9...9,9
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2500
Timing device
travel mm : 7,8...10,2
> mm : (6,7...11,3)

2nd speed 1/min : 1000
Checkbk. volt. mV : 3300
Timing device
travel mm :
> mm : (9,6...11,4)

3rd speed 1/min : 1000
Checkbk. volt. mV : 1800
Timing device
travel mm : max. 0,3
> mm : (max. 1,0)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2125
Checkbk. volt. mV : 3900
Timing device
travel mm : 10,2...11,8
> mm : (9,5...12,5)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2125
Checkbk. volt. mV : 3900
Measuring
temperature °C : 53
Overflow : 40...60
> cm³/10 : (35...65)

Fuel delivery variations:

1st temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2125
 Checkbk. volt mV : 3900
 Measuring
 temperature °C : 53
 Fuel delivery cm³/ : 46,4...49,0
 > 1000s : (45,2...50,2)
 Dispersion cm³/ : 3,0
 > 1000s. :

2nd temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 60
 Speed 1/min : 1000
 Checkbk. volt mV : 3300
 Measuring
 temperature °C : 56
 Fuel delivery cm³/ : 47,5...50,1
 > 1000s : (46,3...51,3)
 Dispersion cm³/ : 2,5
 > 1000s : (4,0)

3rd temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2740
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (36,5...40,5)

4th temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2500
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 35,5...38,1
 > 1000s : (34,5...39,1)
 Dispersion cm³/ : 3,0
 > 1000s :

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 400
 Checkbk. volt mV : 2000
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 6,5...11,5
 > 1000s : (4,5...13,5)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 5,0
 > 1000s : (6,0)

Starting fuel delivery:
 1st temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 3500
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ :
 > 1000s : 73,0
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:
 Speed 1/min : 1100
 Checkbk. volt mV : 4125
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3,0
 Start of
 injection, volts : 12

Shutoff solenoid:
 Cut-in voltage
 min.> volts : 10,0
 Rated voltage,
 volts : 12,0

Notes:
 Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:
 Description
 K mm :
 KF mm : 6,5...6,9
 SVS max. mm :
 FH mm :
 TS : 1 467 010 494

BOSCH TEST SPECS. IP ASSEMBLY

Pump: PES 5 P 120 A 720/3 LS 7250
 Regulator: RE 30
 IP-ASSEMBLY 0 402 795 800

TEST SHEET: MAN
 Edition: 06.93 (2) EN
 Type number: 0 412 725 810
 Type number: 0 421 890 012
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MAN
 Engine: D 2865 LF 10
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 025	
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING 1)			
PC setting cyl.		5	
Test pressure bar		25	27
Prestroke (from BDC)	mm	4.80	4.90
P Prestroke (from BDC)	mm	4.75	4.95
Control-rod travel	mm	15.0	16.0
Cam sequence		1 - 3 - 5 - 4 - 2	
PC difference	°CS	0-72-144-216-288	
tolerance +/-°CS			0.50
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.70	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60	
pos.amplitude	V	0.8	2.0
P pos.amplitude	V	0.6	3.0
Speed	1/min	600	
Difference Amplitude to Amplitude	V	max.	1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1000	
U/actual	V	3.120	
Fuel			
delivery	cm3/1000str	263.0	265.0
P Fuel			
delivery	cm3/1000str	260.0	268.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	325	
U/actual	V	1.410	1.530
Fuel			
delivery	cm3/1000str	27.0	33.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MAN-NR.: 51.11103-7233

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Note additional test
 "Start-of-delivery
 difference":

Between CRT mm	6.40	6.60
and CRT mm	15.0	16.0
Difference °CS	1.75	3.25
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel
 position at start of delivery
 of cylinder No. 5.
- 4) = U/actual value min:
 U/actual minimum value with
 deenergized servo magnet and
 control rod in shutoff
 position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 8501
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 996 301

TEST SHEET : MAC
 Edition : 11.93 (3) EN
 Type number : 0 412 926 201
 Type number : 0 421 890 015
 CUSTOMER IDENT. NO.:

=====
 Customer-specific details
 Customer: MACK
 Engine: EM 7 - 350
 Output kW: - -
 at 1/min:
 =====

	Min	Max
===== T e s t P R E R E Q U I S I T E S =====		

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 084	
Inlet pressure bar	2.4	2.6
Overflow 1) l/h	- -	- -
Calibrating nozzle-holder assembly	1 688 901 103	
Opening pressure bar	207	210
Perforated plate diameter mm	0.7	
Test pressure line	1 680 750 008	
Dimensions:		
Outer diameter mm	6.0	
x wall thickness mm	2.0	
x length mm	600	

=====
 T E S T S P E C I F I C A T I O N S
 =====

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

=====
 PORT CLOSING
 =====

PC setting cyl.	6	
Test pressure bar	22	24
Prestroke (from BDC) mm	4.55	4.65
P Prestroke (from BDC) mm	4.50	4.70
Control-rod travel mm	11.8	12.2
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference °CS	60 each	
tolerance +/-°CS		0.30
P tolerance +/-°CS		0.75

	Min	Max
===== PC mark Cyl.-No. - 3) Pulse wheel position (PC cam) °CS 0 4) Tolerance +/-°CS 0.20 P Tolerance +/-°CS 0.75 =====		

Section B -
 Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

=====
 CONTROL-ROD PICKUP SETTING
 =====

Test speed	1/min 0	
Setting value U/actual	V 3.100	
Control-rod travel	mm 12.95	13.05
P Control-rod travel	mm 12.90	13.10
Check value U/actual	V 1.700	
Control-rod travel	mm 5.90	6.40
P Control-rod travel	mm 5.85	6.45
Stop position U/actual	V mind. 5)	
Control-rod travel	mm 0.5	1.0
P Control-rod travel	mm 0.4	1.1

=====
 SPEED SENSOR SIGNALS
 =====

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference
 Amplitude to Amplitude V max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.050	
Fuel			
delivery	cm3/1000str	309.0	311.0
P Fuel			
delivery	cm3/1000str	305.0	315.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		14,0
Speed	1/min	325	
U/actual	V	1.250	1.370
Fuel			
delivery	cm3/1000str	30.0	36.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

MACK-No.: 313 GC 5205-P1

Dimension "Y"
 (Adjustment flange) 15.6 15.9

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 3) = No start-of-delivery mark.
- 4) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 5) = U/actual value min:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Obsereve notes in remark colum

Test sheet : BMW
 Date of manufacture :
 Edition : 19.10.1992
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE6/10E2400R300-1
 Type No. : 0 460 406 995
 Customer Ident.No. :

Customer-specific details
 Customer : BMW

Engine : M51

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 022

Opening
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00
 x wall thickness > : 2.00
 x length > mm : 450

Test line : 0 986 612 430
 (fuel-delivery
 actuator) : (KDEP 1865/1)

Test line : 0 986 612 435
 (solenoid valve
 start of injection): (KDEP 1865/6)

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

Control-collar travel sensor
 Test temperature :
 15°...70°C
 Connections 2 and 3
 kohms : 1.0...3.0
 Connections 1 and 3
 kohms : 0.5...2.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connentions 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1500
Checkbk. volt. : 3000
Setting value, bar : 7.2...7.8

Timing device travel:

Speed 1/min : 1500
Checkbk. volt : 3000
Setting value, mm : 8.4...8.8

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 1500
Checkbk. volt : 3000
Fuel delivery cm³/
> 1000s : 44.5...44.9
Dispersion cm³/ : 2.0
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2400
Checkbk. volt : 3000
Supply pump
pressure > bar : 8.5...9.5
> bar :

2st speed 1/min : 350
Checkbk. volt : 3850
Supply pump
pressure > bar : 5.4...6.3
> bar :

Timing device variations:

1st speed 1/min : 350
Checkbk. volt. mV : 3850
Timing device
travel mm : 4.8...6.2
> mm : (4.5...6.5)

2nd speed 1/min : 1500
Checkbk. volt. mV : 3000
Timing device
travel mm :
> mm : (7.9...9.3)

3rd speed 1/min : 1500
Checkbk. volt. mV : 3000
Timing device
travel mm : 0.0...0.2
> mm :

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2300
Checkbk. volt. mV : 3000
Timing device
travel mm : 9.5...10.1
> mm : (9.3...10.3)

5.th speed 1/min : 150
Checkbk. volt. mV : 3850
Timing device
travel mm : 1.3...4.7
> mm : (1.0...5.0)

Overflow at overflow valve:

Speed 1/min : 2400
Checkbk. volt. mV : 3000
Overflow : 69...180
> cm³/10 :

Fuel delivery variations:

1. Speed 1/min : 2400
Checkbk. volt mV : 3000
Fuel delivery cm³/ : 45.0...47.0
> 1000s : (43.5...48.5)
Dispersion cm³/ : 2.5
> 1000s. : (2.5)

2. Speed 1/min : 1500
Checkbk. volt mV : 3000
Fuel delivery cm³/ :
> 1000s : (42.9...46.5)
Dispersion cm³/ :
> 1000s : (2.0)

3. Speed 1/min : 1000
Checkbk. volt mV : 3100
Fuel delivery cm³/ : 46.0...48.0
> 1000s : (44.5...49.5)
Dispersion cm³/ : 2.0
> 1000s : (2.0)

4. Speed 1/min : 1000
Checkbk. volt mV : 2350
Fuel delivery cm³/ : 13.6...14.8
> 1000s : (11.9...16.5)
Dispersion cm³/ : 2.0
> 1000s : (2.0)

4. Speed 1/min : 5000
Checkbk. volt mV : 3000
Fuel delivery cm³/ : 30.9...32.9
> 1000s : (29.4...34.4)
Dispersion cm³/ : 2.0
> 1000s : (2.0)

Idle delivery:

Speed 1/min : 350
Checkbk. volt mV : 2600
Fuel delivery cm³/ : 7.4...9.4
> 1000s : (5.9...10.9)

Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 4.0
> 1000s : (2.0)

Starting fuel delivery:
Speed 1/min : 100
Checkbk. volt mV : 3680
Fuel delivery cm³/ :
> 1000s : 33.0
Solenoid valve
Start of
injection, volts : 12

Stop test:
Speed 1/min : 2400
Checkbk. volt mV : 3000
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : Audi
 Date of manufacture :
 Edition : 01.06.1993
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE5/11E2300L460
 Type No. : 0 460 415 997
 Customer Ident.No. :

Customer-specific details
 Customer : Audi

Engine : 180-02-TDI-C4

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0,30...0,40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6,00
 x wall thickness > : 2,20
 x length > mm : 350

Overflow valve : 2 467 413 009

Test line : 0 986 612 440
 (fuel-delivery
 actuator) : (KDEP 1865/11)

Test line : 0 986 612 435
 (solenoid valve start
 of injection) : (KDEP 1865/6)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0,4...1,0
 50°...70°C, ohms : 0,45...1,1

Connections 4 and
 ground, Mohms min. : 1,0
 Connections 7 and
 ground, Mohms min. : 1,0
 Connections 2 and 7
 Mohms min. : 1,0
 Connections 4 and 6
 Mohms min. : 1,0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 3
 Ohms : 4,9...6,5
 Connections 2 and 3
 Ohms : 4,9...6,5
 Connections 1 and 2
 Ohms : 9,8...13,0

Connections 1 and
 ground, Mohms min. : 1,0
 Connections 2 and
 ground, Mohms min. : 1,0
 Connections 3 and
 ground, Mohms min. : 1,0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1,2...4,0
 50°...70°C, kohms : 0,3...1,2

Connections 5 and
 ground, Mohms min. : 1,0
 Connections 6 and
 ground Mohms min. : 1,0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14,3...17,3
 50°...70°C, ohms : 15,5...21,0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 750
Checkbk. volt. : 3900
mV : 3900
Setting value, bar : 6,0...7,0

Timing device travel:

Speed 1/min : 750
Checkbk. volt : 3900
mV : 3900
Setting value, mm : 9,30...9,50

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2125
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt : 2460
mV : 2460
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 39,6...40,0
Dispersion cm³/
> 1000s : 2,5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2125
Checkbk. volt : 3900
mV : 3900
Supply pump
pressure > bar : 7,9...8,9
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3900
Timing device
travel mm : 7,5...9,9
> mm : (7,2...10,2)

2nd speed 1/min : 750
Checkbk. volt. mV : 3900
Timing device
travel mm :
> mm : (7,5...11,3)

3rd speed 1/min : 1200
Checkbk. volt. mV : 1800
Timing device
travel mm : max. 0,3
> mm : (max. 1,0)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2125
Checkbk. volt. mV : 3900
Timing device
travel mm : 11,6...12,6
> mm : (11,5...12,7)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2125
Checkbk. volt. mV : 3900
Measuring
temperature °C : 53
Overflow : 110...165
> cm³/10 : (97...180)

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2125
Checkbk. volt mV : 3900
Meßtemperatur °C : 53
Fuel delivery cm³/ : 54,3...56,9
> 1000s : (53,6...57,6)
Dispersion cm³/ : 3,0
> 1000s :

2nd temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 3210
Measuring
temperature °C : 56
Fuel delivery cm³/ : 55,7...58,3
> 1000s : (55,0...59,0)
Dispersion cm³/ : 2,0
> 1000s : (2,5)

3rd temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2460
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (38,5...41,1)
Dispersion cm³/ :
> 1000s :

4th temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2320
Measuring
temperature °C : 57
Fuel delivery cm³/ : 40,8...43,4
> 1000s : (40,1...44,1)
Dispersion cm³/ : 3,0
> 1000s :

Idle delivery:

1st temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 1520
Meßtemperatur °C : 57
Fuel delivery cm³/ : 8,1...12,1
> 1000s : (7,1...13,1)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3,0
> 1000s : (4,0)

Starting fuel delivery:

1st temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2960
Measuring
temperature °C : 61
Fuel delivery cm³/ :
> 1000s : 72,3

Solenoid valve

Start of
injection, volts : 12

Stop test:

Speed 1/min : 1100
Checkbk. volt mV : 4125
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3,0
Start of
injection, volts : 12

Shutoff solenoid:

Cut-in voltage
min.> volts : 10,0
Rated voltage,
volts : 12,0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	: 2.7...2.9
KF	mm	:
SVS max.	mm	:
FH	mm	:

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : Alfa
 Date of manufacture :
 Edition : 19.10.1992
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2100L450
 Type No. : 0 460 404 997
 Customer Ident.No. :

Customer-specific details
 Customer : Motori VM

Engine : 425 CHIEA

Output kW :
 Speed 1/min : 2200

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 022

Opening
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00
 x wall thickness > : 2.00
 x length > mm : 450

Overflow valve : 2 467 413 009

Test line : 0 986 612 434
 (fuel-delivery : (KDEP 1865/5)
 actuator)

Test line : 0 986 612 435
 (solenoid valve : (KDEP 1865/6)
 start of injection)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 45

Test oil supply
 temperature > °C : 35...40

Hold-up
 revolutions >1/min : 1100
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

Control-collar travel sensor
 Test temperature :
 15°...70°C
 Connections 2 and 3
 kohms : 1.0...3.0
 Connections 1 and 3
 kohms : 0.5...2.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt. : 2700
mV : 2700
Setting value, bar : 6.1...6.7

Timing device travel:

Speed 1/min : 500
Checkbk. volt : 2700
mV : 2700
Setting value, mm : 8.10...8.50

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 42
Speed 1/min : 1250
Checkbk. volt : 2000
mV : 2000
Measuring
temperature °C : 44
Fuel delivery cm³/
> 1000s : 30.0...30.4
Dispersion cm³ / : 2.0
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt : 2700
mV : 2700
Supply pump
pressure > bar : 8.2...9.2
> bar :

2st speed 1/min : 150
Checkbk. volt : 2900
mV : 2900
Supply pump
pressure > bar : 3.5...5.5
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2700
Timing device
travel mm :
> mm : (7.6...9.0)

2nd speed 1/min : 1000
Checkbk. volt. mV : 2700
Timing device
travel mm : 9.1...9.7
> mm : (8.7...10.1)

3rd speed 1/min : 1000
Checkbk. volt. mV : 1550
Timing device
travel mm : max. 0.5
> mm :

Solenoid valve
Start of
injection, volts : 12

4th speed 1/min : 2100
Checkbk. volt. mV : 2700
Timing device
travel mm : 9.5...10.1
> mm : (9.4...10.2)

5th speed 1/min : 2100
Checkbk. volt. mV : 1450
Timing device
travel mm : max. 1.0
> mm :

Solenoid valve
Start of
injection, volts : 12

6th speed 1/min : 150
Checkbk. volt. mV : 2900
Timing device
travel mm : 3.0...6.0
> mm : (2.0...7.0)

Solenoid valve

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 41
Speed 1/min : 2100
Checkbk. volt. mV : 2700
Measuring
temperature °C : 43
Overflow : 55...165
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 41
Speed 1/min : 2100
Checkbk. volt mV : 2700
Meßtemperatur °C : 43
Fuel delivery cm³/ : 64.0...67.0
> 1000s : (63.0...68.0)
Dispersion cm³/ : 2.0
> 1000s. : (2.5)

2nd temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 42
Speed 1/min : 1500
Checkbk. volt mV : 2700
Measuring
temperature °C : 44
Fuel delivery cm³/ : 67.6...70.0
> 1000s : (66.3...71.3)
Dispersion cm³/ : 2.0
> 1000s : (2.5)

3rd temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 42
Speed 1/min : 1250
Checkbk. volt mV : 2000
Measuring
temperature °C : 44
Fuel delivery cm³/ :
> 1000s : (28.2...32.2)
Dispersion cm³/ :
> 1000s : (2.5)

4th temperature-conditioning
revolution 1/min : 2100/100
Checkbk. volt mV : 2500
Output
temperature °C : 45
Speed 1/min : 1000
Checkbk. volt mV : 2700
Measuring
temperature °C : 45
Fuel delivery cm³/ : 68.4...70.8
> 1000s : (67.1...72.1)
Dispersion cm³/ : 2.0
> 1000s : (2.5)

5th temperature-conditioning
revolution 1/min : 2100
Checkbk. volt mV : 2500
Output
temperature °C : 48
Speed 1/min : 600
Checkbk. volt mV : 2300
Measuring
temperature °C : 46
Fuel delivery cm³/ : 44.8...47.8
> 1000s : (43.8...48.8)
Dispersion cm³/ : 2.0
> 1000s : (2.5)

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 400
Checkbk. volt mV : 1830
Meßtemperatur °C : 49
Fuel delivery cm³/ :
> 1000s : (13.5...18.5)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ :
> 1000s : (2.5)

Starting fuel delivery:
1st temperature-conditioning
revolution 1/min : 2100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 100
Checkbk. volt mV : 2900
Measuring
temperature °C : 49
Fuel delivery cm³/ :
> 1000s : 56.0
Solenoid valve
Start of
injection, volts : 12

Stop test:
Speed 1/min : 2100
Checkbk. volt mV : 2700
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 19.10.1992
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R440-1
 Type No. : 0 460 404 995
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 028.C
 Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40
 Calibrating nozzle-
 holder assembly > : 1 688 901 114
 Opening
 pressure > bar : 207...210
 Test pressure line : 1 680 750 085
 Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350
 Overflow valve : 2 467 413 006
 Test line : 0 986 612 432
 (fuel-delivery : (KDEP 1865/3)
 actuator)
 Test line : 0 986 612 983
 (solenoid valve : (KDEP 1190)
 start of injection)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55
 Test oil supply
 temperature > °C : 42...47
 Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

Control-collar travel sensor
 Test temperature :
 15°...70°C
 Connections 2 and 3
 kohms : 1.0...3.0
 Connections 1 and 3
 kohms : 0.5...2.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2245
Setting value, bar : 6.5...7.1

Timing device travel:
Speed 1/min : 750
Checkbk. volt
mV : 3350
Setting value, mm : 10.70...10.90

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 40.1...40.5
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 3890
Supply pump
pressure > bar : 9.0...9.6
> bar :

2st speed 1/min : 150
Checkbk. volt
mV : 2230
Supply pump
pressure > bar : mind.3.5

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2245
Timing device
travel mm : 9.3...11.7
> mm : (8.9...12.1)

2nd speed 1/min : 750
Checkbk. volt. mV : 3350
Timing device
travel mm :
> mm : (9.8...11.8)

3rd speed 1/min : 1400
Checkbk. volt. mV : 1475
Timing device
travel mm : max. 0.8
> mm :

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2000
Checkbk. volt. mV : 3890
Timing device
travel mm : 11.6...12.8
> mm : (11.4...13.0)

5.th speed 1/min : 150
Checkbk. volt. mV : 2230
Timing device
travel mm : 2.0...7.0
> mm : (mind.1.5)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3890
Measuring
temperature °C : 53
Overflow : 110...165
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2000
 Checkbk. volt mV : 3890
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 49.3...51.9
 > 1000s : (48.8...52.4)
 Dispersion cm³/ : 2.5
 > 1000s. : (2.5)

2nd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 60
 Speed 1/min : 1000
 Checkbk. volt mV : 2860
 Measuring
 temperature °C : 56
 Fuel delivery cm³/ : 42.9...45.5
 > 1000s : (42.7...45.7)
 Dispersion cm³/ : 2.5
 > 1000s : (2.5)

3rd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2480
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (39.0...41.6)
 Dispersion cm³/ :
 > 1000s : (2.5)

4th temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2245
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 38.3...40.9
 > 1000s : (37.3...41.9)
 Dispersion cm³/ : 3.0
 > 1000s : (3.0)

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 1600
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 11.8...16.8
 > 1000s : (11.3...17.3)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 4.0
 > 1000s : (4.0)

Starting fuel delivery:
 1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2230
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ :
 > 1000s : 31.8

Solenoid valve
 Start of
 injection, volts : 12

Stop test:
 Speed 1/min : 750
 Checkbk. volt mV : 2480
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description
 K mm :
 KF mm : 5.8...6.2
 SVS max. mm :
 FH mm :
 TS : 1 467 010 376

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 320 RS 8018
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 007

TEST SHEET : VOL
 Edition : 06.93 (2) EN
 Type number : 0 412 826 019
 Type number : 0 421 890 010
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO (BUS 8885, 8889)
 Engine: THD 103KF,KB,TD 103KB,KF
 Output kW: 180/210
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 078	
Inlet pressure	bar	2.5	2.6
Overflow	l/h	- -	- -
Calibrating nozzle-holder assembly		1 688 901 103	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	2.95 3.05
P Prestroke (from BDC)	mm	2.90 3.10
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	- 2)	
Pulse wheel position (PC cam)	°CS 0 3)	
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10

Check value

U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.3 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	650	
U/actual	V	2.800	
Fuel			
delivery	cm3/1000str	295.0	297.0
Fuel			
delivery	cm3/1000str	292.0	300.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		11.0

Test point L1

Speed	1/min	300	
U/actual	V	1.340	1.460
Fuel			
delivery	cm3/1000str	24.0	28.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		8.0

REMARKS

VOLVO-No.: 425 510

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 320 RS 8019
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 008

TEST SHEET : VOL
 Edition : 06.93 (2) EN
 Type number : 0 412 826 020
 Type number : 0 421 890 010
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO (LKW3047/1)
 Engine: TD 123 EA/EB/EC
 Output kW: 221/234/265
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 078	
Inlet pressure	bar	2.5	2.6
Overflow	l/h	- -	- -
Calibrating nozzle-holder assembly		1 688 901 103	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	4.30 4.40
P Prestroke (from BDC)	mm	4.25 4.45
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. - 2)		
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45
Stop position U/actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference
 Amplitude to Amplitude V max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	600	
U/actual	V	3.100	
Fuel			
delivery	cm3/1000str	345.0	347.0
Fuel			
delivery	cm3/1000str	342.0	350.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		11.0

Test point L1

Speed	1/min	300	
U/actual	V	1.340	1.460
Fuel			
delivery	cm3/1000str	31.0	35.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		8.0

REMARKS

VOLVO-No.: 479 887

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 320 RS 8020
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 009

TEST SHEET : VOL
 Edition : 06.93 (2) EN
 Type number : 0 412 826 021
 Type number : 0 421 890 010
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO (LKW)
 Engine: TD 123 E/ES, TD 103E/ES
 Output kW: 262/290/210/235
 at 1/min:

	Min	Max
Test PREREQUISITES		
Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 078	.
Inlet pressure bar	2.5	2.6
Overflow l/h	- -	- -
Calibrating nozzle-holder assembly	1 688 901 103	
Opening pressure bar	207	210
Perforated plate diameter mm	0.7	
Test pressure line	1 680 750 008	
Dimensions:		
Outer diameter. mm	6.0	
x wall thickness mm	2.0	
x length mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC) mm	3.95	4.05
P Prestroke (from BDC) mm	3.90	4.10
Control-rod travel mm	10.0	11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference °CS	60 each	
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. -	2)	
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value		
U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45
Stop position		
U/actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

	Min	Max
Section C -		
Injection pump with actuator		
- Check values denoted by "P"		
FUEL DELIVERY TEST AND SETTING		
Test point V1		
Speed	1/min	600
U/actual	V	2.800
Fuel delivery	cm3/1000str	301.0 303.0
Fuel delivery	cm3/1000str	298.0 306.0
Dispersion	cm3/1000str	8.0
P Dispersion	cm3/1000str	11.0
Test point L1		
Speed	1/min	250
U/actual	V	1.340 1.460
Fuel delivery	cm3/1000str	20.0 24.0
Dispersion	cm3/1000str	5.0
P Dispersion	cm3/1000str	8.0
REMARKS		
VOLVO-No.: 479 889		
Dimension "Y"		
(Adjustment flange) 15.6 16.1		
2) = No start-of-delivery mark.		
3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.		
4) = U/actual value min.: U/actual minimum value with deenergized servo magnet and control rod in shutoff position.		

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed 1/min 600

U/actual V 2.800

Fuel delivery cm3/1000str 301.0 303.0

Fuel delivery cm3/1000str 298.0 306.0

Dispersion cm3/1000str 8.0

P Dispersion cm3/1000str 11.0

Test point L1

Speed 1/min 250

U/actual V 1.340 1.460

Fuel delivery cm3/1000str 20.0 24.0

Dispersion cm3/1000str 5.0

P Dispersion cm3/1000str 8.0

REMARKS

VOLVO-No.: 479 889

Dimension "Y"

(Adjustment flange) 15.6 16.1

2) = No start-of-delivery mark.

3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.

4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 320 RS 8020-1
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 010

TEST SHEET : VOL
 Edition : 06.93 (2) EN
 Type number : 0 412 826 022
 Type number : 0 421 890 010
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO LKW 3027/2-BUS8886
 Engine: TD 123 ED, THD 103, KD
 Output kW: 302/250
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 078	
Inlet pressure	bar	2.5	2.6
Overflow	l/h	- -	- -
Calibrating nozzle-holder assembly		1 688 901 103	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	3.95 4.05
P Prestroke (from BDC)	mm	3.90 4.10
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value		
U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10

Check value

U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference
 Amplitude to
 Amplitude V max. 1.4

Continued on next page

	Min	Max
Section C -		
Injection pump with actuator		
- Check values denoted by "P"		
FUEL DELIVERY TEST AND SETTING		
Test point V1		
Speed	1/min	600
U/actual	V	2.800
Fuel delivery	cm3/1000str	301.0 303.0
Fuel delivery	cm3/1000str	298.0 306.0
Dispersion	cm3/1000str	8.0
P Dispersion	cm3/1000str	11.0
Test point L1		
Speed	1/min	300
U/actual	V	1.340 1.460
Fuel delivery	cm3/1000str	29.0 33.0
Dispersion	cm3/1000str	5.0
P Dispersion	cm3/1000str	8.0
REMARKS		
VOLVO-No.: 479 888		
Dimension "Y"		
(Adjustment flange) 15.6 16.1		
2) = No start-of-delivery mark.		
3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.		
4) = U/actual value min.: U/actual minimum value with deenergized servo magnet and control rod in shutoff position.		

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 320 RS 8021
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 011

TEST SHEET : VOL
 Edition : 06.93 (2) EN
 Type number : 0 412 826 023
 Type number : 0 421 890 010
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO (BUS 886)
 Engine: THD 103 KD
 Output kW: 250
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature °C 38 42
 Overflow valve 2 417 413 078
 Inlet pressure bar 2.5 2.6
 Overflow l/h - - - -
 Calibrating nozzle-holder assembly 1 688 901 103
 Opening pressure bar 207 210
 Perforated plate diameter mm 0.7
 Test pressure line 1 680 750 008
 Dimensions:
 Outer diameter. mm 6.0
 x wall thickness mm 2.0
 x length mm 600

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl. 1
 Test pressure bar 25 27
 Prestroke (from BDC) mm 3.95 4.05
 P Prestroke (from BDC) mm 3.90 4.10
 Control-rod travel mm 10.0 11.0
 Cam sequence 1 - 5 - 3 - 6 - 2 - 4
 PC difference °CS 60 each
 tolerance +/-°CS 0.50
 P tolerance +/-°CS 0.75

Min Max
 PC mark Cyl.-No. - 2)
 Pulse wheel position (PC cam) °CS 0 3)
 Tolerance +/-°CS 0.20
 P Tolerance +/-°CS 0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed 1/min 0
 Setting value U/actual V 3.100
 Control-rod travel mm 12.95 13.05
 P Control-rod travel mm 12.90 13.10

Check value

U/actual V 1.700
 Control-rod travel mm 5.90 6.40
 P Control-rod travel mm 5.85 6.45

Stop position

U/actual V mind. 4)
 Control-rod travel mm 0.5 1.0
 P Control-rod travel mm 0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	600	
U/actual	V	2.800	
Fuel			
delivery	cm3/1000str	301.0	303.0
Fuel			
delivery	cm3/1000str	298.0	306.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		11.0

Test point L1

Speed	1/min	250	
U/actual	V	1.340	1.460
Fuel			
delivery	cm3/1000str	29.0	33.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		8.0

REMARKS

VOLVO-No.: 425 515

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 320 RS 8022
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 012

TEST SHEET : VOL
 Edition : 06.93 (2) EN
 Type number : 0 412 826 024
 Type number : 0 421 890 010
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO (LKW 3113)
 Engine: TD 103 E, ES
 Output kW: 210/235
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 078	
Inlet pressure	bar	2.5	2.6
Overflow	l/h	- -	- -
Calibrating nozzle-holder assembly		1 688 901 103	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	3.95 4.05
P Prestroke (from BDC)	mm	3.90 4.10
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No. - 2)		
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10

Check value

U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude	V	0.8 2.0
P pos.amplitude	V	0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

Min Max

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	600	
U/actual	V	2.800	
Fuel			
delivery	cm3/1000str	301.0	303.0
Fuel			
delivery	cm3/1000str	298.0	306.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		11.0

Test point L1

Speed	1/min	250	
U/actual	V	1.340	1.460
Fuel			
delivery	cm3/1000str	20.0	24.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		8.0

REMARKS

VOLVO-No.: 425 515

Dimension "Y"
(Adjustment flange) 15.6 16.1

- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Obsereve notes in remark colum

Test sheet : IVECO
 Date of manufacture :
 Edition : 04.05.1992
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/11E1900R480
 Type No. : 0 460 414 998
 Customer Ident.No. :

Customer-specific details
 Customer : IVECO

Engine : 840.47.2790

Output kW :
 Speed 1/min : 3800

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40
 Calibrating nozzle-
 holder assembly > : 1 688 901 116

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 073

Outer diameter : 6.00
 x wall thickness > : 2.00
 x length > mm : 450

Overflow valve : 2 467 413 006

Test line : KDEP 1865/3
 (fuel-delivery actuator)

Test line : KDEP 1865/6
 (solenoid valve
 start of injection)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 45

Test oil supply
 temperature > °C : 35...40

Hold-up
 revolutions >1/min : 1100
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and.
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

Control-collar travel sensor
 Test temperature :
 15°...70°C
 Connections 2 and 3
 kohms : 1.0...3.0
 Connections 1 and 3
 kohms : 0.5...2.0

Connections 1 and.
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connetions 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 1950
Setting value, bar : 6.6...7.2

Timing device travel:

Speed 1/min : 500
Checkbk. volt
mV : 1952
Setting value, mm : 9.10...9.30

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 1900
Checkbk. volt
mV : 2500
Output
temperature °C : 48
Speed 1/min : 750
Checkbk. volt
mV : 2050
Measuring
temperature °C : 46
Fuel delivery cm³/
> 1000s : 34.3...34.7
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1900
Checkbk. volt
mV : 3500
Supply pump
pressure > bar : 8.5...9.1
> bar :

2st speed 1/min : 150
Checkbk. volt
mV : 2870
Supply pump
pressure > bar : mind.3.8

Timing device variations:

1st speed 1/min : 750
Checkbk. volt. mV : 2050
Timing device
travel mm : 8.9...11.3
> mm : (8.8...11.4)

2nd speed 1/min : 500
Checkbk. volt. mV : 1950
Timing device
travel mm :
> mm : (8.7...9.7)

3rd speed 1/min : 1900
Checkbk. volt. mV : 3500
Timing device
travel mm : 10.9...11.6
> mm : (11.4...13.0)

Solenoid valve

4.th speed 1/min : 900
Checkbk. volt. mV : 1420
Timing device
travel mm : max. 0,3
> mm :

Start of
injection, volts : 12

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 41
Speed 1/min : 1900
Checkbk. volt. mV : 3500
Measuring
temperature °C : 43
Overflow : 40...60
> cm³/10s : (35...65)

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 41
Speed 1/min : 1900
Checkbk. volt mV : 3500
Meßtemperatur °C : 43
Fuel delivery cm³/ : 61.8...64.4
> 1000s : (61.6...64.6)
Dispersion cm³/ : 4.0
> 1000s. :

2nd temperature-conditioning

revolution 1/min : 1900
Checkbk. volt mV : 2500
Output
temperature °C : 45
Speed 1/min : 1185
Checkbk. volt mV : 2170
Measuring
temperature °C : 45
Fuel delivery cm³/ : 29.0...33.0
> 1000s : (28.7...33.3)
Dispersion cm³/ : 2,5
> 1000s : (3.5)

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (37.0...41.0)
Dispersion cm³/ :
> 1000s : (5.0)

4th temperature-conditioning

revolution 1/min : 1900
Checkbk. volt mV : 2500
Output
temperature °C : 45
Speed 1/min : 900
Checkbk. volt mV : 2900
Measuring
temperature °C : 45
Fuel delivery cm³/ : 64.2...67.2
> 1000s : (63.9...67.5)
Dispersion cm³/ : 2.5
> 1000s : (3.5)

Idle delivery:

1st temperature-conditioning

revolution 1/min : 1900
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 400
Checkbk. volt mV : 1670
Meßtemperatur °C : 49
Fuel delivery cm³/ :
> 1000s : (10.5...16.5)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ :
> 1000s : (3.5)

Starting fuel delivery:

1st temperature-conditioning

revolution 1/min : 1900
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 100
Checkbk. volt mV : 2870
Measuring
temperature °C : 49
Fuel delivery cm³/ :
> 1000s : 83.5

Solenoid valve

Start of
injection, volts : 12

Stop test:

Speed 1/min : 1100
Checkbk. volt mV : 3500
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage

min.> volts : 10.0
Rated voltage,
volts : 12.0

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	: 6,2...6,6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : ROW
 Date of manufacture :
 Edition : 01.06.1993
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/11E2000R500
 Type No. : 0 460 414 997
 Customer Ident.No. :

Customer-specific details
 Customer : ROW

Engine : Gemini 3 2.5Tdi
 Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0,30...0,40
 Calibrating nozzle-holder assembly > : 1 688 901 116
 Opening pressure > bar : 207...210
 Test pressure line : 1 680 750 085
 Outer diameter : 6,00
 x wall thickness > : 2,20
 x length > mm : 350

Overflow valve :
 Test line : 0 986 612 437
 (fuel-delivery actuator) : (KDEP 1865/8)
 Test line : 0 986 612 438
 (solenoid valve start of injection) : (KDEP 1865/9)

TEST PRECONDITIONS

Test oil return temp. > °C with thermometer : 55
 Test oil supply temperature > °C : 42...47
 Hold-up revolutions >1/min : 1200
 Feedback voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0,4...1,0
 50°...70°C, ohms : 0,45...1,1

Connections 5 and ground, Mohms min. : 1,0
 Connections 5 and ground, Mohms min. : 1,0
 Connections 3 and 5 Mohms min. : 1,0
 Connections 3 and 7 Mohms min. : 1,0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2 Ohm : 4,9...6,5
 Connections 2 and 3 Ohm : 4,9...6,5
 Connections 1 and 3 Ohm : 9,8...13,0

Connections 1 and ground, Mohms min. : 1,0
 Connections 2 and ground, Mohms min. : 1,0
 Connections 3 and ground, Mohms min. : 1,0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1,2...4,0
 50°...70°C, kohms : 0,3...1,2

Connections 4 and ground, Mohms min. : 1,0
 Connections 7 and ground Mohms min. : 1,0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14,3...17,3
 50°...70°C, ohms : 15,5...21,0

Starting stop mV : 4120...4650
 Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000
Checkbk. volt. : 3500
mV : 3500
Setting value, bar : 6,42...6,8

Timing device travel:

Speed 1/min : 1000
Checkbk. volt : 3500
mV : 3500
Setting value, mm : 8,8...9,2

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt : 2430
mV : 2430
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 53,9...54,3
Dispersion cm³/
> 1000s : 2,5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt : 3500
mV : 3500
Supply pump
pressure > bar : 7,5...8,1
> bar :

2st speed 1/min : 200
Checkbk. volt : 2870
mV : 2870
Supply pump
pressure > bar : 4,7...5,7
> bar :

Timing device variations:

1st speed 1/min : 1000
Checkbk. volt. mV : 3500
Timing device
travel mm :
> mm :

2nd speed 1/min : 2000
Checkbk. volt. mV : 3500
Timing device
travel mm : 11,6...12,8
> mm :

3rd speed 1/min : 1000
Checkbk. volt. mV : 1560
Timing device
travel mm : max. 0,5
> mm :

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 500
Checkbk. volt. mV : 2870
Timing device
travel mm : 6,4...7,4
> mm :

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3500
Measuring
temperature °C : 53
Overflow : 110...165
> cm³/10 :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt mV : 3500
Meßtemperatur °C : 53
Fuel delivery cm³/ : 68,7...70,7
> 1000s :
Dispersion cm³/ : 2,5
> 1000s. :

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 3200
Measuring
temperature °C : 56
Fuel delivery cm³/ : 78,4...81,4
> 1000s :
Dispersion cm³/ : 2,5
> 1000s :

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2430
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s :
Dispersion cm³/ :
> 1000s :

4th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2870
Measuring
temperature °C : 57
Fuel delivery cm³/ : 85,7...88,7
> 1000s :
Dispersion cm³/ : 3,0
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 550
Checkbk. volt mV : 1450
Meßtemperatur °C : 57
Fuel delivery cm³/ : 7,7...11,7
> 1000s :
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 4,0
> 1000s :

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 3130
Measuring
temperature °C : 61
Fuel delivery cm³/ :
> 1000s : 84,8
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 1000
Checkbk. volt mV : 3000
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 5,0

Shutoff solenoid:

Cut-in voltage
min.> volts : 10,0
Rated voltage,
volts : 12,0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions

"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K mm :
KF mm :
SVS max. mm :
FH mm :

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 10.05.1994
 Replaces : 01.06.1993
 Test oil : ISO 4113

Injection pump : VE4/11E2250R510

Type No. : 0 460 404 994
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 028.C

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 006

Test line : KDEP 1865/10
 (fuel-delivery actuator)

Test line : KDEP 1190
 (solenoid valve
 start of injection)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 5 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 3 and 2
 Ohms : 4.9...6.5
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650
 Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 2245
Setting value, bar : 6.2...7.2

Timing device travel:

Speed 1/min : 500
Checkbk. volt
mV : 2245
Setting value, mm : 10.8...11.0

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 38.8...39.2
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 3890
Supply pump
pressure > bar : 8.6...9.6
> bar : ..

2st speed 1/min : 150
Checkbk. volt
mV : 2230
Supply pump
pressure > bar : mind. 3.5
> bar :

Timing device variations:

1st speed 1/min : 300
Checkbk. volt. mV : 2245
Timing device
travel mm :
> mm : (8.9...12.1)

2nd speed 1/min : 2000
Checkbk. volt. mV : 3890
Timing device
travel mm : 11.6...12.8
> mm : (11.4...13.0)

3rd speed 1/min : 1400
Checkbk. volt. mV : 1475
Timing device
travel mm : max. 0.5
> mm : (max. 0.8)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 500
Checkbk. volt. mV : 2245
Timing device
travel mm : 10.8...11.0
> mm : (9.9...11.9)

5.th speed 1/min : 150
Checkbk. volt. mV : 2230
Timing device
travel mm :
> mm : (mind. 1.5)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3890
Measuring
temperature °C : 53
Overflow : 96...150
> cm³/10s : (83...165)

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt mV : 3890
Meßtemperatur °C : 53
Fuel delivery cm³/ : 48.4...51.0
> 1000s : (47.9...51.)
Dispersion cm³/ : 2.5
> 1000s. :

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 2860
Measuring
temperature °C : 56
Fuel delivery cm³/ : 42.1...44.7
> 1000s : (41.9...44.9)
Dispersion cm³/ : 2.5
> 1000s :

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (37.7...40.3)
Dispersion cm³/ :
> 1000s :

4th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2245
Measuring
temperature °C : 57
Fuel delivery cm³/ : 36.9...39.5
> 1000s : (35.9...40,,)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 1600
Meßtemperatur °C : 57
Fuel delivery cm³/ : 11.5...16.5
> 1000s : 11.0...17.0)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 4,0
> 1000s :

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2230
Measuring
temperature °C : 61
Fuel delivery cm³/ :
> 1000s : 30,4
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 750
Checkbk. volt mV : 2480
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 5 M 55 C 320 RS 202
 Regulator : RE 22
 IP-ASSEMBLY: 0 400 195 001

TEST SHEET : MB
 Edition : 11.93 EN
 Type number : 0 410 055 971
 Type number : 0 420 090 002
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: MERCEDES BENZ
 Engine: OM 605
 Vehicle: C 250 D
 Output kW: 83 KW

	Min	Max
=====		
T e s t P R E R E Q U I S I T E S		

Test oil inlet temperature °C	38	42
Overflow valve	1 469 990	351
Inlet pressure bar	0.9	1.1
Overflow 1) l/h	- -	- -
Calibrating nozzle-holder assembly	1 688 901	111
Opening pressure bar	147	150
Perforated plate diameter mm	- -	- -
Test pressure line	1 680 750	014
Dimensions:		
Outer diameter mm	6.0	
x wall thickness mm	2.0	
x length mm	600	

=====

T E S T S P E C I F I C A T I O N S

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC) mm	1.70	1.80
P Prestroke (from BDC) mm	1.65	1.85
Control-rod travel mm	16.0	18.0
Cam sequence	1 - 2 - 4 - 5 - 3	
PC difference °CS	0-72-144-216-288	
tolerance +/-°CS	- -	
P tolerance +/-°CS		1.0

	Min	Max
=====		
PC mark Cyl.-No.	-	
Pulse wheel position (PC cam) °CS	16.5	
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.30

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.45	12.55
P Control-rod travel	mm	12.40	12.60
Check value U/actual	V	1.700	
Control-rod travel	mm	5.25	5.75
P Control-rod travel	mm	5.20	5.80

Stop position

U/actual	V	0.655	0.785
Control-rod travel	mm	1.0	1.0
P Control-rod travel	mm	1.0	1.0

Start position

U/actual	V	4.385	4.615
Control-rod travel	mm	18.2	19.8
P Control-rod travel	mm	18.2	19.8

Continued on next page

=====
 Min Max
 =====

S e c t i o n C -

Injection pump with actuator

- Check values denoted by "p"

 FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1000		
U/actual	V	3.250		
Fuel				
delivery	cm3/1000str	35.0	36.0	
P Fuel				
delivery	cm3/1000str	33.5	37.5	
Dispersion	cm3/1000str		2.5	
P Dispersion	cm3/1000str		3.0	
Speed	1/min	315		
U/actual	V	2.100	2.100	
Fuel				
delivery	cm3/1000str	3.0	9.0	
Dispersion	cm3/1000str		1.0	
P Dispersion	cm3/1000str		1.5	

BOSCH EP TEST VALUES

Please note information given under "Remarks"

Test sheet: Mercedes-Benz
Date of issue: 10.06.1994 EN

Combination no.: 0 402 648 898
Combination no.: 0 402 648 906
Combination no.: 0 402 648 908
Combination no.: 0 402 648 918
Injection pump designation: PE 8 P..LS 7838 and ..LS 7838-10

Combination no.: 0 402 648 893
Combination no.: 0 402 648 894
Combination no.: 0 402 648 895
Combination no.: 0 402 648 914
Combination no.: 0 402 648 915
Injection pump designation: PE 8 P..LS 7835 and ..LS 7835-10

Combination no.: 0 402 648 900
Combination no.: 0 402 648 901
Combination no.: 0 402 648 909
Combination no.: 0 402 648 910
Injection pump designation: PE 8 P..LS 7840 and ..LS 7840-10

Combination no.: 0 402 646 921
Combination no.: 0 402 646 924
Combination no.: 0 402 646 925
Combination no.: 0 402 646 931
Combination no.: 0 402 646 942
Combination no.: 0 402 646 950
Injection pump designation: PE 6 P..LS 7837 and ..LS 7837-10

Combination no.: 0 402 646 917
Combination no.: 0 402 646 926
Combination no.: 0 402 646 929
Combination no.: 0 402 646 922
Combination no.: 0 402 646 954
Combination no.: 0 402 646 930
Injection pump designation: PE 6 P..LS 7834 and ..LS 7834-10

Combination no.: 0 402 646 952
Combination no.: 0 402 646 953
Combination no.: 0 402 646 957
Combination no.: 0 402 646 958
Combination no.: 0 402 646 915
Combination no.: 0 402 646 916
Combination no.: 0 402 646 939
Combination no.: 0 402 646 940
Combination no.: 0 402 646 959
Combination no.: 0 402 646 960
Injection pump designation: PE 6 P..LS 7836 and ..LS 7836-10

...

Testoil-ISO 4113

Combination no.: 0 402 746 913

Combination no.: 0 402 746 916

Combination no.: 0 402 746 919

Injection pump designation: PE 6 P..LS 7237 and ..LS 7237-10

Remarks:

Information on repair and testing is given in the following Service Information:

W 400/.., RQ(V)..PA

Mercedes-Benz series 400 with P pump and two-stage LDA, low output

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 R 120/720 RS 1502
 Regulator: RE 31
 IP-ASSEMBLY: 0 401 496 001

TEST SHEET : 0 401 496 001
 Edition : 12.94 (1) EN
 Type number : 0 411 426 002
 Type number : 0 421 890 200
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO-TRUCK(NKW-3110)
 Engine: TD 163 ES, EJ
 Output kW: 370
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 078	
Inlet pressure	bar	2.4	2.6
Overflow	l/h	- -	- -
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 089	
Dimensions:			
Outer diameter.	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure	ba	30 32
Prestroke (from BDC)	mm	5.35 5.45
P Prestroke (from BDC)	mm	5.30 5.50
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude	V	0.8 2.0
P pos.amplitude	V	0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	550	
U/actual	V	2.950	
Fuel			
delivery	cm3/1000str	389.0	391.0
P Fuel			
delivery	cm3/1000str	386.0	394.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

Test point L1

Speed	1/min	300	
U/actual	V	1.470	1.590
Fuel			
delivery	cm3/1000str	17.0	23.0
Dispersion	cm3/1000str		7.0
P Dispersion	cm3/1000str		11.0

Testoil-ISO 4113

REMARKS

VOLVO-No.: 1 556 156-P03-RELEASED

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Arrangement of pressure-relief valve:
 Pump side 4.1 (previous: pump side 1 rear).
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 R 130/720 RS 1503
 Regulator : RE 31
 IP-ASSEMBLY: 0 401 496 002

TEST SHEET : 0 401 496 002
 Edition : 12.94 (1) EN
 Type number : 0 411 436 001
 Type number : 0 421 890 201
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: IVECO - UNIC
 Engine: 8210.42.5000 (NKW)
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413 025	
Inlet pressure	bar	2.4	2.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 075	
Dimensions:			
Outer diameter.	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	1000	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure bar		25	27
Prestroke (from BDC)	mm	6.95	7.05
P Prestroke (from BDC)	mm	6.90	7.10
Control-rod travel	mm	13.0	14.0
Cam sequence		1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each	
tolerance +/-°CS			0.50
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

Testoil-ISO 4113

	Min	Max
Section C -		
Injection pump with actuator		
- Check values denoted by "P"		
FUEL DELIVERY TEST AND SETTING		
Test point V1		
Speed	1/min	950
U/actual	V	3.218
Fuel delivery	cm3/1000str	278.0 280.0
P Fuel delivery	cm3/1000str	275.0 283.0
Dispersion	cm3/1000str	12.0
P Dispersion	cm3/1000str	16.0
Test point L1		
Speed	1/min	300
U/actual	V	1.250 1.370
Fuel delivery	cm3/1000str	21.0 27.0
Dispersion	cm3/1000str	6.0
P Dispersion	cm3/1000str	10.0
REMARKS		
Dimension "y"	(Adjustment flange)	15.6 16.1
1) = Setting, Start-of-delivery in prestroke according to value in control rod travel 13...14 mm. Then test start-of-delivery difference at other control rod travels:		
Control rod travel:	Start-of-delivery earlier:	
7.9...8.1 mm	0.25...1.75°	
4.9...5.1 mm	1.75 3.75°	
2) = No start-of-delivery mark.		
3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.		
4) = U/actual value min.: U/actual minimum value with deenergized servo magnet and control rod in shutoff position.		

Testoil-ISO 4113

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	950
U/actual	V	3.218
Fuel delivery	cm3/1000str	278.0 280.0
P Fuel delivery	cm3/1000str	275.0 283.0
Dispersion	cm3/1000str	12.0
P Dispersion	cm3/1000str	16.0

Test point L1

Speed	1/min	300
U/actual	V	1.250 1.370
Fuel delivery	cm3/1000str	21.0 27.0
Dispersion	cm3/1000str	6.0
P Dispersion	cm3/1000str	10.0

REMARKS

Dimension "y"	(Adjustment flange)	15.6 16.1
---------------	---------------------	-----------

- 1) = Setting, Start-of-delivery in prestroke according to value in control rod travel 13...14 mm. Then test start-of-delivery difference at other control rod travels:
- | | |
|---------------------|----------------------------|
| Control rod travel: | Start-of-delivery earlier: |
| 7.9...8.1 mm | 0.25...1.75° |
| 4.9...5.1 mm | 1.75 3.75° |
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.: U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PE 6 R 120/720 RS 1504
 Regulator: RE 31
 IP-ASSEMBLY 0 401 496 003

TEST SHEET : 0 401 496 003
 Edition : 12.94 (1) EN
 Type number : 0 411 426 003
 Type number : 0 421 890 200
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: VOLVO-TRUCK (NKW-3059)
 Engine: TD 164
 Output kW: 382
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 078	
Inlet pressure	bar	2.4	2.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 089	
Dimensions:			
Outer diameter.	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure bar		30	32
Prestroke (from BDC)	mm	5.35	5.45
P Prestroke (from BDC)	mm	5.30	5.50
Control-rod travel	mm	10.0	11.0
Cam sequence		1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each	
tolerance +/-°CS			0.50
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.70	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

 FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	525	
U/actual	V	2.950	
Fuel			
delivery	cm3/1000str	389.0	391.0
P Fuel			
delivery	cm3/1000str	386.0	394.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

Test point L1

Speed	1/min	265	
U/actual	V	1.570	1.690
Fuel			
delivery	cm3/1000str	17.0	23.0
Dispersion	cm3/1000str		7.0
P Dispersion	cm3/1000str		11.0

REMARKS

VOLVO-Nr.: 1 556 415-P04-PRELIMIN
 Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Arrangement of pressure-relief valve:
 Pump side 4.1 (previous: pump side 1 rear).
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 720 RS 3184
 Regulator: RE 24
 IP-ASSEMBLY: 0 402 196 703

TEST SHEET : 0 402 196 703
 Edition : 12.94 (1) EN
 Type number : 0 412 026 727
 Type number : 0 421 890 018
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: JOHN DEERE
 Engine: 6076 HRW 30
 Output kW: 181 (LR3 Tractor
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 057	
Inlet pressure	bar	1.4	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 101	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.6	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	3.55 3.65
P Prestroke (from BDC)	mm	3.50 3.70
Control-rod travel	mm	9.0 12.0
Cam sequence 1 - 5	- 3 - 6 - 2 - 4	
PC difference °CS	60 each	
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS 10.5	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to		
Amplitude V		max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1100	
U/actual	V	2.710	
Fuel			
delivery	cm3/1000str	140.0	142.0
P Fuel			
delivery	cm3/1000str	137.0	145.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	425	
U/actual	V	1.340	1.460
Fuel			
delivery	cm3/1000str	18.0	24.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

REMARKS

John Deere-Nr.: RE 57 372

Dimension "Y"
 (Adjustment flange)

- 2) = Port-closing mark 10.5° camshaft after port closing of cylinder 1.
- 3) = Pulse wheel position 10.5° camshaft after port closing of cylinder No. 1.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 H 120/320 LS 4
 Regulator : RE 36
 IP-ASSEMBLY: 0 402 696 031

TEST SHEET : 0 402 696 031
 Edition : 11.94 (2) EN
 Type number : 0 412 626 001
 Type number : 0 421 890 353
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MB
 Engine: OM 441 LA
 Output kW: 250
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature, °C 38 42
 Overflow valve 2 417 413 082
 Inlet pressure bar - - - -
 Overflow 1) 1/h 160 170
 Calibrating nozzle-holder assembly 1 688 901 105
 Opening pressure bar 207 210
 Perforated plate diameter mm - -
 Test pressure line 1 680 750 089
 Dimensions:
 Outer diameter. mm 8.0
 x wall thickness mm 2.5
 x length mm 600

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl. 6
 Test pressure bar 30 32
 Prestroke (from BDC) mm 6.95 7.05
 P Prestroke (from BDC) mm 6.90 7.10
 Control-rod travel mm 10.0 11.0
 Cam sequence 6 - 3 - 5 - 2 - 4 - 1
 PC difference °CS 60 each
 tolerance +/-°CS 0.15
 P tolerance +/-°CS 0.30

	Min	Max
PC mark Cyl.-No. 6 2)		
Nockenscheibe-Position (PC cam) °CS 3)		
Tolerance +/-°CS		- -
P Tolerance +/-°CS		- -

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed 1/min 1050
 U/actual V 3.100

Prestroke magnet -
 Magnet stroke mm 8.0

Fuel
 delivery cm3/1000str 354.0 356.0

P Fuel
 delivery cm3/1000str 351.0 359.0

Dispersion cm3/1000str 5.0

P Dispersion cm3/1000str 9.0

Test point L1

Speed 1/min 300
 U/actual V 1.440 1.560

Prestroke magnet -
 Magnet stroke mm 8.0

Fuel
 delivery cm3/1000str 22.0 28.0

Dispersion cm3/1000str 8.0

P Dispersion cm3/1000str 12.0

Testoil-ISO 4113

REMARKS

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = Start-of-delivery incipient fissure on FB cyl. 6.
 Tolerance +/- 0.10° NW.
- 3) = Setting of cam disk position:
 omitted.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY

Pump : PE 6 H 120/320 LS 4-1
 Regulator : RE 36
 IP-ASSEMBLY: 0 402 696 032

TEST SHEET : 0 402 696 032
 Edition : 11.94 (1) EN
 Type number : 0 412 626 002
 Type number : 0 421 890 353
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MB
 Engine: OM 441 LA
 Vehicle: 250
 Output kW:

Min Max

Test PREREQUISITES

Test oil inlet temperature °C 38 42
 Overflow valve 2 417 413 082
 Inlet pressure bar 3.4 3.6
 Overflow 1) 1/h - - - -
 Calibrating nozzle-holder assembly 1 688 901 105
 Opening pressure bar 207 210
 Perforated plate diameter mm - - - -
 Test pressure line 1 680 750 089
 Dimensions:
 Outer diameter mm 8.0
 x wall thickness mm 2.5
 x length mm 600

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl. 6
 Test pressure bar 30 32
 Prestroke (from BDC) mm 6.95 7.05
 P Prestroke (from BDC) mm 6.90 7.10
 Control-rod travel mm 10.0 11.0
 Cam sequence 6-3-5-2-4-1
 PC difference °CS 60 each
 tolerance +/-°CS 0.15
 P tolerance +/-°CS 0.30

Min Max

PC mark Cyl.-No. 6 2)
 Pulse wheel position (PC cam) °CS 3)
 Tolerance +/-°CS 0.20
 P Tolerance +/-°CS 0.30

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed 1/min 0
 Setting value U/actual V 3.100
 Control-rod travel mm 12.95 13.05
 P Control-rod travel mm 12.90 13.10
 Check value U/actual V 1.700
 Control-rod travel mm 5.90 6.40
 P Control-rod travel mm 5.85 6.45
 Stop position U/actual V mind. 4)
 Control-rod travel mm 0.5 1.0
 P Control-rod travel mm 0.4 1.1

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	750	
U/actual	V	3.000	
Prestroke magnet -			
Magnet stroke	mm	7.0	
Fuel			
delivery	cm3/1000str	374.0	376.0
Fuel			
delivery	cm3/1000str	371.0	379.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Speed	1/min	300	
U/actual	V	1.440	1.560
Prestroke magnet -			
Magnet stroke	mm	8.0	
Fuel			
delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Testoil-ISO 4113

REMARKS

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Setting of overflow volume at full load omitted
- 2) = Start-of-delivery incipient fissure on FB cyl. 6.
Tolerance +/- 0.10° NW.
- 3) = Setting of cam disk position: omitted.
- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 H 120/320 LS 4-2
 Regulator : RE 36
 IP-ASSEMBLY: 0 402 696 033

TEST SHEET : 0 402 696 033
 Edition : 11.94 (1) EN
 Type number : 0 412 626 003
 Type number : 0 421 890 353
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MB
 Engine: OM 441 LA
 Output kW: 250
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 082	
Inlet pressure	bar	3.4	3.6
Overflow 1)	l/h	- -	- -
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	- -	
Test pressure line		1 680 750 089	
Dimensions:			
Outer diameter	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	6	
Test pressure bar	30	32
Prestroke (from BDC)	mm	6.95 7.05
P Prestroke (from BDC)	mm	6.90 7.10
Control-rod travel	mm	10.0 11.0
Cam sequence	6 - 3 - 5 - 2 - 4 - 1	
PC difference	°CS	60 each
tolerance +/-°CS		0.15
P tolerance +/-°CS		0.30

Min Max

PC mark Cyl.-No. 6 2)
 Nockenscheibe-Position (PC cam) °CS 3)
 Tolerance +/-°CS - -
 P Tolerance +/-°CS - -

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

Continued on next page

Testoil-ISO 4113

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	750	
U/actual	V	3.000	
Prestroke magnet	-		
Magnet stroke	mm	7.0	
Fuel			
delivery	cm3/1000str	374.0	376.0
P Fuel			
delivery	cm3/1000str	371.0	379.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9,0
Speed	1/min	300	
U/actual	V	1.440	1.560
Prestroke magnet	-		
Magnet stroke	mm	8.0	
Fuel			
delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Testoil-ISO 4113

REMARKS

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Setting of overflow volume:
omitted.
- 2) = Start-of-delivery incipient
fissure on FB cyl. 6.
Tolerance +/- 0.10° NW.
- 3) = Setting of cam disk position:
omitted.
- 4) = U/actual value min:
U/actual minimum value with
deenergized servo magnet and
control rod in shutoff
position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 720 RS 7211
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 696 801

TEST SHEET : 0 402 696 801
 Edition : 12.94 (5) EN
 Type number : 0 412 626 838
 Type number : 0 421 890 009
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: SCANIA
 Engine: DTC 1102, DSE 1170
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413 025	
Inlet pressure	bar	2.4	2.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 104	
Opening pressure	bar	250	253
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure	bar	25	27
Prestroke (from BDC)	mm	5.00	5.10
P Prestroke (from BDC)	mm	4.95	5.15
Control-rod travel	mm	10.0	11.0
Cam sequence		1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each	
tolerance +/-°CS			0.30
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No. 1 2)		
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value			
U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference
 Amplitude to Amplitude V max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
(Observe "Remarks" Point 5), 6))

Test point V1

Speed	1/min	700	
U/actual	V	3.000	
Fuel delivery	cm3/1000str	247.0	249.0
P Fuel delivery	cm3/1000str	244.0	252.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Test point L1

Speed	1/min	250	
U/actual	V	1,350	1,470
Fuel delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		4.0
P Dispersion	cm3/1000str		8.0

Testoil-ISO 4113

REMARKS

SCANIA-No.: 1 328 037

Dimension "Y"
(Adjustment flange) 15.6 16.1
(If provided;
adjustment flange was
introduced in the course
of series production).

- 1) = Arrangement of pressure-relief valve:
Pump side 4.2 (previous: pump side 2 rear).
- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.

REMARKS (Continued)

- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.
- 5) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm:
Pump page 3.2
(previous: pump side 2).
- 6) = Delivery-valve holder:
* Valve spring
pre-tension: mm 3.2 3.4
* Allowed
variation: mm 3.0 3.5
* Required setting
for new delivery-valve holders due
to flattening: mm 2.9 3.1

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 320 RS 7874
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 696 802

TEST SHEET : 0 402 696 802
 Edition : 12.94 (1) EN
 Type number : 0 412 626 913
 Type number : 0 421 890 020
 CUSTOMER IDENT. NO.:

Testoil-ISO 4113

Customer-specific details
 Customer: Mercedes Benz
 Engine: OM 401 LA (Krupp crane)
 Output kW: 230
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature °C	38	42
Overflow valve	1 417 413 025	
Inlet pressure bar	1.4	1.6
Overflow 1) l/h	- -	- -
Calibrating nozzle-holder assembly	1 688 901 105	
Opening pressure bar	207	210
Perforated plate diameter mm	0.8	
Test pressure line	1 680 750 075	
Dimensions:		
Outer diameter mm	8.0	
x wall thickness mm	2.5	
x length mm	1000	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	6	
Test pressure bar	25	27
Prestroke (from BDC) mm	5.20	5.30
P Prestroke (from BDC) mm	4.15	4.35
Control-rod travel mm	20.0	21.0
Cam sequence	6 - 3 - 5 - 2 - 4 - 1	
PC difference °CS	60 each	
tolerance +/-°CS		0.30
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	6	2)
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U'actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value			
U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value			
U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	5)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference
 Amplitude to
 Amplitude V max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AT TING

Test point V1

Speed	1/min	700	
U/actual	V	3.100	
Fuel			
delivery	cm3/1000str	229.0	231.0
P Fuel			
delivery	cm3/1000str	226.0	234.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0
Speed	1/min	350	
U/actual	V	1.375	1.495
Fuel			
delivery	cm3/1000str	10.0	16.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

Testoil-ISO 4113

REMARKS

Mercedes Benz-Nr.: 0 250 743 602

Dimension "Y"
 (Adjustment flange) 15.6 16.1
 (If provided;
 adjustment flange was
 introduced in the course
 of series production).

- 2) = Start-of-delivery invipient fissure on FB cyl. 6.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 6.
- 4) = U/actual value min:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PE 8 H 120/320 LS 3
 Regulator: RE 36
 IP-ASSEMBLY: 0 402 698 031

TEST SHEET : 0 402 698 031
 Edition : 11.94 (2) EN
 Type number : 0 412 628 001
 Type number : 0 421 890 353
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MB
 Engine: OM 442 LA
 Output kW: 370
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413	082
Inlet pressure	bar	3.4	3.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901	105
Opening pressure	bar	207	210
Perforated plate diameter	mm	-	-
Test pressure line		1 680 750	089
Dimensions:			
Outer diameter.	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		8	
Test pressure bar		30	32
Prestroke (from BDC)	mm	6.95	7.05
P Prestroke (from BDC)	mm	6.90	7.10
Control-rod travel	mm	10.0	11.0
Cam sequence		8-7-2-6-3-5-4-1	
PC difference	°CS	45 each	
	tolerance +/-°CS		0.15
P	tolerance +/-°CS		0.30

Min Max

PC mark	Cyl.-No.	8	2)
Nockenscheibe-Position (PC cam)	°CS		3)
Tolerance +/-°CS		-	-
P Tolerance +/-°CS		-	-

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value			
U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position			
U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	750	
U/actual	V	2.800	
Prestroke magnet -			
Magnet stroke mm		7.4	
Fuel			
delivery	cm3/1000str	340.0	342.0
P Fuel			
delivery	cm3/1000str	337.0	345.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	300	
U/actual	V	1.440	1.560
Prestroke magnet -			
Magnet stroke mm		8.0	
Fuel			
delivery	cm3/1000str	20.0	26.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Testoil-ISO 4113

REMARKS

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Setting of overflow volume:
omitted.
- 2) = Start-of-delivery incipient
fissure on FB cyl. 8.
Tolerance +/- 0.10° NW.
- 3) = Setting of cam disk position:
omitted.
- 4) = U/actual value min.:
U/actual minimum value with
deenergized servo magnet and
control rod in shutoff
position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PE 8 H 120/320 LS 3-1
 Regulator: RE 36
 IP-ASSEMBLY 0 402 698 032

TEST SHEET : 0 402 698 032
 Edition : 11.94 (1) EN
 Type number : 0 412 628 002
 Type number : 0 421 890 353
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MB
 Engine: OM 442 LA
 Output kW:
 at 1/min:

	Min	Max

Test PREREQUISITES

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 082	
Inlet pressure bar	3.4	3.6

Overflow 1) 1/h	-	-
-----------------	---	---

Calibrating nozzle-holder assembly	1 688 901 105	
------------------------------------	---------------	--

Opening pressure bar	207	210
----------------------	-----	-----

Perforated plate diameter mm	-	-
------------------------------	---	---

Test pressure line	1 680 750 089	
--------------------	---------------	--

Dimensions:

Outer diameter mm	8.0	
x wall thickness mm	2.5	
x length mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	8	
Test pressure bar	30	32
Prestroke (from BDC) mm	6.95	7.05
P Prestroke (from BDC) mm	6.90	7.10
Control-rod travel mm	10.0	11.0
Cam sequence	8-7-2-6-3-5-4-1	
PC difference °CS	45 each	
tolerance +/-°CS		0.15
P tolerance +/-°CS		0.30

	Min	Max
PC mark Cyl.-No. 8 2)		
Nockenscheibe-Position (PC cam) °CS		3)
Tolerance +/-°CS		- -
P Tolerance +/-°CS		- -

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed 1/min	0	
Setting value U/actual	V	3.100
Control-rod travel mm	12.95	13.05
P Control-rod travel mm	12.90	13.10
Check value U/actual	V	1.700
Control-rod travel mm	5.90	6.40
P Control-rod travel mm	5.85	6.45
Stop position U/actual	V	mind. 4)
Control-rod travel mm	0.5	1.0
P Control-rod travel mm	0.4	1.1

Continued on next page

Testoil-ISO 4113

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed 1/min 750
 U/actual V 2.800
 Prestroke magnet -
 Magnet stroke mm 7.4

Fuel
 delivery cm3/1000str 340.0 342.0
 P Fuel
 delivery cm3/1000str 337.0 345.0
 Dispersion cm3/1000str 5.0
 P Dispersion cm3/1000str 9.0

Test point L1

Speed 1/min 300
 U/actual V 1.440 1.560
 Prestroke magnet -
 Magnet stroke mm 8.0

Fuel
 delivery cm3/1000str 20.0 26.0
 Dispersion cm3/1000str 8.0
 P Dispersion cm3/1000str 12.0

Testoil-ISO 4113

REMARKS

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Setting of overflow volume:
 omitted.
- 2) = Start-of-delivery incipient
 fissure on FB cyl. 6.
 Tolerance +/- 0.10° NW.
- 3) = Setting of cam disk position:
 omitted.
- 4) = U/actual value min.:
 U/actual minimum value with
 deenergized servo magnet and
 control rod in shutoff
 position.

BOSCH TEST SPECS. IP ASSEMBLY

Pump: PE 8 H 120/320 LS 3-2
 Regulator: RE 36
 IP-ASSEMBLY: 0 402 698 033

TEST SHEET : 0 402 698 033
 Edition : 11.94 (2) EN
 Type number : 0 412 628 003
 Type number : 0 421 890 353
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: MB
 Engine: OM 442 LA
 Output kW: - -
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature °C 38 42
 Overflow valve 2 417 413 082
 Inlet pressure bar 3.4 3.6
 Overflow 1) 1/h - - - -
 Calibrating nozzle-holder assembly 1 688 901 1051
 Opening pressure bar 207 210
 Perforated plate diameter mm - -
 Test pressure line 1 680 750 089
 Dimensions:
 Outer diameter. mm 8.0
 x wall thickness mm 2.5
 x length mm 600

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl. 8
 Test pressure bar 30 32
 Prestroke (from BDC) mm 6.95 7.05
 P Prestroke (from BDC) mm 6.90 7.10
 Control-rod travel mm 10.0 11.0
 Cam sequence 8-7-2-6-3-5-4-1
 PC difference °CS 45 each
 tolerance +/-°CS 0.15
 P tolerance +/-°CS 0.30

Min Max
 PC mark Cyl.-No. 8 2)
 Nockenscheibe-Position
 (PC cam) °CS - - 3)
 Tolerance +/-°CS - -
 P Tolerance +/-°CS - -

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed 1/min 0
 Setting value
 U/actual V 3.100
 Control-rod travel mm 12.95 13.05
 P Control-rod travel mm 12.90 13.10

Check value

U/actual V 1.700
 Control-rod travel mm 5.90 6.40
 P Control-rod travel mm 5.85 6.45

Stop position

U/actual V mind. 4)
 Control-rod travel mm 0.5 1.0
 P Control-rod travel mm 0.4 1.1

Continued on next page

=====
 Min Max
 =====

S e c t i o n C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	750	
U/actual	V	2.800	
Prestroke magnet -			
Magnet stroke mm		7.4	
Fuel			
delivery	cm3/1000str	340.0	342.0
P Fuel			
delivery	cm3/1000str	337.0	345.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	300	
U/actual	V	1.440	1.560
Prestroke magnet -			
Magnet stroke mm		8.0	
Fuel			
delivery	cm3/1000str	20.0	26.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Setting of overflow volume:
omitted.
- 2) = Start-of-delivery incipient
fissure on FB cyl. 8.
Tolerance +/- 0.10° NW.
- 3) = Setting of cam disk position:
omitted.
- 4) = U/actual value min:
U/actual minimum value with
deenergized servo magnet and
control rod in shutoff
position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PE 8 P 120 A 920/4 LS 7149
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 698 802

TEST SHEET : 0 402 698 802
 Edition : 12.94 (7) EN
 Type number : 0 412 628 826
 Type number : 0 421 890 007
 CUSTOMER IDENT. NO.:

Testoil-ISO 4113

Customer-specific details
 Customer: SCANIA
 Engine: DSC 1404
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413 025	
Inlet pressure	bar	1.4	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 019	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure bar		25	27
Prestroke (from BDC)	mm	5.00	5.10
P Prestroke (from BDC)	mm	4.95	5.15
Control-rod travel	mm	9.0	12.0
Cam sequence		1-2-7-3-4-5-6-8	
PC difference	°CS	45 each	
tolerance +/-°CS			0.30
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
(Observe "Remarks" Point 5), (6))

Test point V1

Speed	1/min	700	
U/actual	V	3.180	
Fuel delivery	cm3/1000str	226.0	228.0
P Fuel delivery	cm3/1000str	223.0	231.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	250	
U/actual	V	1.540	1.660
Fuel delivery	cm3/1000str	15.0	21.0
Dispersion	cm3/1000str		3.0
P Dispersion	cm3/1000str		6.0

REMARKS

SCANIA No.: 397 567

Dimension "Y"
(Adjustment flange) 15.6 16.1
(If provided;
adjustment flange was
introduced in the course
of series production)

- 1) = Arrangement of pressure-relief valve:
Pump side 4.2 (previous: pump side 2 rear).
- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.

REMARKS (Continued)

- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.
- 5) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm:
Pump page 3.2
(previous: pump side 2).
- 6) = Delivery-valve holder:
* Valve spring pre-tension: mm 3.2 3.4
* Allowed variation: mm 3.0 3.5
* Required setting for new delivery-valve holders due to flattening: mm 2.9 3.1

Testoil-ISO 4113

=====
Min Max
=====

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 8 P 120 A 920/4 LS 7205
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 698 804

TEST SHEET : 0 402 698 804
 Edition : 12.94 (6) EN
 Type number : 0 412 628 845
 Type number : 0 421 890 007
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: SCANIA
 Engine: DSC 1409, DSC 1416
 Output kW:
 at 1/min:

	Min	Max
=====		
T e s t P R E R E Q U I S I T E S		
=====		

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413	025
Inlet pressure	bar	2.4	2.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901	104
Opening pressure	bar	250	253
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750	008
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

Testoil-ISO 4113

=====

T E S T S P E C I F I C A T I O N S

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure bar		25	27
Prestroke (from BDC)	mm	5.00	5.10
P Prestroke (from BDC)	mm	4.95	5.15
Control-rod travel	mm	10.0	11.0
Cam sequence		1-2-7-3-4-5-6-8	
PC difference tolerance +/-°CS		45 each	0.50
P tolerance +/-°CS			0.75

	Min	Max
=====		
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60	
pos.amplitude V		0.8	2.0
P pos.amplitude V		0.6	3.0
Speed	1/min	600	
Difference Amplitude to Amplitude	V	max.	1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
(Observe "Remarks" Point 5), 6))

Test point V1

Speed	1/min	700
U/actual	V	3.000
Fuel delivery	cm3/1000str	247.0 249.0

P Fuel delivery	cm3/1000str	244.0 252.0
Dispersion	cm3/1000str	8.0
P Dispersion	cm3/1000str	12.0

Test point L1

Speed	1/min	250
U/actual	V	1.350 1.470

Fuel delivery	cm3/1000str	13.0 19.0
Dispersion	cm3/1000str	4.0
P Dispersion	cm3/1000str	8.0

REMARKS

SCANIA-No.: 1 328 039

Dimension "Y"
(Adjustment flange) 15.6 16.1
(If provided;
adjustment flange was
introduced in the course
of series production)

- 1) = Arrangement of pressure-relief valve:
Pump side 4.2 (previous: pump side 2 rear).
- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.

REMARKS (Continued)

- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.
- 5) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm: Pump page 3.2 (previous: pump side 2).
- 6) = Pressure valve holder:
Setting of valve spring pretensioning omitted.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY

Pump : PE 8 P 120 A 920/4 LS 7205
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 698 805

TEST SHEET : 0 402 698 805
 Edition : 12.94 (1) EN
 Type number : 0 412 628 845
 Type number : 0 421 890 019
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: SCANIA
 Engine: DSC 1409, DSC 1416
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413 025	
Inlet pressure	bar	2.4	2.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 104	
Opening pressure	bar	250	253
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure bar		25	27
Prestroke (from BDC)	mm	5.00	5.10
P Prestroke (from BDC)	mm	4.95	5.15
Control-rod travel	mm	10.0	11.0
Cam sequence		1-2-7-3-4-5-6-8	
PC difference	°CS	45 each	
	tolerance +/-°CS		0.45
P	tolerance +/-°CS		0.75

	Min	Max
--	-----	-----

PC mark	Cyl.-No.	1 2)	
Pulse wheel position (PC cam)	°CS	0 3)	
Tolerance +/-°CS			0.20
P Tolerance +/-°CS			0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

(On our copy, revolution norm at test point L1 is missing).

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
 (Observe "Remarks" Point 5), 6))

Test point V1

Speed	1/min	700	
U/actual	V	3.000	
Fuel delivery	cm3/1000str	247.0	249.0
P Fuel delivery	cm3/1000str	244.0	252.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Test point L1

Speed	1/min	250	
U/actual	V	1,350	1,470
Fuel delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		4.0
P Dispersion	cm3/1000str		8.0

Testoil-ISO 4113

REMARKS

SCANIA-No.: 1 361 306

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Arrangement of pressure-relief valve:
 Pump side 4.2 (previous: pump side 2 rear).
- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.

REMARKS (Continued)

- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.
- 5) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm:
 Pump page 3.2
 (previous: pump side 2).
- 6) = Pressure valve holder:
 Setting of valve spring pretensioning omitted.

1W8

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PE 8 P 120 A 920/4 LS 7331
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 698 806

TEST SHEET : 0 402 698 806
 Edition : 12.94 (1) EN
 Type number : 0 412 628 884
 Type number : 0 421 890 022
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: SCANIA
 Engine: DSC 1409, DSC 1416
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413 025	
Inlet pressure	bar	2.4	2.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 104	
Opening pressure	bar	250	253
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure	bar	25	27
Prestroke (from BDC)	mm	5.00	5.10
P Prestroke (from BDC)	mm	4.95	5.15
Control-rod travel	mm	10.0	11.0
Cam sequence		1-2-7-3-4-5-6-8	
PC difference	°CS	45 each	
tolerance +/-°CS			0.50
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10

Check value

U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference
 Amplitude to Amplitude V max. 1.4

Continued on next page

Testoil-ISO 4113

	Min	Max
--	-----	-----

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator
 - Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
 (Observe "Remarks" Point 5), 6))

Test point V1

Speed	1/min	700	
U/actual	V	3.000	
Fuel delivery	cm3/1000str	247.0	249.0
P Fuel delivery	cm3/1000str	244.0	252.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Test point L1

Speed	1/min	250	
U/actual	V	1.350	1.470
Fuel delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		4.0
P Dispersion	cm3/1000str		8.0

Testoil-ISO 4113

REMARKS

SCANIA No.: 1 362 097

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Arrangement of pressure-relief valve:
 Pump side 4.2 (previous: pump side 2 rear).
- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

REMARKS (Continued)

- 5) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm:
 Pump page 3.2
 (previous: pump side 2).
- 6) = Pressure valve holder:
 Setting of valve spring pretensioning omitted.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 5 H 120/720/3 LS 1002
 Regulator : RE 33
 IP-ASSEMBLY: 0 402 795 201

TEST SHEET : 0 402 795 201
 Edition : 10.94 (1) EN
 Type number : 0 412 725 201
 Type number : 0 421 890 354
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MAN
 Engine: D 2865 LF 09
 Output kW: - -
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 082	
Inlet pressure	bar	- -	- -
Overflow 1)	l/h	160	170
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	- -	
Test pressure line		1 680 750 089	
Dimensions:			
Outer diameter.	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	5	
Test pressure bar	30	32
Prestroke (from BDC)	mm	9.94 10.04
P Prestroke (from BDC)	mm	9.89 10.09
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 3 - 5 - 4 - 2	
PC difference	°CS	72 each
tolerance +/-°CS		0.15
P tolerance +/-°CS		0.30

Min Max

PC mark	Cyl.-No. - 2)		
Nockenscheibe-Position (PC cam)	°CS	0 3)	
Tolerance +/-°CS		0	0.10
P Tolerance +/-°CS			- -

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10

Check value

U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

Continued on next page

	Min	Max	Min	Max
--	-----	-----	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	750		
U/actual	V	3.350		
Prestroke magnet -				
Magnet stroke	mm	10.0		
Fuel				
delivery	cm3/1000str	331.0	333.0	
P Fuel				
delivery	cm3/1000str	328.0	336.0	
Dispersion	cm3/1000str		5.0	
P Dispersion	cm3/1000str		9.0	

Test point L1

Speed	1/min	300		
U/actual	V	1.460	1.580	
Prestroke magnet -				
Magnet stroke	mm	7.2		
Fuel				
delivery	cm3/1000str	27.0	33.0	
Dispersion	cm3/1000str		8.0	
P Dispersion	cm3/1000str		12.0	

Testoil-ISO 4113

REMARKS

Dimension "Y"
(Adjustment flange) 15.6 16.1

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = No start-of-delivery mark.
- 3) = Setting of cam disk position: on FB cyl. 5.
- 4) = U/actual value min:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

Pump : PES 6 H 120/720 LS 7
 Regulator: RE 36
 IP-ASSEMBLY 0 402 796 033

TEST SHEET : 0 402 796 033
 Edition : 11.94 (2) EN
 Type number : 0 412 726 004
 Type number : 0 421 890 356
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MB
 Engine: OM 447 LA
 Output kW: - -
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 082	
Inlet pressure	bar	3.4	3.6
Overflow 1)	l/h	- -	- -
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	- -	
Test pressure line		1 680 750 089	
Dimensions:			
Outer diameter.	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING 2)

PC setting cyl.		6	
Test pressure bar		30	32
Prestroke (from BDC)	mm	6.95	7.05
P Prestroke (from BDC)	mm	6.90	7.10
Control-rod travel	mm	10.0	11.0
Cam sequence		6 - 2 - 4 - 1 - 5 - 3	
PC difference	°CS	60 each	
tolerance +/-°CS			0.15
P tolerance +/-°CS			0.30

	Min	Max
--	-----	-----

PC mark	Cyl.-No.	6	2)
Cam disk position (PC cam)	°CS	- -	3)
Tolerance +/-°CS			- -
P Tolerance +/-°CS			- -

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

 FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	800	
U/actual	V	2.650	
Prestroke magnet -			
Magnet stroke	mm	9.0	
Fuel			
delivery	cm3/1000str	301.0	303.0
P Fuel			
delivery	cm3/1000str	298.0	306.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	300	
U/actual	V	1.380	1.500
Prestroke magnet -			
Magnet stroke	mm	9.0	
Fuel			
delivery	cm3/1000str	22.0	28.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Testoil-ISO 4113

 REMARKS

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Setting of overflow volume:
 omitted.
- 2) = Start-of-delivery incipient
 fissure on FB cyl. 6.
 Tolerance +/- 0.30° NW.
- 3) = Setting of cam disk position:
 omitted.
- 4) = U/actual value min.:
 U/actual minimum value with
 deenergized servo magnet and
 control rod in shutoff
 position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 H 120/320 RS 8
 Regulator: RE 36
 IP-ASSEMBLY: 0 402 796 034

TEST SHEET : 0 402 796 034
 Edition : 11.94 (1) EN
 Type number : 0 412 726 005
 Type number : 0 421 890 355
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MAN
 Engine: D 0826 LUH 11
 Output kW: 162
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature °C 38 42
 Overflow valve 2 417 413 082
 Inlet pressure bar 3.4 3.6
 Overflow 1/h - -
 Calibrating nozzle-holder assembly 1 688 901 105
 Opening pressure bar 207 210
 Perforated plate diameter mm - -
 Test pressure line 1 680 750 089
 Dimensions:
 Outer diameter. mm 8.0
 x wall thickness mm 2.5
 x length mm 600

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl. 1
 Test pressure bar 30 32
 Prestroke (from BDC) mm 7.95 8.05
 P Prestroke (from BDC) mm 7.90 8.10
 Control-rod travel mm 10.0 11.0
 Cam sequence 1 - 5 - 3 - 6 - 2 - 4
 PC difference °CS 60 each
 tolerance +/-°CS 0.15
 P tolerance +/-°CS 0.30

Min Max

PC mark Cyl.-No. 1 2)
 Cam disk position (PC cam) °CS 0 3)
 Tolerance +/-°CS - -
 P Tolerance +/-°CS - -

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed 1/min 0
 Setting value U/actual V 3.100
 Control-rod travel mm 12.95 13.05
 P Control-rod travel mm 12.90 13.10
 Check value U/actual V 1.700
 Control-rod travel mm 5.90 6.40
 P Control-rod travel mm 5.85 6.45

Stop position

U/actual V mind. 4)
 Control-rod travel mm 0.5 1.0
 P Control-rod travel mm 0.4 1.1

Continued on next page

	Min	Max	Min	Max
--	-----	-----	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1200		
U/actual	V	2.540		
Prestroke magnet -				
Magnet stroke mm		10.3		
Fuel				
delivery	cm3/1000str	208.0	210.0	
P Fuel				
delivery	cm3/1000str	205.0	213.0	
Dispersion	cm3/1000str		5.0	
P Dispersion	cm3/1000str		9.0	

Testoil-ISO 4113

Test point L1

Speed	1/min	300		
U/actual	V	1,380	1,500	
Prestroke magnet -				
Magnet stroke mm		8.8		
Fuel				
delivery	cm3/1000str	12.0	18.0	
Dispersion	cm3/1000str		8.0	
P Dispersion	cm3/1000str		12.0	

REMARKS

Dimension "Y"
(Adjustment flange) 15.6 16.1

- 1) = Setting of overflow volume:
omitted.
- 2) = Start-of-delivery incipient
fissure on FB cyl. 1.
Tolerance +/- 0.10° NW.
- 3) = Setting of cam disk position:
omitted.
- 4) = U/actual value min.:
U/actual minimum value with
deenergized servo magnet and
control rod in shutoff
position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 H 120/720/3 LS 1001
 Regulator: RE 33
 IP-ASSEMBLY: 0 402 796 201

TEST SHEET : 0 402 796 201
 Edition : 11.94 (2) EN
 Type number : 0 412 726 201
 Type number : 0 421 890 354
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MAN
 Engine: D 2866 LF 14
 Output kW:
 at 1/min:

	Min	Max

Test PREREQUISITES

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 082	
Inlet pressure bar	- -	- -
Overflow 1) 1/h	160	170
Calibrating nozzle-holder assembly	1 688 901 105	
Opening pressure bar	207	210
Perforated plate diameter mm	- -	
Test pressure line	1 680 750 089	
Dimensions:		
Outer diameter. mm	8.0	
x wall thickness mm	2.5	
x length mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "p"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	6	
Test pressure bar	30	32
Prestroke (from BDC) mm	9.94	10.04
P Prestroke (from BDC) mm	9.89	10.09
Control-rod travel mm	10.0	11.0
Cam sequence	6-2-4-1-5-3	
PC difference °CS	60 each	
tolerance +/-°CS		0.15
P tolerance +/-°CS		0.30

	Min	Max

PC mark Cyl.-No.	-	2)	
Pulse wheel position (PC cam) °CS	0	3)	
Tolerance +/-°CS			0.10
P Tolerance +/-°CS			- -

Section B -

Actuator test
 - Check values denoted by "p"
 - Assembly warm-up time: 3 mins. at n = 600 1/min Control-rod ca. 10 mm

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel mm		12.95	13.05
P Control-rod travel mm		12.90	13.10

Check value

U/actual Control-rod travel mm	V	1.700	
P Control-rod travel mm		5.90	6.40
P Control-rod travel mm		5.85	6.45

Stop position

U/actual Control-rod travel mm	V	mind.	4)
P Control-rod travel mm		0.5	1.0
P Control-rod travel mm		0.4	1.1

Continued on next page

Testoil-ISO 4113

	Min	Max
--	-----	-----

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
(Observe "Remarks" Point 5))

Test point V1

Speed	1/min	750
U/actual	V	3.350

Prestroke magnet -
Magnet stroke mm 10.0

Fuel delivery	cm3/1000str	331.0	333.0
P Fuel delivery	cm3/1000str	328.0	336.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	300
U/actual	V	1.460 1.580

Prestroke magnet -
Magnet stroke mm 7.2

Fuel delivery	cm3/1000str	27.0	33.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Testoil-ISO 4113

REMARKS

Dimension "Y"
(Adjustment flange) 15.6 16.1

- 1) = Setting of overflow at full load (refer to measurement point V1).
- 2) = No start-of-delivery mark.
- 3) = Setting of cam disk position: omitted: on FB cyl. 6.
- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 7240
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 796 806

TEST SHEET : 0 402 796 806
 Edition : 12.94 (3) EN
 Type number : 0 412 726 855
 Type number : 0 421 890 013
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: IVECO - UNIC
 Engine: 8460.41.5020
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 025	
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 105	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.8	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	5.10 5.20
P Prestroke (from BDC)	mm	5.05 5.25
Control-rod travel	mm	9.0 12.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value		
U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45
Stop position		
U/actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

Testoil-ISO 4113

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1050	
U/actual	V	2.900	
Fuel			
delivery	cm3/1000str	235.0	237.0
P Fuel			
delivery	cm3/1000str	232.0	240.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	275	
U/actual	V	1.520	1.640
Fuel			
delivery	cm3/1000str	32.0	38.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

REMARKS

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 720 RS 7259
 Regulator: RE 30
 IP-ASSEMBLY 0 402 796 809

TEST SHEET: DEE
 Edition: 06.93 (1) EN
 Type number: 0 412 726 863
 Type number: 0 421 890 014
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: JOHN DEERE
 Engine: 6101 HRW 11
 Output kW: 233
 at 1/min: 2100

	Min	Max
Test PREREQUISITES		

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413 077	
Inlet pressure	bar	1.5	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 103	
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 015	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	1.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING 1)

PC setting cyl.		1	
Test pressure	bar	25	27
Prestroke (from BDC)	mm	3.55	3.65
P Prestroke (from BDC)	mm	3.50	3.70
Control-rod travel	mm	9.00	12.0
Cam sequence		1 - 5 - 3 - 6 - 2 - 4	
PC difference tolerance +/-°CS		60 each	0.50
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	-	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed		1/min	0
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.70	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1050	
U/actual	V	2.840	
Fuel			
delivery	cm3/1000str	212.0	214.0
P Fuel			
delivery	cm3/1000str	210.0	216.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	250	
U/actual	V	1.530	1.650
Fuel			
delivery	cm3/1000str	23.0	29.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

REMARKS

JOHN DEERE : RE 42 302

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = Flow begin-incipient fissure
 8.75 degrees NW after flow
 begin cylinder 1.
 Incipient fissure over clutch
 and indicator.
 Incipient fissure measured at
 62...68 degrees to vertical
 axis of pump.
- 3) = Setting of pulse-wheel
 position at flow begin
- 4) = U/actual value min:
 U/actual minimum value with
 deenergized servo magnet and
 control rod in shutoff
 position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 7315
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 796 812

TEST SHEET : 0 402 796 812
 Edition : 12.94 (1) EN
 Type number : 0 412 726 902
 Type number : 0 421 890 017
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: JOHN DEERE
 Engine: 6081 (8400 ROW)
 Output kW: 205
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413	077
Inlet pressure	bar	1.4	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901	103
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750	089
Dimensions:			
Outer diameter.	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	3.55 3.65
P Prestroke (from BDC)	mm	3.50 3.70
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

Min Max

PC mark	Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0	3)
Tolerance +/-°CS			0.20
P Tolerance +/-°CS			0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10
Check value U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60
pos.amplitude V		0.8 2.0
P pos.amplitude V		0.6 3.0
Speed	1/min	600
Difference Amplitude to Amplitude	V	max. 1.4

Continued on next page

Testoil-ISO 4113

=====
 Min Max
 =====

S e c t i o n C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1050	
U/actual	V	2.840	
Fuel			
delivery	cm3/1000str	212.0	214.0
P Fuel			
delivery	cm3/1000str	209.0	217.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	450	
U/actual	V	1.530	1.650
delivery	cm3/1000str	23.0	29.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

REMARKS

John Deere Nr.: RE 57 375
 Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = Start-of-delivery - Incipient fissure 9.75 degrees NW after start-of-delivery cyl.1 Incipient fissure over coupling and pointer. Incipient fissure measured at 67...73 degrees from vertical axis of pump.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.: U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 7356
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 796 813

TEST SHEET : 0 402 796 816
 Edition : 12.94 (1) EN
 Type number : 0 412 726 919
 Type number : 0 421 890 017
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: JOHN DEERE
 Engine: 6081 (8400 ROW)
 Output kW: 205
 at 1/min:

	Min	Max
Test PREREQUISITES		

Test oil inlet temperature	°C	38	42
Overflow valve		2 417 413	077
Inlet pressure	bar	1.4	1.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901	103
Opening pressure	bar	207	210
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750	089
Dimensions:			
Outer diameter.	mm	8.0	
x wall thickness	mm	2.5	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure	bar	25	27
Prestroke (from BDC)	mm	3.55	3.65
P Prestroke (from BDC)	mm	3.50	3.70
Control-rod travel	mm	10.0	11.0
Cam sequence		1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each	
tolerance +/-°CS			0.50
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60	
pos.amplitude	V	0.8	2.0
P pos.amplitude	V	0.6	3.0
Speed	1/min	600	
Difference Amplitude to Amplitude	V	max.	1.4

Continued on next page

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	1050	
U/actual	V	3.030	
Fuel			
delivery	cm3/1000str	212.0	214.0
P Fuel			
delivery	cm3/1000str	209.0	217.0
Dispersion	cm3/1000str		5.0
P Dispersion	cm3/1000str		9.0

Test point L1

Speed	1/min	450	
U/actual	V	1.680	1.800
delivery	cm3/1000str	23.0	29.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		10.0

REMARKS

John Deere-Nr.: RE 61 658
 Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 2) = Start-of-delivery - Incipient fissure 9.75 degrees NW after start-of-delivery cyl.1 Incipient fissure over coupling and pointer. Incipient fissure measured at 67...73 degrees from vertical axis of pump.
- 3) = Pulse wheel position 10.5° camshaft after port closing of cylinder 1.
- 4) = U/actual value min.: U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 720 RS 8010
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 004

TEST SHEET : 0 402 896 004
 Edition : 12.94 (5) EN
 Type number : 0 412 826 014
 Type number : 0 421 890 009
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: SCANIA
 Engine: DSC 1127 (Bus)
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413 025	
Inlet pressure	bar	2.4	2.6
Overflow	l/h	-	-
Calibrating nozzle-holder assembly		1 688 901 104	
Opening pressure	bar	250	253
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	25	27
Prestroke (from BDC)	mm	2.75 2.85
P Prestroke (from BDC)	mm	2.70 2.90
Control-rod travel	mm	10.0 11.0
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each
tolerance +/-°CS		0.50
P tolerance +/-°CS		0.75

	Min	Max
PC mark Cyl.-No.	1	2)
Pulse wheel position (PC cam)	°CS	0 3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0
Setting value U/actual	V	3.100
Control-rod travel	mm	12.95 13.05
P Control-rod travel	mm	12.90 13.10

Check value

U/actual	V	1.700
Control-rod travel	mm	5.90 6.40
P Control-rod travel	mm	5.85 6.45

Stop position

U/actual	V	mind. 4)
Control-rod travel	mm	0.5 1.0
P Control-rod travel	mm	0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference
 Amplitude to Amplitude V max. 1.4

Continued on next page

Testoil-ISO 4113

	Min	Max
--	-----	-----

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
(Observe "Remarks" Point 5), 6)).

Test point V1

Speed	1/min	700	
U/actual	V	3.500	
Fuel delivery	cm3/1000str	331.0	333.0
P Fuel delivery	cm3/1000str	328.0	336.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Test point L1

Speed	1/min	250	
U/actual	V	1.660	1.780
Fuel delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		4.0
P Dispersion	cm3/1000str		8.0

REMARKS

SCANIA-No.: 1 328 145

Dimension "Y"
(Adjustment flange) 15.6 16.1

- 1) = Arrangement of pressure-relief valve:
Pump side 4.2 (previous: pump side 2 rear).
- 2) = Start of delivery mark at start of delivery of cylinder No 1.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

REMARKS (Continued)

5) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm: Pump page 3.1 (previous: pump side 1).

6) = Pressure valve holder: Setting of valve spring pretensioning omitted.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 720 RS 8025
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 896 013

TEST SHEET : 0 402 896 013
 Edition : 12.94 (1) EN
 Type number : 0 412 826 026
 Type number : 0 421 890 019
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: SCANIA
 Engine: DSC 1124 (BUS)
 Output kW:
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413 025	
Inlet pressure	bar	2.4	2.6
Overflow	l/h	220	260
Calibrating nozzle-holder assembly		1 688 901 104	
Opening pressure	bar	250	253
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750 008	
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure	bar	25	27
Prestroke (from BDC)	mm	2.80	2.90
P Prestroke (from BDC)	mm	2.75	2.95
Control-rod travel	mm	10.0	11.0
Cam sequence		1 - 5 - 3 - 6 - 2 - 4	
PC difference	°CS	60 each	
tolerance +/-°CS			0.50
P tolerance +/-°CS			0.75

	Min	Max
PC mark Cyl.-No.	1	3)
Pulse wheel position (PC cam)	°CS	0 4)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10

Check value

U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	5)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference
 Amplitude to Amplitude V max. 1.4

Continued on next page

(On our copy, revolution norm at test point I1 is missing).

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
 (Observe "Remarks" Point 6), 7))

Test point V1

Speed	1/min	700	
U/actual	V	3.500	
Fuel delivery	cm3/1000str	339.0	341.0
P Fuel delivery	cm3/1000str	336.0	344.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		12.0

Test point L1

Speed	1/min	250	
U/actual	V	1,580	1,700
Fuel delivery	cm3/1000str	13.0	19.0
Dispersion	cm3/1000str		4.0
P Dispersion	cm3/1000str		8.0

Testoil-ISO 4113

REMARKS

SCANIA-No.: 1 361 124

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Arrangement of pressure-relief valve:
 Pump side 4.2 (previous: pump side 2 rear).
- 2) = Setting of overflow at full load (refer to measurement point V1).
- 3) = Start of delivery mark at start of delivery of cylinder No 1.

REMARKS (Continued)

- 4) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 5) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.
- 6) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm:
 Pump page 3.1
 (previous: pump side 1).
- 7) = Pressure valve holder:
 Setting of valve spring pretensioning omitted.

=====
 Min Max
 =====

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PE 6 P 120 A 720 RS 8029
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 896 014

TEST SHEET : 0 402 896 014
 Edition : 12.94 (1) EN
 Type number : 0 412 626 028
 Type number : 0 421 890 021
 CUSTOMER IDENT. NO.:

Customer-specific details
 Customer: SCANIA
 Engine: DSC 1124, (BUS, NKW)
 Output kW:
 at 1/min:

	Min	Max
=====		
T e s t P R E R E Q U I S I T E S		
=====		

Test oil inlet temperature	°C	38	42
Overflow valve		1 417 413	025
Inlet pressure	bar	2.4	2.6
Overflow	l/h	220	260
Calibrating nozzle-holder assembly		1 688 901	104
Opening pressure	bar	250	253
Perforated plate diameter	mm	0.7	
Test pressure line		1 680 750	008
Dimensions:			
Outer diameter.	mm	6.0	
x wall thickness	mm	2.0	
x length	mm	600	

Testoil-ISO 4113

=====

T E S T S P E C I F I C A T I O N S

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.		1	
Test pressure bar		25	27
Prestroke (from BDC)	mm	2.80	2.90
P Prestroke (from BDC)	mm	2.75	2.95
Control-rod travel	mm	10.0	11.0
Cam sequence		1-5-3-6-2-4	
PC difference tolerance +/-°CS		60 each	0.50
P tolerance +/-°CS			0.75

	Min	Max
=====		
PC mark	Cyl.-No.	1 3)
Pulse wheel position (PC cam)	°CS	0 4)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.75

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5 V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45
Stop position U/actual	V	mind.	5)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60	
pos.amplitude V		0.8	2.0
P pos.amplitude V		0.6	3.0
Speed	1/min	600	
Difference Amplitude to Amplitude	V	max.	1.4

Continued on next page

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING
 (Observe "Remarks" Point 6), 7))

Test point V1

Speed 1/min 700
 U/actual V 3.500

Fuel delivery cm3/1000str 339.0 341.0

P Fuel delivery cm3/1000str 336.0 344.0

Dispersion cm3/1000str 8.0

P Dispersion cm3/1000str 12.0

Test point L1

Speed 1/min 250
 U/actual V 1.580 1.700

Fuel delivery cm3/1000str 13.0 19.0

Dispersion cm3/1000str 4.0

P Dispersion cm3/1000str 8.0

REMARKS

SCANIA-No.: 1 361 124

Dimension "Y"
 (Adjustment flange) 15.6 16.1

- 1) = Arrangement of pressure-relief valve:
 Pump side 4.2 (previous: pump side 2 rear).
- 2) = Setting of overflow at full load (refer to measurement point V1).
- 3) = Start of delivery mark at start of delivery of cylinder No 1.
- 4) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.

REMARKS (Continued)

- 5) = U/actual value min.:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.
- 6) = Feed rate checking and adjustment with ROBO diaphragm. Connection of the ROBO diaphragm: Pump page 3.1 (previous: pump side 2).
- 7) = Pressure valve holder:
 Setting of valve spring pretensioning omitted.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump: PES 6 P 120 A 720 RS 8505
 Regulator: RE 30
 IP-ASSEMBLY: 0 402 996 302

TEST SHEET : 0 402 996 302
 Edition : 12.94 (1) EN
 Type number : 0 412 926 204
 Type number : 0 421 890 015
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MACK
 Engine: E 7 - 450
 Output kW: - -
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413 084	
Inlet pressure bar	2.4	2.6
Overflow 1) l/h	- -	- -
Calibrating nozzle-holder assembly	1 688 901 103	
Opening pressure bar	207	210
Perforated plate diameter mm	0.7	
Test pressure line	1 680 750 008	
Dimensions:		
Outer diameter. mm	6.0	
x wall thickness mm	2.0	
x length mm	600	

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	22	24
Prestroke (from BDC) mm	3.55	3.65
P Prestroke (from BDC) mm	3.50	3.70
Control-rod travel mm	11.8	12.2
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference °CS	60 each	
tolerance +/-°CS		0.30
P tolerance +/-°CS		0.75

	Min	Max
--	-----	-----

PC mark Cyl.-No.	-	2)	
Pulse wheel position (PC cam) °CS	0	3)	
Tolerance +/-°CS			0.20
P Tolerance +/-°CS			0.50

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed	1/min	0	
Setting value U/actual	V	3.100	
Control-rod travel	mm	12.95	13.05
P Control-rod travel	mm	12.90	13.10
Check value U/actual	V	1.700	
Control-rod travel	mm	5.90	6.40
P Control-rod travel	mm	5.85	6.45

Stop position

U/actual	V	mind.	4)
Control-rod travel	mm	0.5	1.0
P Control-rod travel	mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position

Speed	1/min	60	
pos.amplitude V		0.8	2.0
P pos.amplitude V		0.6	3.0
Speed	1/min	600	
Difference Amplitude to Amplitude	V	max.	1.4

Continued on next page

Testoil-ISO 4113

Min Max

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.280	
Fuel			
delivery	cm3/1000str	364.0	366.0
P Fuel			
delivery	cm3/1000str	361.0	369.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		14.0

Test point L1

Speed	1/min	325	
U/actual	V	1.240	1.360
Fuel			
delivery	cm3/1000str	27.0	33.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		14.0

REMARKS

MACK-No.: 313 GC 5205-P3

Dimension "Y"
(Adjustment flange) 15.6 15.9

- 1) = Setting of overflow volume at full load omitted
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 8509
 Regulator: RE 30
 IP-ASSEMBLY 0 402 996 303

TEST SHEET : 0 402 996 303
 Edition : 12.94 (1) EN
 Type number : 0 412 926 205
 Type number : 0 421 890 023
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MACK
 Engine: E 7 - 400
 Output kW: - -
 at 1/min:

	Min	Max
--	-----	-----

Test PREREQUISITES

Test oil inlet temperature °C	38	42
Overflow valve	2 417 413	084
Inlet pressure bar	2.4	2.6
Overflow 1) 1/h	- -	- -
Calibrating nozzle-holder assembly	1 688 901	103
Opening pressure bar	207	210
Perforated plate diameter mm	0.7	
Test pressure line	1 680 750	008
Dimensions:		
Outer diameter. mm	6.0	
x wall thickness mm	2.0	
x length mm	600	

Testoil-ISO 4113

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl.	1	
Test pressure bar	22	24
Prestroke (from BDC) mm	4.55	4.65
P Prestroke (from BDC) mm	4.50	4.70
Control-rod travel mm	11.8	12.2
Cam sequence	1 - 5 - 3 - 6 - 2 - 4	
PC difference °CS	60 each	
tolerance +/-°CS		0.30
P tolerance +/-°CS		0.75

	Min	Max
--	-----	-----

PC mark Cyl.-No. - 2)		
Pulse wheel position (PC cam) °CS	0	3)
Tolerance +/-°CS		0.20
P Tolerance +/-°CS		0.50

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed 1/min	0	
Setting value U/actual V	3.100	
Control-rod travel mm	12.95	13.05
P Control-rod travel mm	12.90	13.10

Check value

U/actual V	1.700	
Control-rod travel mm	5.90	6.40
P Control-rod travel mm	5.85	6.45

Stop position

U/actual V	mind.	4)
Control-rod travel mm	0.5	1.0
P Control-rod travel mm	0.4	1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

Min Max

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.050	
Fuel			
delivery	cm3/1000str	309.0	311.0
P Fuel			
delivery	cm3/1000str	306.0	314.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		14.0

Test point L1

Speed	1/min	325	
U/actual	V	1.250	1.370
Fuel			
delivery	cm3/1000str	30.0	36.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		14.0

REMARKS

MACK-No.: 313 GC 5205-P3

Dimension "Y"
(Adjustment flange) 15.6 15.9

- 1) = Setting of overflow volume at full load omitted
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min.:
U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

Testoil-ISO 4113

BOSCH TEST SPECS. IP ASSEMBLY
 Pump : PES 6 P 120 A 720 RS 8510
 Regulator : RE 30
 IP-ASSEMBLY: 0 402 996 304

TEST SHEET : 0 402 996 304
 Edition : 12.94 (1) EN
 Type number : 0 412 926 206
 Type number : 0 421 890 023
 CUSTOMER IDENT. NO.:

Customer-specific details

Customer: MACK
 Engine: E 7-450
 Output kW: - -
 at 1/min:

Min Max

Test PREREQUISITES

Test oil inlet temperature °C 38 42

Overflow valve 2 417 413 084

Inlet pressure bar 2.9 3.1

Overflow 1) l/h - - - -

Calibrating nozzle-holder assembly 1 688 901 103

Opening pressure bar 207 210

Perforated plate diameter mm 0.7

Test pressure line 1 680 750 008

Dimensions:
 Outer diameter. mm 6.0
 x wall thickness mm 2.0
 x length mm 600

TEST SPECIFICATIONS

Section A -
 Setting values of injection pump
 - Check values denoted by "P"
 - No basic setting. Equal delivery setting under Section C.

PORT CLOSING

PC setting cyl. 1
 Test pressure bar 22 24
 Prestroke (from BDC) mm 3.55 3.65
 P Prestroke (from BDC) mm 3.50 3.70
 Control-rod travel mm 11.8 12.2
 Cam sequence 1 - 5 - 3 - 6 - 2 - 4
 PC difference °CS 60 each
 tolerance +/-°CS 0.30
 P tolerance +/-°CS 0.75

Min Max

PC mark Cyl.-No. - 2)
 Pulse wheel position (PC cam) °CS 0 3)
 Tolerance +/-°CS 0.20
 P Tolerance +/-°CS 0.50

Section B -

Actuator test
 - Check values denoted by "P"
 - Assembly warm-up time: 3 mins. at n = 600 1/min, U/actual = 2.5V

CONTROL-ROD PICKUP SETTING

Test speed 1/min 0
 Setting value U/actual V 3.100
 Control-rod travel mm 12.95 13.05
 P Control-rod travel mm 12.90 13.10
 Check value U/actual V 1.700
 Control-rod travel mm 5.90 6.40
 P Control-rod travel mm 5.85 6.45

Stop position

U/actual V mind. 4)
 Control-rod travel mm 0.5 1.0
 P Control-rod travel mm 0.4 1.1

SPEED SENSOR SIGNALS

- Test with control rod in stop position
 Speed 1/min 60
 pos.amplitude V 0.8 2.0
 P pos.amplitude V 0.6 3.0
 Speed 1/min 600
 Difference Amplitude to Amplitude V max. 1.4

Continued on next page

Testoil-ISO 4113

=====
 Min Max
 =====

Section C -

Injection pump with actuator

- Check values denoted by "P"

FUEL DELIVERY TEST AND SETTING

Test point V1

Speed	1/min	900	
U/actual	V	3.280	
Fuel			
delivery	cm3/1000str	364.0	366.0
P Fuel			
delivery	cm3/1000str	361.0	369.0
Dispersion	cm3/1000str		8.0
P Dispersion	cm3/1000str		14.0

Test point L1

Speed	1/min	325	
U/actual	V	1.240	1.360
Fuel			
delivery	cm3/1000str	27.0	33.0
Dispersion	cm3/1000str		6.0
P Dispersion	cm3/1000str		14.0

REMARKS

MACK-No.: 313 GC 5205-P3

Dimension "Y"
 (Adjustment flange) 15.6 15.9

- 1) = Setting of overflow volume at full load omitted
- 2) = No start-of-delivery mark.
- 3) = Setting of pulse-wheel position at start of delivery of cylinder No. 1.
- 4) = U/actual value min:
 U/actual minimum value with deenergized servo magnet and control rod in shutoff position.

Testoil-ISO 4113

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Obsereve notes in remark colum

Test sheet : VW
 Date of manufacture :
 Edition : 25.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R590-1
 Type No. : 0 460 404 982
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 TDI USA

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery actuator): (KDEP 1865/10)

Test line : 0 986 611 983
 (solenoid valve
 start of injection): (KDEP 1190)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and.
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 5 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and.
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connentions 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2450
Setting value, bar : 7.6...8.4

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2450
Setting value, mm : 9.7...9.9

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2420
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 37.2...37.6
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 4000
Supply pump
pressure > bar : 9.9...10.9
> bar :

2st speed 1/min : 300
Checkbk. volt
mV : 2450
Supply pump
pressure > bar : 6.6...8.0
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2450
Timing device
travel mm :
> mm : (8.8...10.8)

2nd speed 1/min : 2000
Checkbk. volt. mV : 4000
Timing device
travel mm : 11.8...12.6
> mm : (11.4...13.0)

3rd speed 1/min : 1400
Checkbk. volt. mV : 1310
Timing device
travel mm : max. 0.5
> mm : (max. 0.8)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 300
Checkbk. volt. mV : 2450
Timing device
travel mm : 6.6...9.6
> mm : (6.1...10.1)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3890
Measuring
temperature °C : 53
Overflow : 96...150
> cm³/10s : (83...165)

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt mV : 4000
Meßtemperatur °C : 53
Fuel delivery cm³/ : 54.9...57.3
> 1000s : (54.3...57.9)
Dispersion cm³/ : 2.5
> 1000s :

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 3210
Measuring
temperature °C : 56
Fuel delivery cm³/ : 52.8...55.2
> 1000s : (52.2...55.8)
Dispersion cm³/ : 2.5
> 1000s :

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 2000
Measuring
temperature °C : 56
Fuel delivery cm³/ : 23.7...25.7
> 1000s : (23.2...26.2)
Dispersion cm³/ : 2.50
> 1000s :

4th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2450
Measuring
temperature °C : 57
Fuel delivery cm³/ : 43.8...46.4
> 1000s : (43.3...46.9)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:

1st temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1550
Meßtemperatur °C : 57
Fuel delivery cm³/ : 7.3...11.3
> 1000s : (6.3...12.3)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 4.0
> 1000s :

Starting fuel delivery:

1st temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2310
Measuring
temperature °C : 61
Fuel delivery cm³/ : 37.0...47.0
> 1000s : (34.0...50.0)

Solenoid valve

Start of
injection, volts : 12

Stop test:

Speed 1/min : 750
Checkbk. volt mV : 3650
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	: 6,2...6,6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 25.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2075R638
 Type No. : 0 460 404 986
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 TDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery actuator): (KDEP 1865/10)

Test line : 0 986 611 983
 (solenoid valve
 start of injection): (KDEP 1190)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator

Connections 5 and 6

Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0

Connections 6 and
 ground, Mohms min. : 1.0

Connections 3 and 5
 Mohms min. : 1.0

Connections 5 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils

Connections 1 and 2
 Ohms : 4.9...6.5

Connections 2 and 3
 Ohms : 4.9...6.5

Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0

Connections 2 and
 ground, Mohms min. : 1.0

Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7

Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0

Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2

Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2560
Setting value, bar : 8.1...8.9

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2560
Setting value, mm : 10.1...10.3

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.7...35.1
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2050
Checkbk. volt
mV : 3890
Supply pump
pressure > bar : 10.5...11.5
> bar :

2st speed 1/min : 300
Checkbk. volt
mV : 2560
Supply pump
pressure > bar : 6.8...8.2
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2560
Timing device
travel mm :
> mm : (9.2...11.2)
2nd speed 1/min : 2050
Checkbk. volt. mV : 3890
Timing device
travel mm : 11.9...12.7
> mm : (11.5...13.1)
3rd speed 1/min : 1500
Checkbk. volt. mV : 1500
Timing device
travel mm : max. 0.5
> mm : (max. 0.8)
Solenoid valve
Start of
injection, volts : 12
4.th speed 1/min : 300
Checkbk. volt. mV : 2560
Timing device
travel mm : 6.5...10.5
> mm : (5.5...11.5)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2050
Checkbk. volt. mV : 3890
Measuring
temperature °C : 53
Overflow : 123...205
> cm³/10 : (109...219)

Fuel delivery variations:

1st temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2050
 Checkbk. volt mV : 3890
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 49.3...51.7
 > 1000s : (48.7...52.3)
 Dispersion cm³/ : 2.5
 > 1000s. :

2nd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 60
 Speed 1/min : 1000
 Checkbk. volt mV : 3350
 Measuring
 temperature °C : 56
 Fuel delivery cm³/ : 53.1...55.5
 > 1000s : (52.8...55.8)
 Dispersion cm³/ : 2.5
 > 1000s :

3rd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2480
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (33.6...36.2)
 Dispersion cm³/ : 2,50
 > 1000s :

4th temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2560
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 42.0...44.6
 > 1000s : (41.3...45.3)
 Dispersion cm³/ : 3,0
 > 1000s :

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 400
 Checkbk. volt mV : 1800
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 8.7...12.7
 > 1000s : (7.7...13.7)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 4.0
 > 1000s :

Starting fuel delivery:
 1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2420
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 35.7...45.7
 > 1000s : (32.7...48.7)
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:
 Speed 1/min : 1000
 Checkbk. volt mV : 4000
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0
 Start of

Shutoff solenoid:
 Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:
 High-pressure compressor sensor
 Testing only possible with ballast
 EPS 910

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description		
K	mm	: 3.6...3.8
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 25.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R640
 Type No. : 0 460 404 987
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 SDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-holder assembly > : 1 688 901 114

Opening pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery actuator) : (KDEP 1865/10)

Test line : 0 986 611 983
 (solenoid valve start of injection): (KDEP 1190)

TEST PRECONDITIONS

Test oil return temp. > °C with thermometer : 55

Test oil supply temperature > °C : 42...47

Hold-up revolutions >1/min : 1200
 Feedback voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and ground, Mohms min. : 1.0
 Connections 6 and ground, Mohms min. : 1.0
 Connections 3 and 5 Mohms min. : 1.0
 Connections 5 and 7 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2 Ohms : 4.9...6.5
 Connections 2 and 3 Ohms : 4.9...6.5
 Connections 1 and 3 Ohms : 9.8...13.0

Connections 1 and ground, Mohms min. : 1.0
 Connections 2 and ground, Mohms min. : 1.0
 Connections 3 and ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and ground, Mohms min. : 1.0
 Connections 7 and ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2360
Setting value, bar : 6.1...6.5

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2360
Setting value, mm : 10.6...10.8

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt
mV : 2550
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.6...35.0
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt
mV : 3370
Supply pump
pressure > bar : 8.7...9.3
> bar : (8.5...9.5)

2st speed 1/min : 300
Checkbk. volt
mV : 2360
Supply pump
pressure > bar : 5.4...6.6
> bar : (5.2...6.8)

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2360
Timing device
travel mm :
> mm : (9.7...11.7)
2nd speed 1/min : 2100
Checkbk. volt. mV : 3370
Timing device
travel mm : 11.8...12.4
> mm : (11.4...13.0)
3rd speed 1/min : 2100
Checkbk. volt. mV : 1400
Timing device
travel mm : max. 3.0
> mm : (max. 4.0)
Solenoid valve
Start of
injection, volts : 12
4.th speed 1/min : 300
Checkbk. volt. mV : 2360
Timing device
travel mm : 8.6...11.0
> mm : (8.2...11.4)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt. mV : 3370
Measuring
temperature °C : 53
Overflow : 109...164
> cm³/10 : (82...193)

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt mV : 3370
Meßtemperatur °C : 53
Fuel delivery cm³/
> 1000s : 36.4...38.8
> 1000s : (35.8...39.4)
Dispersion cm³/
> 1000s. :

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1100
Checkbk. volt mV : 2770
Measuring
temperature °C : 56
Fuel delivery cm³/ : 34.4...36.8
> 1000s : (33.8...37.4)
Dispersion cm³/ : 2.5
> 1000s :

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1100
Checkbk. volt mV : 2160
Measuring
temperature °C : 56
Fuel delivery cm³/ : 23.5...25.5
> 1000s : (23.0...26.0)
Dispersion cm³/ : 2.50
> 1000s :

4th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt mV : 2550
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (33.5...36.1)
Dispersion cm³/ : 2.5
> 1000s :

5th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2360
Measuring
temperature °C : 57
Fuel delivery cm³/ : 35.7...38.3
> 1000s : (35.2...38.8)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1640
Meßtemperatur °C : 57
Fuel delivery cm³/ : 6.0...10.0
> 1000s : (5.0...11.0)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 4.0
> 1000s :

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2730
Measuring
temperature °C : 61
Fuel delivery cm³/ : 43.0...53.0
> 1000s : (40.0...51.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 750
Checkbk. volt mV : 3650
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K mm :
KF mm : 6.2...6.6
SVS max. mm :
FH mm :
TS : 1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 25.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R600
 Type No. : 0 460 404 989
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 SDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0,30...0,40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery
 actuator) : (KDEP 1865/10)

Test line : 0 986 611 983
 (solenoid valve
 start of injection) : (KDEP 1190)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 5 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2360
Setting value, bar : 6.2...6.6

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2360
Setting value, mm : 10.6...10.8

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt
mV : 2550
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.6...35.0
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt
mV : 3370
Supply pump
pressure > bar : 8.7...9.3
> bar : (8.5...9.5)

2st speed 1/min : 300
Checkbk. volt
mV : 2360
Supply pump
pressure > bar : 5.4...6.6
> bar : (5.2...6.8)

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2360
Timing device
travel mm :
> mm : (9.7...11.7)
2nd speed 1/min : 2100
Checkbk. volt. mV : 3370
Timing device
travel mm : 11.8...12.4
> mm : (11.4...13.0)
3rd speed 1/min : 2100
Checkbk. volt. mV : 1400
Timing device
travel mm : max. 3.0
> mm : (max. 4.0)
Solenoid valve
Start of
injection, volts : 12
4.th speed 1/min : 300
Checkbk. volt. mV : 2360
Timing device
travel mm : 8.6...11.0
> mm : (8.2...11.4)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt. mV : 3370
Measuring
temperature °C : 53
Overflow : 96...150
> cm³/10 : (82...164)

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt mV : 3370
Meßtemperatur °C : 53
Fuel delivery cm³/
> 1000s : 36.4...38.7
> 1000s : (35.7...39.3)
Dispersion cm³/
> 1000s. :

2nd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1100
Checkbk. volt mV : 2770
Measuring
temperature °C : 56
Fuel delivery cm³/ : 34.6...37.0
> 1000s : (34.0...37.6)
Dispersion cm³/ : 2.5
> 1000s :

3rd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1100
Checkbk. volt mV : 2160
Measuring
temperature °C : 56
Fuel delivery cm³/ : 23.5...25.5
> 1000s : (23.0...26.0)
Dispersion cm³/ : 2.50
> 1000s :

4th temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt mV : 2550
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (33.5...36.1)
Dispersion cm³/ : 2.5
> 1000s :

5th temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2360
Measuring
temperature °C : 57
Fuel delivery cm³/ : 35.7...38.3
> 1000s : (35.2...38.8)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1640
Meßtemperatur °C : 57
Fuel delivery cm³/ : 6.5...10.5
> 1000s : (5.5...11.5)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 4.0
> 1000s :

Starting fuel delivery:
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2730
Measuring
temperature °C : 61
Fuel delivery cm³/ : 45.0...55.0
> 1000s : (42.0...58.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:
Speed 1/min : 750
Checkbk. volt mV : 3650
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:
Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:
High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 25.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/11E2250R590
 Type No. : 0 460 404 990
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 TDI USA

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0,30...0,40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6,00
 x wall thickness > : 2,20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery actuator): KDEP 1865/10

Test line : 0 986 611 983
 (solenoid valve
 start of injection): KDEP 1190

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0,4...1,0
 50°...70°C, ohms : 0,45...1,1

Connections 5 and
 ground, Mohms min. : 1,0
 Connections 6 and
 ground, Mohms min. : 1,0
 Connections 3 and 5
 Mohms min. : 1,0
 Connections 5 and 7
 Mohms min. : 1,0

High-pressure compressor sensor
 Sensor coils
 Connections 3 and 2
 Ohms : 4,9...6,5
 Connections 1 and 2
 Ohms : 4,9...6,5
 Connections 1 and 3
 Ohms : 9,8...13,0

Connections 1 and
 ground, Mohms min. : 1,0
 Connections 2 and
 ground, Mohms min. : 1,0
 Connections 3 and
 ground, Mohms min. : 1,0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1,2...4,0
 50°...70°C, kohms : 0,3...1,2

Connections 4 and
 ground, Mohms min. : 1,0
 Connections 7 and
 ground Mohms min. : 1,0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14,3...17,3
 50°...70°C, ohms : 15,5...21,0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2450
Setting value, bar : 7,8...8,2

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2450
Setting value, mm : 9,7...9,9

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2420
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 37,2...37,6
Dispersion cm³/
> 1000s : 2,5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 200
Checkbk. volt
mV : 4000
Supply pump
pressure > bar : 9,9...10,5
> bar : (9,7...10,7)

2st speed 1/min : 300
Checkbk. volt
mV : 2450
Supply pump
pressure > bar : 6,7...7,9
> bar : (6,6...8,0)

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2450
Timing device
travel mm :
> mm : (8,8...10,8)

2nd speed 1/min : 2000
Checkbk. volt. mV : 4000
Timing device
travel mm : 11,8...12,6
> mm : (11,4...13,0)

3rd speed 1/min : 2100
Checkbk. volt. mV : 1310
Timing device
travel mm : max. 0,5
> mm : (max. 1,5)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 300
Checkbk. volt. mV : 2450
Timing device
travel mm : 6,9...9,3
> mm : (6,5...9,7)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 4000
Measuring
temperature °C : 53
Overflow : 109...164
> cm³/10 : (96...178)

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt mV : 4000
Meßtemperatur °C : 53
Fuel delivery cm³/
> 1000s : 55,2...57,6
Dispersion cm³/
> 1000s. : 2,5

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 3210
Measuring
temperature °C : 56
Fuel delivery cm³/ : 52,8...55,2
> 1000s : (52,2...55,8)
Dispersion cm³/ : 2,5
> 1000s :

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1100
Checkbk. volt mV : 2000
Measuring
temperature °C : 56
Fuel delivery cm³/ : 24,0...26,0
> 1000s : (23,5...26,5)
Dispersion cm³/ : 2,5
> 1000s :

4th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2420
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (36,1...38,7)
Dispersion cm³/ : 2,5
> 1000s :

5th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2450
Measuring
temperature °C : 57
Fuel delivery cm³/ : 43,8...46,4
> 1000s : (43,3...46,9)
Dispersion cm³/ : 3,0
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1550
Meßtemperatur °C : 57
Fuel delivery cm³/ : 8,2...12,2
> 1000s : (7,2...13,2)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 4,0
> 1000s :

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2310
Measuring
temperature °C : 61
Fuel delivery cm³/ : 37,0...47,0
> 1000s : (34,0...50,0)
Solenoid valve
Start of
injection, volts : 12
Stop test:
Speed 1/min : 750
Checkbk. volt mV : 3300
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3,0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10,0
Rated voltage,
volts : 12,0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	: 6.2...6.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : PSA
 Date of manufacture :
 Edition : 26.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2150R520
 Type No. : 0 460 404 993
 Customer Ident.No. :

Customer-specific details
 Customer : PSA

Engine : DK5ATE

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 022

Opening
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00
 x wall thickness > : 2.00
 x length > mm : 450

Overflow valve : 2 467 413 009

Test line : 0 986 612 441
 (fuel-delivery actuator): (KDEP 1865/12)

Test line : 0 986 612 435
 (solenoid valve
 start of injection): (KDEP 1865/6)

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 2 and 6
 Mohms min. : 1.0
 Connections 4 and 5
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000
Checkbk. volt.
mV : 2150
Setting value, bar : 9.4...10.4

Timing device travel:

Speed 1/min : 1000
Checkbk. volt
mV : 3020
Setting value, mm : 10.7...10.9

Speed 1/min : 1250
Checkbk. volt
mV : 2230
Fuel delivery cm³/
> 1000s : 32.4...32.8
Dispersion cm³/
> 1000s : 2.0

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2150
Checkbk. volt
mV : 3020
Supply pump
pressure > bar : 9.4...10.4
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3020
Timing device
travel mm : 9.1...10.1
> mm : (8.4...10.8)

2nd speed 1/min : 1000
Checkbk. volt. mV : 3020
Timing device
travel mm :
> mm : (10.0...11.6)

3rd speed 1/min : 1600
Checkbk. volt. mV : 1600
Timing device
travel mm : 0.0...1.0
> mm : (0.0...2.5)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2150
Checkbk. volt. mV : 3020
Timing device
travel mm : 12.0...12.6
> mm : (11.8...12.8)

Overflow at overflow valve:

Speed 1/min : 2400
Checkbk. volt. mV : 3020
Overflow : 96...178
> cm³/10s :

Fuel delivery variations:

Speed 1/min : 2150
Checkbk. volt mV : 3120
Fuel delivery cm³/ : 70.5...73.5
> 1000s : (69.7...74.3)
Dispersion cm³/ : 2.0
> 1000s. :

Speed 1/min : 1250
Checkbk. volt mV : 2230
Fuel delivery cm³/ :
> 1000s : (31.3...33.9)
Dispersion cm³/ :
> 1000s :

Speed 1/min : 1000
Checkbk. volt mV : 3275
Fuel delivery cm³/ : 90.5...93.5
> 1000s : (89.5...94.5)
Dispersion cm³/ : 2.0
> 1000s :

Idle delivery:

Speed 1/min : 375
Checkbk. volt mV : 2175
Fuel delivery cm³/ : 19.7...22.7
> 1000s : (18.7...23.7)

Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 2.0
> 1000s :

Starting fuel delivery:
Speed 1/min : 100
Checkbk. volt mV : 3410
Fuel delivery cm³/ : 72.0...82.0
> 1000s : (69.0...85.0)

Solenoid valve
Start of
injection, volts : 12

Stop test:
Speed 1/min : 1000
Checkbk. volt mV : 3020
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Dispersion cm³/ : 5.0

Shutoff solenoid:
Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Dimensions for mounting and setting:

Description
K mm : 3.6...3.8
KF mm : 8.2...8.6
SVS max. mm :
FH mm :
TS : 1 467 010 495

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : Audi
 Date of manufacture :
 Edition : 25.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE5/11E2300L460-2
 Type No. : 0 460 415 989
 Customer Ident.No. :
 Customer-specific details
 Customer : VW

Engine : R5 2.5 L TDi

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0,30...0,40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 440
 (fuel-delivery actuator): (KDEP 1865/10)

Test line : 0 986 612 435
 Solenoid valve
 start of injection): (KDEP 1865/6)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 5 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 4.9...6.5
 Connections 1 and 2
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 750
Checkbk. volt.
mV : 3900
Setting value, bar : 6.0...7.0

Timing device travel:

Speed 1/min : 750
Checkbk. volt
mV : 3900
Setting value, mm : 9.3...9.5

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2125
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2460
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 40.8...41.2
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2125
Checkbk. volt
mV : 3900
Supply pump
pressure > bar : 7.9...8.9
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3900
Timing device
travel mm : 7.5...9.9
> mm : (7.2...10.2)
2nd speed 1/min : 750
Checkbk. volt. mV : 3900
Timing device
travel mm :
> mm : (7.5...11.3)
3rd speed 1/min : 1200
Checkbk. volt. mV : 1800
Timing device
travel mm : max. 0.3
> mm : (max. 1.0)
Solenoid valve
Start of
injection, volts : 12
4.th speed 1/min : 2125
Checkbk. volt. mV : 3900
Timing device
travel mm : 11.6...12.6
> mm : (11.5...12.7)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2125
Checkbk. volt. mV : 3900
Measuring
temperature °C : 53
Overflow : 54...164
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2125
 Checkbk. volt mV : 3910
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 55.9...58.5
 > 1000s : (55.2...59.2)
 Dispersion cm³/ : 3.0
 > 1000s. :

2nd temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 60
 Speed 1/min : 1000
 Checkbk. volt mV : 3210
 Measuring
 temperature °C : 56
 Fuel delivery cm³/ : 57.2...59.8
 > 1000s : (56.5...60.5)
 Dispersion cm³/ : 2.0
 > 1000s : (2.5)

3rd temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2460
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (39.7...42.3)
 Dispersion cm³/ :
 > 1000s :

4th temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2320
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 42.1...44.7
 > 1000s : (41.4...45.4)
 Dispersion cm³/ : 3.0
 > 1000s :

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 1520
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 10.2...13.5
 > 1000s : (9.2...15.2)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 3.0
 > 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
 revolution 1/min : 2125
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2960
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 77.5...89.5
 > 1000s : (72.5...84.5)
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:

Speed 1/min : 1500
 Checkbk. volt mV : 4125
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0
 Start of
 injection, volts : 12
 Speed 1/min : 750
 Checkbk. volt mV : 2460
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 5.0

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	:	2.7...2.9
KF	mm	:	6.5...6.9
SVS max.	mm	:	
FH	mm	:	
TS		:	1 467 010 494

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : Volvo
 Date of manufacture :
 Edition : 25.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE5/11E2300L649
 Type No. : 0 460 415 990
 Customer Ident.No. :

Customer-specific details
 Customer : Audi

Engine : 2.5 TDI USA

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery actuator): (KDEP 1865/10)

Test line : 0 986 611 983
 (solenoid valve
 start of injection): (KDEP 1190)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.5...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1,2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 750
Checkbk. volt.
mV : 3900
Setting value, bar : 6.0...7.0

Timing device travel:
Speed 1/min : 750
Checkbk. volt
mV : 3900
Setting value, mm : 9.3...9.5

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2125
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2460
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 40.8...41.2
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2125
Checkbk. volt
mV : 3900
Supply pump
pressure > bar : 7.9...8.9
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3900
Timing device
travel mm : 7.5...9.9
> mm : (7.2...10.2)

2nd speed 1/min : 750
Checkbk. volt. mV : 3900
Timing device
travel mm :
> mm : (7.5...11.3)

3rd speed 1/min : 1200
Checkbk. volt. mV : 1800
Timing device
travel mm : max. 0.3
> mm : (max. 1.0)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2125
Checkbk. volt. mV : 3900
Timing device
travel mm : 11.6...12.6
> mm : (11.5...12.7)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2125
Checkbk. volt. mV : 3900
Measuring
temperature °C : 53
Overflow : 60...170
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2125
Checkbk. volt mV : 3910
Meßtemperatur °C : 53
Fuel delivery cm³/ : 55.7...58.3
> 1000s : (55.0...59.0)
Dispersion cm³/ : 3.0
> 1000s. :

2nd temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 3210
Measuring
temperature °C : 56
Fuel delivery cm³/ : 58.0...60.6
> 1000s : (57.3...61.3)
Dispersion cm³/ : 2.0
> 1000s : (2.5)

3rd temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2460
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (39.7...42.3)
Dispersion cm³/ :
> 1000s :

4th temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2320
Measuring
temperature °C : 57
Fuel delivery cm³/ : 41.1...44.0
> 1000s : (40.7...44.7)
Dispersion cm³/ : 3,0
> 1000s :

Idle delivery:

1st temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 1520
Meßtemperatur °C : 57
Fuel delivery cm³/ : 9.0...13.0
> 1000s : (8.0...14.0)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning

revolution 1/min : 2125
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2960
Measuring
temperature °C : 61
Fuel delivery cm³/ : 79.0...91.0
> 1000s : (74.0...96.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 1500
Checkbk. volt mV : 4125
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of
Solenoid valve
Start of
injection, volts : 12

Speed 1/min : 750
Checkbk. volt mV : 2460
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 5.0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10,0
Rated voltage,
volts : 12,0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	: 2.7...2.9
KF	mm	: 6.5...6.9
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 494

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : MB
 Date of manufacture :
 Edition : 05.12.1995
 Replaces :
 Test oil : ISO 4113

 Injection pump : VE5/11E1900R641

 Type No. : 0 460 415 992
 Customer Ident.No. :

 Customer-specific details
 Customer : Mercedes-Benz

 Engine : T1N-2-Fh

 Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

 Calibrating nozzle-
 holder assembly > : 1 688 901 116

 Opening
 pressure > bar : 207...210

 Test pressure line : 1 680 750 085

 Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

 Overflow valve : 2 467 413 018

 Test line : 0 986 612 698
 (fuel-delivery
 actuator) : (KDEP 1865/10)

 Test line : Prüfkabelset
 (solenoid valve
 start of injection) : (1 687 011 208)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

 Test oil supply
 temperature > °C : 42...47

 Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 12 and 13
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

 Connections 13 and
 ground, Mohms min. : 1.0
 Connections 12 and
 ground, Mohms min. : 1.0
 Connections 8 and 13
 Mohms min. : 1.0
 Connections 12 and 1
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 8 and 7
 Ohms : 4.9...6.5
 Connections 6 and 7
 Ohms : 4.9...6.5
 Connections 6 and 8
 Ohms : 9.8...13.0

Connections 6 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 8 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 1 and 2
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt. : 2620
mV : 2620
Setting value, bar : 9.3...9.5
: (9.1...9.7)

Timing device travel:

Speed 1/min : 500
Checkbk. volt : 2620
mV : 2620
Setting value, mm : 11.9...12.7
: (11.0...13.6)

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt : 2520
mV : 2520
Measuring
temperature °C : 57
Fuel delivery cm³/ : 51.3...51.7
> 1000s : (49.5...53.3)
Dispersion cm³/ : 2.5
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 1900
Checkbk. volt : 3570
mV : 3570
Supply pump
pressure > bar : 11.3...11.9
> bar : (11.1...12.1)

2st speed 1/min : 200
Checkbk. volt : 2620
mV : 2620
Supply pump
pressure > bar : 4.6...6.6
> bar : (4.4...6.8)

Timing device variations:

1st speed 1/min : 1900
Checkbk. volt. mV : 3570
Timing device
travel mm : 11.8...12.8
> mm : (11.5...13.1)

2nd speed 1/min : 200
Checkbk. volt. mV : 2620
Timing device
travel mm : 3.0...6.0
> mm : (1.3...7.7)

3rd speed 1/min : 1900
Checkbk. volt. mV : 1500
Timing device
travel mm : 0...3.5
> mm :

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 1100
Checkbk. volt. mV : 1530
Timing device
travel mm : 0...0.6
> mm : (0...0.8)

Solenoid valve
Start of
injection, volts : 12
Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 1900
Checkbk. volt. mV : 3570
Measuring
temperature °C : 53
Overflow : 137...192
> cm³/10s : (123...206)

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 1900
Checkbk. volt mV : 3570
Meßtemperatur °C : 53
Fuel delivery cm³/ : 68.1...70.5
> 1000s : (66.6...72.0)
Dispersion cm³/ : 2.5
> 1000s. :

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 3080
Measuring
temperature °C : 56
Fuel delivery cm³/ : 69.3...71.9
> 1000s : (68.6...72.6)
Dispersion cm³/ : 4.0
> 1000s :

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2620
Measuring
temperature °C : 57
Fuel delivery cm³/ : 62.7...65.3
> 1000s : (62.0...66.0)
Dispersion cm³/ :
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 340
Checkbk. volt mV : 2000
Meßtemperatur °C : 57
Fuel delivery cm³/ : 13.5...17.5
> 1000s : (12.5...18.5)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 3110
Measuring
temperature °C : 61
Fuel delivery cm³/ : 75.6
> 1000s :
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 1000
Checkbk. volt mV : 4000
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	: 3.2...3.4
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 22.10.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2100R701
 Type No. : 0 460 404 976
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.7 SDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444
 (fuel-delivery actuator)

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator

Connections 5 and 6

Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0

Connections 6 and
 ground, Mohms min. : 1.0

Connections 3 and 5
 Mohms min. : 1.0

Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils

Connections 1 and 2
 Ohms : 4.9...6.5

Connections 2 and 3
 Ohms : 4.9...6.5

Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0

Connections 2 and
 ground, Mohms min. : 1.0

Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7

Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0

Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2

Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 2510
Setting value, bar : 7.8...8.6

Timing device travel:

Speed 1/min : 500
Checkbk. volt
mV : 2510
Setting value, mm : 9.6...9.8

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt
mV : 2650
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.8...35.2
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt
mV : 3330
Supply pump
pressure > bar : 10.4...11.4
> bar :

2st speed 1/min : 300
Checkbk. volt
mV : 2510
Supply pump
pressure > bar : 6.8...8.2
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2510
Timing device
travel mm :
> mm : (8.7...10.7)

2nd speed 1/min : 2100
Checkbk. volt. mV : 3330
Timing device
travel mm : 11.8...12.8
> mm : (11.5...13.1)

3rd speed 1/min : 2100
Checkbk. volt. mV : 1440
Timing device
travel mm : max. 3.0
> mm :

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 300
Checkbk. volt. mV : 2510
Timing device
travel mm : 6.5...10.5
> mm : (5.1...11.9)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt. mV : 3330
Measuring
temperature °C : 53
Overflow : 116...200
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt mV : 3330
Meßtemperatur °C : 53
Fuel delivery cm³/ : 36.3...38.7
> 1000s : (35.7...39.3)
Dispersion cm³/ : 3.0
> 1000s. :

2nd temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 1100
Checkbk. volt mV : 2880
Measuring
temperature °C : 53
Fuel delivery cm³/ : 34,9...37.3
> 1000s : (34.3...37.9)
Dispersion cm³/ :
> 1000s :

3rd temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 1100
Checkbk. volt mV : 2420
Measuring
temperature °C : 53
Fuel delivery cm³/ : 25.4...27.8
> 1000s : (25.1...28.1)
Dispersion cm³/ :
> 1000s :

4th temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt mV : 2650
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (33.7...36.3)
Dispersion cm³/ :
> 1000s : (2.5)

5th temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2510
Measuring
temperature °C : 57
Fuel delivery cm³/ : 35.5...38.1
> 1000s : (34.8...38.8)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1820
Meßtemperatur °C : 57
Fuel delivery cm³/ : 5.6...9.6
> 1000s : (4.6...10.6)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2820
Measuring
temperature °C : 61
Fuel delivery cm³/ : 43.0...53.0
> 1000s : (40.0...56.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:
Speed 1/min : 1000
Checkbk. volt mV : 3330
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:
Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:
High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description			
K	mm	:	
KF	mm	:	8.2...8.6
SVS max.	mm	:	
FH	mm	:	
TS		:	1 467 010 495

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : Audi
 Date of manufacture :
 Edition : 17.03.1997
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R530-1
 Type No. : 0 460 404 983
 Customer Ident.No. :

Customer-specific details
 Customer : Audi

Engine : 1.9 TDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 440
 (fuel-delivery
 actuator) : (KDEP 1865/10)

Test line : 0 986 611 983
 Solenoid valve
 start of injection): (KDEP 1190)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 3 and 4
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 3
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 2
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2245
Setting value, bar : 6.0...7.4

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2245
Setting value, mm : 10.8...11.0

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 38.8...39.2
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 3890
Supply pump
pressure > bar : 8.4...9.8
> bar : (8.3...9.9)

2nd speed 1/min : 150
Checkbk. volt
mV : 2230
Supply pump
pressure > bar : min. 3.5
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2245
Timing device
travel mm :
> mm : (9.9...11.9)
2nd speed 1/min : 2000
Checkbk. volt. mV : 3890
Timing device
travel mm : 11.5...12.9
> mm : (11.4...13.0)
3rd speed 1/min : 1400
Checkbk. volt. mV : 1475
Timing device
travel mm : max. 0.5
> mm : (max. 0.8)
Solenoid valve
Start of
injection, volts : 12
4.th speed 1/min : 300
Checkbk. volt. mV : 2245
Timing device
travel mm : 8.9...12.1
> mm : (8.5...12.5)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3890
Measuring
temperature °C : 53
Overflow : 83...167
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt mV : 3890
Meßtemperatur °C : 53
Fuel delivery cm³/ : 48.2...51.2
> 1000s : (47.9...51.5)
Dispersion cm³/ : 2.5
> 1000s. : (2.5)

2nd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (37.7...40.3)
Dispersion cm³/ :
> 1000s : (2.5)

3rd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2245
Measuring
temperature °C : 57
Fuel delivery cm³/ : 36.7...39.7
> 1000s : (35.9...40.5)
Dispersion cm³/ : 3.0
> 1000s : (3.0)

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 1600
Meßtemperatur °C : 57
Fuel delivery cm³/ : 11.2...16.8
> 1000s : (11.0...17.0)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 4.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2230
Measuring
temperature °C : 61
Fuel delivery cm³/ : 32.4...44.4
> 1000s : (30.4...46.4)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 750
Checkbk. volt mV : 2480
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	:	
KF	mm	:	6.2...6.6
SVS max.	mm	:	
FH	mm	:	
TS		:	1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : Chrysler
 Date of manufacture :
 Edition : 24.01.1997
 Replaces :
 Test oil : ISO 4113

 Injection pump : VE4/10E2100L694-1

 Type No. : 0 460 404 963
 Customer Ident.No. :

 Customer-specific details
 Customer : Chrysler

 Engine : 425 CLIEE

 Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

 Calibrating nozzle-
 holder assembly > : 1 688 901 022

 Opening
 pressure > bar : 130...133

 Test pressure line : 1 680 750 073

 Outer diameter : 6.00
 x wall thickness > : 2.00
 x length > mm : 450

 Overflow valve : 2 467 413 018

 Test line : 0 986 612 445
 (fuel-delivery actuator)

 Test line : 1 687 011 208
 (solenoid valve start
 of injection) : (Test cable set)

Actuator
 Connections 8 and 9
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 8 and
 ground, Mohms min. : 1.0
 Connections 9 and
 ground, Mohms min. : 1.0
 Connections 2 and 8
 Mohms min. : 1.0
 Connections 7 and 9
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 kohms : 4.9...6.5
 Connections 3 and 2
 kohms : 4.9...6.5
 Connections 1 and 3
 kohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000
Checkbk. volt. : 3100
mV : 3100
Setting value, bar : 6.4...7.8

Timing device travel:

Speed 1/min : 1000
Checkbk. volt : 3100
mV : 3100
Setting value, mm : 6.9...7.1

Full-load delivery :

Speed 1/min : 1250
Checkbk. volt : 2270
mV : 2270
Fuel delivery cm³/
> 1000s : 30.6...31.0
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt : 3100
mV : 3100
Supply pump
pressure > bar : 8.0...9.4
> bar :

2st speed 1/min : 500
Checkbk. volt : 3100
mV : 3100
Supply pump
pressure > bar : 6.0...7.4
> bar :

3st speed 1/min : 150
Checkbk. volt : 3680
mV : 3680
Supply pump
pressure > bar : min. 3.5
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3100
Timing device
travel mm : 6.9...7.1
> mm : (5.0...7.0)

2nd speed 1/min : 1000
Checkbk. volt. mV : 3100
Timing device
travel mm :
> mm : (6.1...7.9)

3rd speed 1/min : 1500
Checkbk. volt. mV : 1680
Timing device
travel mm : 0.0...0.5
> mm : (0.0...1.5)

Solenoid valve

Start of
injection, volts : 12

Overflow at overflow valve:

Speed 1/min : 2100
Checkbk. volt. mV : 3100
Overflow : 56...167
> cm³/10s :

Fuel delivery variations:

1. Speed 1/min : 2100
 Checkbk. volt mV : 3100
 Fuel delivery cm³/ : 63.5...66.5
 > 1000s : (63.0...67.0)
 Dispersion cm³/ :
 > 1000s. :

2. Speed 1/min : 1250
 Checkbk. volt mV : 2270
 Fuel delivery cm³/ :
 > 1000s : (29.5...32.1)
 Dispersion cm³/ :
 > 1000s : (3.0)

3. Speed 1/min : 1000
 Checkbk. volt mV : 3100
 Fuel delivery cm³/ : 67.7...69.7
 > 1000s : (66.2...70.2)
 Dispersion cm³/ : 2.0
 > 1000s :

4. Speed 1/min : 500
 Checkbk. volt mV : 2660
 Fuel delivery cm³/ : 43.4...46.4
 > 1000s : (42.9...46.9)
 Dispersion cm³/ : 2.0
 > 1000s :

Idle delivery:

Speed 1/min : 400
 Checkbk. volt mV : 2000
 Fuel delivery cm³/ : 12.1...15.5
 > 1000s : (11.5...16.1)

Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 2.0
 > 1000s : (3.0)

Starting fuel delivery:
 Speed 1/min : 100
 Checkbk. volt mV : 3680
 Fuel delivery cm³/ :
 > 1000s : 72.0...82.0

Solenoid valve
 Start of
 injection, volts : 12

Stop test:
 Speed 1/min.: 2100
 Checkbk. volt mV : 3100
 ELAB volts : 0
 Fuel delivery cm³/ : 3.0
 max. 1000s :

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 14.02.1997
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R640-3
 Type No. : 0 460 404 964
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 SDI EDC
 Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40
 Calibrating nozzle-holder assembly > : 1 688 901 114
 Opening pressure > bar : 207...210
 Test pressure line : 1 680 750 085
 Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350
 Overflow valve : 2 467 413 018
 Test line (fuel-delivery actuator) : 0 986 612 439 : (KDEP 1865/10)
 Test line (solenoid valve start of injection) : 0 986 611 983 : (KDEP 1190)

TEST PRECONDITIONS

Test oil return temp. > °C with thermometer : 55
 Test oil supply temperature > °C : 42...47
 Hold-up revolutions >1/min : 1200
 Feedback voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and ground, Mohms min. : 1.0
 Connections 6 and ground, Mohms min. : 1.0
 Connections 3 and 5 Mohms min. : 1.0
 Connections 6 and 7 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2 Ohms : 4.9...6.5
 Connections 2 and 3 Ohms : 4.9...6.5
 Connections 1 and 3 Ohms : 9.8...13.0

Connections 1 and ground, Mohms min. : 1.0
 Connections 2 and ground, Mohms min. : 1.0
 Connections 3 and ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and ground, Mohms min. : 1.0
 Connections 7 and ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2360
Setting value, bar : 5.6...7.0

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2360
Setting value, mm : 10.6...10.8

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt
mV : 2550
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.6...35.0
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt
mV : 3370
Supply pump
pressure > bar : 8.3...9.7
> bar : (8.2...9.8)

2st speed 1/min : 300
Checkbk. volt
mV : 2360
Supply pump
pressure > bar : 5.2...6.8
> bar : (5.1...6.9)

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2360
Timing device
travel mm :
> mm : (9.7...11.7)
2nd speed 1/min : 2100
Checkbk. volt. mV : 3370
Timing device
travel mm : 11.5...12.9
> mm : (11.4...13.0)
3rd speed 1/min : 2100
Checkbk. volt. mV : 1400
Timing device
travel mm : max. 3.2
> mm : (max. 4.0)
Solenoid valve
Start of
injection, volts : 12
4.th speed 1/min : 300
Checkbk. volt. mV : 2360
Timing device
travel mm : 8.4...11.2
> mm : (8.2...11.4)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt. mV : 3370
Measuring
temperature °C : 53
Overflow : 109...164
> cm³/10s : (82...192)

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2100
 Checkbk. volt mV : 3370
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 36.2...38.2
 > 1000s : (35.9...39.5)
 Dispersion cm³/ : 2.5
 > 1000s. : (2.5)

2nd temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 800
 Checkbk. volt mV : 2550
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (33.5...36.1)
 Dispersion cm³/ :
 > 1000s : (3.0)

3rd temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2360
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 35.6...38.6
 > 1000s : (35.3...38.9)
 Dispersion cm³/ : 3.0
 > 1000s : (3.0)

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 400
 Checkbk. volt mV : 1640
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 6.0...11.0
 > 1000s : (5.5...11.5)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 3.0
 > 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2730
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 42.0...54.0
 > 1000s : (40.0...56.0)
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:

Speed 1/min : 750
 Checkbk. volt mV : 3650
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0
 Start of

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:

High-pressure compressor sensor
 Testing only possible with ballast
 EPS 910

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	: 6.2...6.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : Nissan
 Date of manufacture :
 Edition : 24.03.1997
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2200L736
 Type No. : 0 460 404 965
 Customer Ident.No. :

Customer-specific details
 Customer : Nissan

Engine : CD 20 T

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 022

Opening
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00
 x wall thickness > : 2.00
 x length > mm : 450

Overflow valve :

Overflow valve :

Test line : 0 986 612 442
 (fuel-delivery actuator)

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 3
 kohms : 4.9...6.5
 Connections 2 and 3
 kohms : 4.9...6.5
 Connections 1 and 2
 kohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 1050
Checkbk. volt.
mV : 2860
Setting value, bar : 8.5...8.7

Timing device travel:
Speed 1/min : 1050
Checkbk. volt
mV : 2860
Setting value, mm : 11.6...12.6

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 1500
Checkbk. volt
mV : 2250
Fuel delivery cm³/
> 1000s : 23.2...23.6
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 2915
Supply pump
pressure > bar : 9.6...10.6
> bar : (9.4...10.8)

2st speed 1/min : 1050
Checkbk. volt
mV : 2860
Supply pump
pressure > bar :
> bar : (7.9...9.3)

3st speed 1/min : 600
Checkbk. volt
mV : 2610
Supply pump
pressure > bar : 7.5...8.5
> bar : (7.3...8.7)

4st speed 1/min : 200
Checkbk. volt
mV : 2570
Supply pump
pressure > bar : 5.2...6.8
> bar : (4.9...7.1)

Timing device variations:

1st speed 1/min : 600
Checkbk. volt. mV : 2580
Timing device
travel mm : 10.6...12.6
> mm : (9.1...14.1)

2nd speed 1/min : 1050
Checkbk. volt. mV : 2860
Timing device
travel mm :
> mm : (11.3...12.9)

3rd speed 1/min : 1050
Checkbk. volt. mV : 1850
Timing device
travel mm : max. 0.4
> mm : (max. 0.6)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 1500
Checkbk. volt. mV : 2960
Timing device
travel mm : 12.0...12.6
> mm : (11.3...13.3)

5.th speed 1/min : 2000
Checkbk. volt. mV : 2915
Timing device
travel mm : 11.9...12.7
> mm : (11.5...13.1)

6.th speed 1/min : 2200
Checkbk. volt. mV : 1620
Timing device
travel mm : max. 1.5
> mm : (max. 2.0)

Solenoid valve
Start of
injection, volts : 12

7.th speed 1/min : 600
Checkbk. volt. mV : 2580
Timing device
travel mm : 10.6...12.6
> mm : (9.1...13.1)

Overflow at overflow valve:

Speed 1/min : 2200
Checkbk. volt. mV : 2910
Overflow : 125...208
> cm³/10s :

Fuel delivery variations:

1. Speed 1/min : 2000
Checkbk. volt mV : 2915
Fuel delivery cm³/ : 51.0...54.4
> 1000s : (50.2...55.2)
Dispersion cm³/ : 2.5
> 1000s. :

2. Speed 1/min : 1600
Checkbk. volt mV : 2580
Fuel delivery cm³/ : 37.2...39.6
> 1000s : (36.4...40.4)
Dispersion cm³/ : 2.0
> 1000s :

3. Speed 1/min : 1200
Checkbk. volt mV : 2980
Fuel delivery cm³/ : 54.5...57.3
> 1000s : (53.4...58.3)
Dispersion cm³/ : 2.0
> 1000s :

4. Speed 1/min : 1200
Checkbk. volt mV : 2250
Fuel delivery cm³/ :
> 1000s : (21.6...25.2)
Dispersion cm³/ :
> 1000s : (3.0)

5. Speed 1/min : 600
Checkbk. volt mV : 2610
Fuel delivery cm³/ : 34.6...38.0
> 1000s : (33.8...40.8)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:

Speed 1/min : 400
Checkbk. volt mV : 2190
Fuel delivery cm³/ : 10.4...14.4
> 1000s : (9.4...15.4)

Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 2.0
> 1000s : (3.0)

Starting fuel delivery:
Speed 1/min : 100
Checkbk. volt mV : 3550
Fuel delivery cm³/ : 53.9...65.9
> 1000s : (50.9...68.9)

Solenoid valve
Start of
injection, volts : 12

Stop test:
Speed 1/min : 1500
Checkbk. volt mV : 4000
ELAB volts : 0
Fuel delivery cm³/ : 2.5
max. 1000s :

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 08.10.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R728
 Type No. : 0 460 404 966
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 SDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444
 (fuel-delivery actuator)

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator

Connections 5 and 6

Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor

Sensor coils

Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel

Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection

Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 2360
Setting value, bar : 5.9...6.7

Timing device travel:

Speed 1/min : 500
Checkbk. volt
mV : 2360
Setting value, mm : 10.6...10.8

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt
mV : 2550
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.6...35.0
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt
mV : 3370
Supply pump
pressure > bar : 8.4...9.6
> bar : (8.2...9.8)

2st speed 1/min : 300
Checkbk. volt
mV : 2360
Supply pump
pressure > bar : 5.3...6.7
> bar : (5.1...6.9)

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2360
Timing device
travel mm :
> mm : (9.7...11.7)

2nd speed 1/min : 2100
Checkbk. volt. mV : 3370
Timing device
travel mm : 11.8...12.6
> mm : (11.4...13.0)

3rd speed 1/min : 2100
Checkbk. volt. mV : 1400
Timing device
travel mm : max. 3.2
> mm : (max. 4.0)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 300
Checkbk. volt. mV : 2360
Timing device
travel mm : 8.6...11.0
> mm : (8.2...11.4)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt. mV : 3370
Measuring
temperature °C : 53
Overflow : 111...167
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt mV : 3370
Meßtemperatur °C : 53
Fuel delivery cm³/ : 36.5...38.9
> 1000s : (35.9...39.5)
Dispersion cm³/ : 2.5
> 1000s. : (2.5)

2nd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt mV : 2550
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (33.5...36.1)
Dispersion cm³/ :
> 1000s : (2.5)

3rd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2360
Measuring
temperature °C : 57
Fuel delivery cm³/ : 35.6...38.6
> 1000s : (35.3...38.9)
Dispersion cm³/ : 3.0
> 1000s : (3.0)

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1640
Meßtemperatur °C : 57
Fuel delivery cm³/ : 6.5...10.5
> 1000s : (5.5...11.5)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2730
Measuring
temperature °C : 61
Fuel delivery cm³/ : 43.0...53.0
> 1000s : (40.0...56.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 750
Checkbk. volt mV : 3650
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	: 6.2...6.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 22.10.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2100R701-3
 Type No. : 0 460 404 967
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.7 SDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444
 (fuel-delivery actuator)

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator

Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils

Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2

Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2510
Setting value, bar : 7.8...8.6

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2510
Setting value, mm : 9.6...9.8

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt
mV : 2650
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.8...35.2
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt
mV : 3330
Supply pump
pressure > bar : 10.4...11.4
> bar :

2st speed 1/min : 300
Checkbk. volt
mV : 2510
Supply pump
pressure > bar : 6.8...8.2
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2510
Timing device
travel mm :
> mm : (8.7...10.7)

2nd speed 1/min : 2100
Checkbk. volt. mV : 3330
Timing device
travel mm : 11.8...12.8
> mm : (11.5...13.1)

3rd speed 1/min : 2100
Checkbk. volt. mV : 1440
Timing device
travel mm : max. 3.0
> mm :

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 300
Checkbk. volt. mV : 2510
Timing device
travel mm : 6.5...10.5
> mm : (5.1...11.9)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2100
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt. mV : 3300
Measuring
temperature °C : 53
Overflow : 116...200
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2100
 Checkbk. volt mV : 3330
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 36.3...38.7
 > 1000s : (35.7...39.3)
 Dispersion cm³/ : 3.0
 > 1000s :

2nd temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 1100
 Checkbk. volt mV : 2880
 Measuring
 temperature °C : 53
 Fuel delivery cm³/ : 34.9...37.3
 > 1000s : (34.3...37.9)
 Dispersion cm³/ :
 > 1000s :

3rd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 800
 Checkbk. volt mV : 2650
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (33.7...36.3)
 Dispersion cm³/ :
 > 1000s : (2.5)

4th temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2510
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 35.5...38.1
 > 1000s : (34.8...38.8)
 Dispersion cm³/ : 3.0
 > 1000s :

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 400
 Checkbk. volt mV : 1820
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 5.6...9.6
 > 1000s : (4.6...10.6)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 3.0
 > 1000s : (4.0)

Starting fuel delivery:
 1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2820
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 43.0...53.0
 > 1000s : (40.0...56.0)
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:
 Speed 1/min : 1000
 Checkbk. volt mV : 3330
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0
 Start of

Shutoff solenoid:
 Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:
 High-pressure compressor sensor
 Testing only possible with ballast
 EPS 910

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 11.10.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2075R696-3
 Type No. : 0 460 404 968
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 TDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 638 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444
 (fuel-delivery actuator)

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt. : 2560
mV : 2560
Setting value, bar : 8.4...9.2

Timing device travel:

Speed 1/min : 500
Checkbk. volt. : 2510
mV : 2510
Setting value, mm : 10.1...10.3

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt. : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt. : 2480
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.7...35.1
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt. : 3890
mV : 3890
Supply pump
pressure > bar : 10.9...11.9
> bar :

2st speed 1/min : 300
Checkbk. volt. : 2560
mV : 2560
Supply pump
pressure > bar : 6.6...8.0
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2510
Timing device
travel mm :
> mm : (9.2...11.2)
2nd speed 1/min : 2050
Checkbk. volt. mV : 3330
Timing device
travel mm : 11.8...12.8
> mm : (11.5...13.1)
3rd speed 1/min : 1500
Checkbk. volt. mV : 1500
Timing device
travel mm : max. 0.5
> mm : (max. 0.8)
Solenoid valve
Start of
injection, volts : 12

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2050
Checkbk. volt. mV : 3890
Measuring
temperature °C : 53
Overflow : 121...208
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2050
Checkbk. volt mV : 290
Meßtemperatur °C :
Fuel delivery cm³/ : 2.5...51.9
> 1000s : (48,9...52.5)
Dispersion cm³/ : 3.0
> 1000s. :

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (33.6...36.2)
Dispersion cm³/ :
> 1000s : (2.5)

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2560
Measuring
temperature °C : 57
Fuel delivery cm³/ : 41.9...44.5
> 1000s : (41.2...45.2)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:

1st temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1800
Meßtemperatur °C : 57
Fuel delivery cm³/ : 7.7...11.7
> 1000s : (6.7...12.7)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2420
Measuring
temperature °C : 61
Fuel delivery cm³/ : 35.7...45.7
> 1000s : (32.7...48.7)

Solenoid valve

Start of
injection, volts : 12

Stop test:

Speed 1/min : 1000
Checkbk. volt mV : 4000
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K mm :
KF mm : 8.2...8.6
SVS max. mm :
FH mm :
TS : 1 467 010 495

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : Audi
 Date of manufacture :
 Edition : 11.10.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2075R638-3
 Type No. : 0 460 404 969
 Customer Ident.No. :

Customer-specific details
 Customer : Audi

Engine : 1.9 TDI

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery
 actuator) : (KDEP 1865/10)

Test line : 0 986 611 983
 Solenoid valve
 start of injection): (KDEP 1190)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 2560
Setting value, bar : 8.4...9.2

Timing device travel:

Speed 1/min : 500
Checkbk. volt
mV : 2510
Setting value, mm : 10.1...10.3

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 34.7...35.1
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2050
Checkbk. volt
mV : 3890
Supply pump
pressure > bar : 10.9...11.9
> bar :

2st speed 1/min : 300
Checkbk. volt
mV : 2560
Supply pump
pressure > bar : 6.6...8.0
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2510
Timing device
travel mm :
> mm : (9.2...11.2)
2nd speed 1/min : 2050
Checkbk. volt. mV : 3330
Timing device
travel mm : 11.8...12.8
> mm : (11.5...13.1)
3rd speed 1/min : 1500
Checkbk. volt. mV : 1500
Timing device
travel mm : max. 0.5
> mm : (max. 0.8)
Solenoid valve
Start of
injection, volts : 12

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2050
Checkbk. volt. mV : 3890
Measuring
temperature °C : 53
Overflow : 121...208
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2050
Checkbk. volt mV : 3890
Meßtemperatur °C : 53
Fuel delivery cm³/ : 49.5...51.9
> 1000s : (48.9...52.5)
Dispersion cm³/ : 3.0
> 1000s. :

2nd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (33.6...36.2)
Dispersion cm³/ :
> 1000s : (2.5)

3rd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2560
Measuring
temperature °C : 57
Fuel delivery cm³/ : 41.9...44.5
> 1000s : (41.2...45.2)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1800
Meßtemperatur °C : 57
Fuel delivery cm³/ : 7.7...11.7
> 1000s : (6.7...12.7)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2420
Measuring
temperature °C : 61
Fuel delivery cm³/ : 35.7...45.7
> 1000s : (32.7...48.7)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 1000
Checkbk. volt mV : 4000
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	: 3.6...3.8
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

K7

k7

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 18.02.1997
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R590-3
 Type No. : G 460 404 970
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 TDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery
 actuator) : (KDEP 1865/10)

Test line : 0 986 611 983
 (solenoid valve
 start of injection): (KDEP 1190)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 2450
Setting value, bar : 7.3...8.7

Timing device travel:

Speed 1/min : 500
Checkbk. volt
mV : 2450
Setting value, mm : 9.7...9.9

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2420
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 37.2...37.6
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt
mV : 4000
Supply pump
pressure > bar : 9.7...11.1
> bar : (9.6...11.2)

2st speed 1/min : 300
Checkbk. volt
mV : 2450
Supply pump
pressure > bar : 6.6...8.1
> bar : (6.4...8.2)

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2450
Timing device
travel mm :
> mm : (8.8...10.8)
2nd speed 1/min : 2000
Checkbk. volt. mV : 4000
Timing device
travel mm : 11.2...12.9
> mm : (11.4...13.0)
3rd speed 1/min : 2100
Checkbk. volt. mV : 1310
Timing device
travel mm : max. 0.5
> mm : (max. 0.8)
Solenoid valve
Start of
injection, volts : 12
4.th speed 1/min : 300
Checkbk. volt. mV : 2450
Timing device
travel mm : 6.5...9.7
> mm : (6.1...10.1)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt. mV : 4000
Measuring
temperature °C : 53
Overflow : 97...208
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2000
 Checkbk. volt mV : 4000
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 54.2...57.2
 > 1000s : (53.9...57.5)
 Dispersion cm³/ : 2.5
 > 1000s : (2.5)

2nd temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2420
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (36.1...38.7)
 Dispersion cm³/ :
 > 1000s : (2.5)

3rd temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2450
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 43.6...46.6
 > 1000s : (42.8...47.4)
 Dispersion cm³/ : 3.0
 > 1000s : (3.0)

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 400
 Checkbk. volt mV : 1550
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 6.8...11.8
 > 1000s : (6.3...12.3)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 4.0
 > 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2310
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 36.0...48.0
 > 1000s : (34.0...50.0)
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:

Speed 1/min : 750
 Checkbk. volt mV : 3650
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0
 Start of

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:

High-pressure compressor sensor
 Testing only possible with ballast
 EPS 910

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	: 6.2...6.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 28.10.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2250R510-3
 Type No. : 0 460 404 971
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 TDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 439
 (fuel-delivery
 actuator) : (KDEP 1865/10)

Test line : 0 986 611 983
 (solenoid valve
 start of injection) : (KDEP 1190)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 2245
Setting value, bar : 6.0...7.4

Timing device travel:

Speed 1/min : 500
Checkbk. volt
mV : 2245
Setting value, mm : 10.7...10.9

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 38.8...39.2
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 3890
Supply pump
pressure > bar : 8.2...9.6
> bar : (8.1...9.7)

2st speed 1/min : 150
Checkbk. volt
mV : 2230
Supply pump
pressure > bar : min. 3.5
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2245
Timing device
travel mm :
> mm : (8.6...11.8)

2nd speed 1/min : 2000
Checkbk. volt. mV : 3890
Timing device
travel mm : 11.5...12.9
> mm : (11.6...13.0)

3rd speed 1/min : 1400
Checkbk. volt. mV : 1475
Timing device
travel mm : max. 0.5
> mm : (max. 0.8)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 300
Checkbk. volt. mV : 2245
Timing device
travel mm : 8.8...11.6
> mm : (8.6...11.8)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3890
Measuring
temperature °C : 53
Overflow : 97...180
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2000
 Checkbk. volt mV : 3890
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 48.2...51.2
 > 1000s : (47.9...51.5)
 Dispersion cm³/ : 2.5
 > 1000s : (2.5)

2nd temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2480
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (37.7...40.3)
 Dispersion cm³/ :
 > 1000s : (2.5)

3rd temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2245
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 36.8...39.8
 > 1000s : (36.0...40.6)
 Dispersion cm³/ : 3.0
 > 1000s : (3.0)

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 1600
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 11.7...17.3
 > 1000s : (11.5...17.5)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 3.0
 > 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2230
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 30.5...42.5
 > 1000s : (28.5...44.5)
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:

Speed 1/min : 750
 Checkbk. volt mV : 2480
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0
 Start of

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:

High-pressure compressor sensor
 Testing only possible with ballast
 EPS 910

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	: 6.2...6.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 410

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : Skoda
 Date of manufacture :
 Edition : 03.03.1997
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2100R724
 Type No. : 0 460 404 972
 Customer Ident.No. :

Customer-specific details
 Customer : Skoda

Engine : 1.9 SDI EDC

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444
 (fuel-delivery actuator)

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 500
Checkbk. volt.
mV : 2510
Setting value, bar : 7.3...8.7

Timing device travel:

Speed 1/min : 500
Checkbk. volt
mV : 2510
Setting value, mm : 9.7...9.9

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt
mV : 2650
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 36.2...36.6
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2100
Checkbk. volt
mV : 3330
Supply pump
pressure > bar : 10.0...11.4
> bar :

2st speed 1/min : 300
Checkbk. volt
mV : 2510
Supply pump
pressure > bar : 6.3...8.7
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2510
Timing device
travel mm :
> mm : (8.8...10.8)
2nd speed 1/min : 2100
Checkbk. volt. mV : 3330
Timing device
travel mm : 11.6...13.0
> mm : (11.5...13.1)
3rd speed 1/min : 2100
Checkbk. volt. mV : 1600
Timing device
travel mm : max. 3.0
> mm : (max. 3.0)
Solenoid valve
Start of
injection, volts : 12
4.th speed 1/min : 300
Checkbk. volt. mV : 2510
Timing device
travel mm : 6.0...11.0
> mm : (5.1...11.9)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt. mV : 3330
Measuring
temperature °C : 53
Overflow : 125...208
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt mV : 3330
Meßtemperatur °C : 53
Fuel delivery cm³/ : 36.3...39.3
> 1000s : (36.0...39.6)
Dispersion cm³/ : 3.0
> 1000s. : (3.0)

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 800
Checkbk. volt mV : 2550
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (35.1...37.7)
Dispersion cm³/ :
> 1000s : (2.5)

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2510
Measuring
temperature °C : 57
Fuel delivery cm³/ : 36.9...39.9
> 1000s : (36.4...40.4)
Dispersion cm³/ : 3.0
> 1000s : (3.0)

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 400
Checkbk. volt mV : 1820
Meßtemperatur °C : 57
Fuel delivery cm³/ : 7.3...12.3
> 1000s : (6.8...12.8)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2820
Measuring
temperature °C : 61
Fuel delivery cm³/ : 42.0...56.0
> 1000s : (41.0...57.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 1000
Checkbk. volt mV : 3330
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0
Start of

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : ROW
 Date of manufacture :
 Edition : 06.12.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2100L720
 Type No. : 0 460 404 973
 Customer Ident.No. :

Customer-specific details
 Customer : ROW

Engine : TCIE Job 3

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 0 986 612 437

Test line :
 (fuel-delivery actuator)

Test line : 0 986 611 438
 (solenoid valve
 start of injection)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohm : 4.9...6.5
 Connections 2 and 3
 Ohm : 4.9...6.5
 Connections 1 and 3
 Ohm : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4,0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 700
Checkbk. volt.
mV : 2200
Setting value, bar : 8.1...9.5

Timing device travel:

Speed 1/min : 700
Checkbk. volt
mV : 2200
Setting value, mm : 10.6...10.8

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 700
Checkbk. volt
mV : 2200
Measuring
temperature °C : 57
Fuel delivery $\text{cm}^3/$
> 1000s : 29.2...30.2
Dispersion $\text{cm}^3/$: 2.5
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 3880
Supply pump
pressure > bar : 10.0...11.4
> bar :

2st speed 1/min : 300
Checkbk. volt
mV : 2420
Supply pump
pressure > bar : 6.2...8.6
> bar :

Timing device variations:

1st speed 1/min : 400
Checkbk. volt. mV : 2420
Timing device
travel mm : 7.9...11.5
> mm : (7.2...12.2)

2nd speed 1/min : 2100
Checkbk. volt. mV : 3880
Timing device
travel mm : 11.8...12.8
> mm : (11.7...12.9)

3rd speed 1/min : 1500
Checkbk. volt. mV : 1460
Timing device
travel mm : max. 1.0
> mm : (max. 1.5)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 700
Checkbk. volt. mV : 2200
Timing device
travel mm :
> mm : (9.7...11.7)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3880
Measuring
temperature °C : 53
Overflow : 111...194
> $\text{cm}^3/10$:

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2100
Checkbk. volt mV : 3880
Meßtemperatur °C : 53
Fuel delivery cm³/ : 52.9...55.9
> 1000s : (52.4...56.4)
Dispersion cm³/ : 2.5
> 1000s. : (3.0)

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 700
Checkbk. volt mV : 2200
Measuring
temperature °C : 56
Fuel delivery cm³/ :
> 1000s : (28.5...31.5)
Dispersion cm³/ :
> 1000s : (3.0)

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2420
Measuring
temperature °C : 57
Fuel delivery cm³/ : 41.4...44.4
> 1000s : (40.9...44.9)
Dispersion cm³/ : 3.0
> 1000s : (3.0)

Idle delivery:

1st temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 450
Checkbk. volt mV : 1950
Meßtemperatur °C : 57
Fuel delivery cm³/ : 18.0...23.0
> 1000s : (17.5...23.5)
Dispersion cm³/ : 3.0
> 1000s. : (4.0)

Solenoid valve

Start of
injection, volts : 12
Dispersion cm³/ : 4.0
> 1000s :

Starting fuel delivery:

1st temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2570
Measuring
temperature °C : 61
Fuel delivery cm³/ : 44.0...60.0
> 1000s : (41.0...63.0)

Solenoid valve

Start of
injection, volts : 12

Stop test:

Speed 1/min : 1000
Checkbk. volt mV : 2250
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:
High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description			
K	mm	:	3,6..3,8
KF	mm	:	
SVS max.	mm	:	
FH	mm	:	
TS		:	2 467 010 004

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : Nissan
 Date of manufacture :
 Edition : 02.10.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/10E2100L715
 Type No. : 0 460 404 974
 Customer Ident.No. :

Customer-specific details
 Customer : Nissan

Engine : TD 27 Ti

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 022

Opening
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00
 x wall thickness > : 2.00
 x length > mm : 450

Overflow valve :

Overflow valve :

Test line : 0 986 612 442
 (fuel-delivery actuator)

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 3
 ohms : 4.9...6.5
 Connections 2 and 3
 ohms : 4.9...6.5
 Connections 1 and 2
 ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1050
Checkbk. volt.
mV : 3080
Setting value, bar : 7.5...8.3

Timing device travel:

Speed 1/min : 1050
Checkbk. volt
mV : 3080
Setting value, mm : 10.7...10.9

Full-load delivery :

Speed 1/min : 1250
Checkbk. volt
mV : 2170
Fuel delivery cm³/
> 1000s : 28.3...28.7
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2200
Checkbk. volt
mV : 2810
Supply pump
pressure > bar : 9.4...10.8
> bar : (9.4...10.8)

2st speed 1/min : 1050
Checkbk. volt
mV : 3080
Supply pump
pressure > bar :
> bar : (7.2...8.6)

3st speed 1/min : 500
Checkbk. volt
mV : 2640
Supply pump
pressure > bar : 6.7...7.7
> bar : (6.4...8.0)

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 2640
Timing device
travel mm : 6.6...10.4
> mm : (6.1...11.1)

3rd speed 1/min : 1050
Checkbk. volt. mV : 1750

Timing device
travel mm : max. 0.4
> mm : (max. 0.6)

Solenoid valve

Start of
injection, volts : 12

4nd speed 1/min : 2200
Checkbk. volt. mV : 2810

Timing device
travel mm : 11,7...12,9
> mm : (11,5...13,1)

Overflow at overflow valve:

Speed 1/min : 2200
Checkbk. volt. mV : 2810
Overflow : 111...222
> cm³/10s :

Fuel delivery variations:

1. Speed 1/min : 2200
Checkbk. volt mV : 2810
Fuel delivery cm³/ : 54.1...56.7
> 1000s : (52.9...57.9)
Dispersion cm³/ : 2.5
> 1000s. :

2. Speed 1/min : 1250
Checkbk. volt mV : 2170
Fuel delivery cm³/ :
> 1000s : (26.7...30.3)
Dispersion cm³/ :
> 1000s :

3. Speed 1/min : 500
Checkbk. volt mV : 2640
Fuel delivery cm³/ : 48.3...52.1
> 1000s : (47.7...52.7)
Dispersion cm³/ :
> 1000s :

Idle delivery:

Speed 1/min : 400
Checkbk. volt mV : 1870
Fuel delivery cm³/ : 7.0...11.6
> 1000s : (6.3...12.3)

Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 2.0
> 1000s : (3.0)

Starting fuel delivery:
Speed 1/min : 100
Checkbk. volt mV : 3300
Fuel delivery cm³/ : 69.5...81.5
> 1000s : (66.5...84.5)

Solenoid valve
Start of
injection, volts : 12

Stop test:
Speed 1/min : 1500
Checkbk. volt mV : 4000
ELAB volts : 0
Fuel delivery cm³/ : max. 3.0
max. 1000s : (max. 3.0)

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : BMW
 Date of manufacture :
 Edition : 29.09.1993
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE6/10E2400R575
 Type No. : 0 460 406 993
 Customer Ident.No. :

Customer-specific details
 Customer : BMW

Engine : M51

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar: 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 022

Opening
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6.00
 x wall thickness > : 2.00
 x length > mm : 450

Test line : 0 986 612 430
 (fuel-delivery actuator)

Test line : 0 986 612 435
 (solenoid valve
 start of injection)

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

Control-collar travel sensor
 Test temperature :
 15°...70°C
 Connections 1 and 3
 kohms : 0,5...2,0
 Connections 2 and 3
 kohms : 1,0...3,0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1500
Checkbk. volt.
mV : 3000
Setting value, bar : 7.2...7.8

Timing device travel:

Speed 1/min : 1500
Checkbk. volt
mV : 3000
Setting value, mm : 8.4...8.8

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 1500
Checkbk. volt
mV : 3000
Fuel delivery cm³/
> 1000s : 44.4...44.8
Dispersion cm³/
> 1000s : 2.0

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2400
Checkbk. volt
mV : 3000
Supply pump
pressure > bar : 8.6...9.4
> bar : (8.8...9.5)

2st speed 1/min : 350
Checkbk. volt
mV : 3850
Supply pump
pressure > bar : 5.6...6.2
> bar : (5.4...6.4)

Timing device variations:

1st speed 1/min : 350
Checkbk. volt. mV : 3850
Timing device
travel mm : 5.0...6.4
> mm : (4.7...6.7)

2nd speed 1/min : 1500
Checkbk. volt. mV : 3000
Timing device
travel mm :
> mm : (7.9...9.3)

3rd speed 1/min : 1500
Checkbk. volt. mV : 3000
Timing device
travel mm : 0.0...0.4
> mm :

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2300
Checkbk. volt. mV : 3000
Timing device
travel mm : 9.5...10.1
> mm : (9.3...10.3)

5.th speed 1/min : 150
Checkbk. volt. mV : 3850
Timing device
travel mm : 2.7...5.1
> mm : (1.9...5.9)

Overflow at overflow valve:

Speed 1/min : 2400
Checkbk. volt. mV : 3000
Overflow : 69...180
> cm³/10s :

Fuel delivery variations:

1. Speed 1/min : 2400
 Checkbk. volt mV : 3000
 Fuel delivery cm³/ : 44.8...46.8
 > 1000s : (43.3...48.3)
 Dispersion cm³/ : 2.5
 > 1000s : (2.5)

2. Speed 1/min : 1500
 Checkbk. volt mV : 3000
 Fuel delivery cm³/ :
 > 1000s : (42.8...46.4)
 Dispersion cm³/ :
 > 1000s : (2.0)

3. Speed 1/min : 1000
 Checkbk. volt mV : 3100
 Fuel delivery cm³/ : 45.9...47.9
 > 1000s : (44.4...52.4)
 Dispersion cm³/ : 2.0
 > 1000s : (2.0)

4. Speed 1/min : 1000
 Checkbk. volt mV : 2350
 Fuel delivery cm³/ : 13.3...14.5
 > 1000s : (11.6...16.2)
 Dispersion cm³/ : 2.0
 > 1000s : (2.0)

5. Speed 1/min : 500
 Checkbk. volt mV : 3000
 Fuel delivery cm³/ : 30.2...32.2
 > 1000s : (28.7...37.7)
 Dispersion cm³/ : 2.0
 > 1000s : (2.0)

Idle delivery:

Speed 1/min : 350
 Checkbk. volt mV : 2600
 Fuel delivery cm³/ : 7.0...9.0
 > 1000s : (5.5...10.5)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 2.0
 > 1000s : (2.0)

Starting fuel delivery:
 Speed 1/min : 100
 Checkbk. volt mV : 3680
 Fuel delivery cm³/ : 33.0...45.0
 > 1000s : (30.0...48.0)
 Solenoid valve
 Dispersion cm³/ :
 > 1000s :
 Start of
 injection, volts : 12

Stop test:
 Speed 1/min : 2400
 Checkbk. volt mV : 3000
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Dimensions for mounting and setting:

Description
 K mm :
 KF mm :
 SVS max. mm :
 FH mm :
 Prestroke..mm : 0,28...0,32
 : (0,26...0,34)

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : BMW
 Date of manufacture :
 Edition : 15.10.1996
 Replaces :
 Test oil : ISO 4113

Injection pump : VE6/10E2200R515

Type No. : 0 460 406 994
 Customer Ident.No. :

Customer-specific details
 Customer : BMW

Engine : M51

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 022

Opening
 pressure > bar : 130...133

Test pressure line : 1 680 750 073

Outer diameter : 6,00
 x wall thickness > : 2.00
 x length > mm : 450

Overflow valve :

Test line : 0 986 612 430
 (fuel-delivery actuator)

Test line : 0 986 612 435
 (solenoid valve
 start of injection)

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 3
 kohms : 4.9...6.5
 Connections 2 and 3
 kohms : 4.9...6.5
 Connections 1 and 2
 kohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1500
Checkbk. volt.
mV : 2820
Setting value, bar : 7.3...8.1

Timing device travel:

Speed 1/min : 1500
Checkbk. volt
mV : 2820
Setting value, mm : 8.5...8.7

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 1500
Checkbk. volt
mV : 2820
Fuel delivery cm³/
> 1000s : 45.1...45.5
Dispersion cm³/
> 1000s : 2.0

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2400
Checkbk. volt
mV : 2520
Supply pump
pressure > bar : 8.8...9.8
> bar :

2st speed 1/min : 350
Checkbk. volt
mV : 3470
Supply pump
pressure > bar : 5.3...6.5
> bar :

Timing device variations:

1st speed 1/min : 350
Checkbk. volt. mV : 3470
Timing device
travel mm : 5.0...6.4
> mm : (4.4...7.0)

2nd speed 1/min : 1500
Checkbk. volt. mV : 2820
Timing device
travel mm :
> mm : (7.8...9.4)

3rd speed 1/min : 1500
Checkbk. volt. mV : 2820
Timing device
travel mm : 0.0...0.4
> mm :

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 2300
Checkbk. volt. mV : 2820
Timing device
travel mm : 9.5...10.1
> mm : (9.3...10.3)

5.th speed 1/min : 150
Checkbk. volt. mV : 3470
Timing device
travel mm : 2.7...5.1
> mm : (1.9...5.9)

Overflow at overflow valve:

Speed 1/min : 2400
Checkbk. volt. mV : 2820
Overflow : 69...180
> cm³/10s :

Fuel delivery variations:

1. Speed 1/min : 2400
 Checkbk. volt mV : 2820
 Fuel delivery cm³/ : 45.4...48.0
 > 1000s : (44.2...49.2)
 Dispersion cm³/ : 2.5
 > 1000s. :

2. Speed 1/min : 1500
 Checkbk. volt mV : 2820
 Fuel delivery cm³/ :
 > 1000s : (44.0...46.0)
 Dispersion cm³/ :
 > 1000s : (3.0)

3. Speed 1/min : 1000
 Checkbk. volt mV : 2910
 Fuel delivery cm³/ : 46.6...48.6
 > 1000s : (45.6...49.6)
 Dispersion cm³/ : 2.0
 > 1000s : (3.0)

4. Speed 1/min : 1000
 Checkbk. volt mV : 2170
 Fuel delivery cm³/ : 14.4...15.8
 > 1000s : (13.8...16.4)
 Dispersion cm³/ : 2.0
 > 1000s :

5. Speed 1/min : 5000
 Checkbk. volt mV : 2820
 Fuel delivery cm³/ : 30.5...33.1
 > 1000s : (29.8...33.8)
 Dispersion cm³/ : 2.0
 > 1000s :

Idle delivery:

Speed 1/min : 350
 Checkbk. volt mV : 2430
 Fuel delivery cm³/ : 8.8...11.4
 > 1000s : (7.6...12.6)

Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 2.0
 > 1000s : (3.0)

Starting fuel delivery:
 Speed 1/min : 100
 Checkbk. volt mV : 3470
 Fuel delivery cm³/ :
 > 1000s : 33.0

Solenoid valve
 Start of
 injection, volts : 12

Stop test:
 Speed 1/min : 500
 Checkbk. volt mV : 2820
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Dimensions for mounting and setting:

Description
 K mm :
 KF mm :
 SVS max. mm :
 FH mm :
 Prestroke..mm : 0,28...0,32
 : (0,26...0,34)

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 09.08.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/11E2075R712
 Type No. : 0 460 414 990
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 1.9 TDI

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444
 (fuel-delivery
 actuator) :

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 750
Checkbk. volt. : 2340
mV : 2340
Setting value, bar : 8.4...8.6

Timing device travel:

Speed 1/min : 750
Checkbk. volt : 2340
mV : 2340
Setting value, mm : 11.9...12.7

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt : 2340
mV : 2340
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 38.3...38.7
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt : 3790
mV : 3790
Supply pump
pressure > bar : 10.4...11.0
> bar :

2st speed 1/min : 300
Checkbk. volt. : 2450
mV : 2450
Supply pump
pressure > bar : 5.6...7.2
> bar :

Timing device variations:

1st speed 1/min : 400
Checkbk. volt. mV : 2450
Timing device
travel mm : 9.8...11.2
> mm : (8.0...14.0)

2nd speed 1/min : 2000
Checkbk. volt. mV : 3790
Timing device
travel mm : 11.8...12.8
> mm : (11.5...13.1)

3rd speed 1/min : 1300
Checkbk. volt. mV : 1400
Timing device
travel mm : max. 0.3
> mm : (max. 1.0)

Solenoid valve

Start of
injection, volts : 12

4.th speed 1/min : 750
Checkbk. volt. mV : 2340
Timing device
travel mm :
> mm : (11.5...13.1)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3790
Measuring
temperature °C : 53
Overflow : 133...188
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2000
 Checkbk. volt mV : 3790
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 60.3...62.7
 > 1000s : (59.7...63.3)
 Dispersion cm³/ : 3.0
 > 1000s. : (3.0)

2nd temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2340
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (37.0...40.0)
 Dispersion cm³/ :
 > 1000s : (3.0)

3rd temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 1000
 Checkbk. volt mV : 3070
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 55.8...58.2
 > 1000s : (55.2...58.8)
 Dispersion cm³/ :
 > 1000s :

4th temperature-conditioning

revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2450
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 47.2...49.8
 > 1000s : (46.5...50.5)
 Dispersion cm³/ : 3.0
 > 1000s : (3.0)

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 400
 Checkbk. volt mV : 1760
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 14.5...18.5
 > 1000s : (13.5...19.5)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 3.0
 > 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2450
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 48.0...60.0
 > 1000s : (44.0...64.0)
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:

Speed 1/min : 1200
 Checkbk. volt mV : 2340
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0
 Start of

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:

High-pressure compressor sensor
 Testing only possible with ballast
 EPS 910

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description

K	mm	:
KF	mm	:
SVS max.	mm	:
FH	mm	:
TS		: 2 467 010 004

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : ROW
 Date of manufacture :
 Edition : 15.11.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/11E2000R500-1
 Type No. : 0 460 414 991
 Customer Ident.No. :

Customer-specific details
 Customer : ROW

Engine : Gemini 3

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40
 Calibrating nozzle-holder assembly > : 1 688 901 116
 Opening pressure > bar : 207...210
 Test pressure line : 1 680 750 085
 Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve :
 Test line : 0 986 612 437
 (fuel-delivery actuator)
 Test line : 0 986 612 438
 (solenoid valve start of injection)

TEST PRECONDITIONS

Test oil return temp. > °C with thermometer : 55
 Test oil supply temperature > °C : 42...47
 Hold-up revolutions >1/min : 1200
 Feedback voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and ground, Mohms min. : 1.0
 Connections 6 and ground, Mohms min. : 1.0
 Connections 3 and 5 Mohms min. : 1.0
 Connections 6 and 7 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2 Ohm : 4.9...6.5
 Connections 2 and 3 Ohm : 4.9...6.5
 Connections 1 and 3 Ohm : 9.8...13.0

Connections 1 and ground, Mohms min. : 1.0
 Connections 2 and ground, Mohms min. : 1.0
 Connections 3 and ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and ground, Mohms min. : 1.0
 Connections 7 and ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000
Checkbk. volt. : 3500
mV : 3500
Setting value, bar : 5.8...7.2

Timing device travel:

Speed 1/min : 1000
Checkbk. volt : 3500
mV : 3500
Setting value, mm : 8.9...9.1

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt : 2430
mV : 2430
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 53.9...54.3
Dispersion cm³ / : 2.5
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt : 3500
mV : 3500
Supply pump
pressure > bar : 7.5...8.9
> bar :

2st speed 1/min : 150
Checkbk. volt : 2870
mV : 2870
Supply pump
pressure > bar : 3.5...6.5
> bar :

Timing device variations:

1st speed 1/min : 1000
Checkbk. volt. mV : 3500
Timing device
travel mm :
> mm : (8.0...10.0)

2nd speed 1/min : 2000
Checkbk. volt. mV : 3500
Timing device
travel mm : 11.8...12.8
> mm : (11.6...13.0)

3rd speed 1/min : 1000
Checkbk. volt. mV : 1560
Timing device
travel mm : max. 3.0
> mm : (max. 3.0)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 500
Checkbk. volt. mV : 2870
Timing device
travel mm : 6.1...8.5
> mm : (5.8...8.8)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3500
Measuring
temperature °C : 53
Overflow : 97...153
> cm³/10s:

Fuel delivery variations:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt mV : 3500
Meßtemperatur °C : 53
Fuel delivery cm³/ : 67.5...70.5
> 1000s :
Dispersion cm³/ : 2.5
> 1000s. :

2nd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1000
Checkbk. volt mV : 3200
Measuring
temperature °C : 56
Fuel delivery cm³/ : 77.9...80.9
> 1000s : (77.4...81.4)
Dispersion cm³/ : 2.5
> 1000s :

3rd temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2430
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (52.4...55.8)
Dispersion cm³/ :
> 1000s : (3.0)

4th temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2870
Measuring
temperature °C : 57
Fuel delivery cm³/ : 85.4...89.0
> 1000s : (84.9...89.5)
Dispersion cm³/ : 2.5
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 1750
Meßtemperatur °C : 57
Fuel delivery cm³/ : 19.9...24.9
> 1000s : (19.4...25.4)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 3130
Measuring
temperature °C : 61
Fuel delivery cm³/ : 83.0...99.0
> 1000s : (80.0...102.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:
Speed 1/min : 1200
Checkbk. volt mV : 3000
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:
Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:
High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	: 6.5...6.9
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 494

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : ROW
 Date of manufacture :
 Edition : 30.10.1995
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/11E2250L580-1
 Type No. : 0 460 414 992
 Customer Ident.No. :

Customer-specific details
 Customer : ROVER

Engine : TCIE

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve :

Test line : 0 986 612 437
 (fuel-delivery actuator)

Test line : 0 986 612 438
 (solenoid valve
 start of injection)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohm : 4.9...6.5
 Connections 2 and 3
 Ohm : 4.9...6.5
 Connections 1 and 3
 Ohm : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 1000
Checkbk. volt.
mV : 3400
Setting value, bar : 6.6...7.9

Timing device travel:
Speed 1/min : 1000
Checkbk. volt
mV : 3400
Setting value, mm : 7.8...8.0

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2450
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 38.4...38.8
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2250
Checkbk. volt
mV : 3400
Supply pump
pressure > bar : 8.4...9.8
> bar :

2nd speed 1/min : 500
Checkbk. volt
mV : 3400
Supply pump
pressure > bar : 6.0...7.2
> bar :

3rd speed 1/min : 150
Checkbk. volt
mV : 2560
Supply pump
pressure > bar : 3.5...10.5
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3400
Timing device
travel mm : 4.5...7.3
> mm : (3.9...7.9)

2nd speed 1/min : 2250
Checkbk. volt. mV : 3400
Timing device
travel mm : 9.4...10.2
> mm : (9.2...10.4)

3rd speed 1/min : 1500
Checkbk. volt. mV : 1650
Timing device
travel mm : max. 0.5
> mm : (max. 3.5)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 1000
Checkbk. volt. mV : 3400
Timing device
travel mm :
> mm : (6.9...8.9)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2250
Checkbk. volt. mV : 3400
Measuring
temperature °C : 53
Overflow : 108...191
> cm³/10 :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2250
Checkbk. volt mV : 3400
Meßtemperatur °C : 53
Fuel delivery cm³/ : 41.7...44.3
> 1000s : (41.0...45.0)
Dispersion cm³/ : 3.0
> 1000s. :

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 60
Speed 1/min : 1250
Checkbk. volt mV : 3200
Measuring
temperature °C : 56
Fuel delivery cm³/ : 48.9...51.9
> 1000s : (48.1...52.7)
Dispersion cm³/ : 3.0
> 1000s :

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2450
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (37.1...40.1)
Dispersion cm³/ :
> 1000s : (3.0)

4th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2450
Measuring
temperature °C : 57
Fuel delivery cm³/ : 44.6...47.2
> 1000s : (43.9...47.9)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 1600
Meßtemperatur °C : 57
Fuel delivery cm³/ : 9.9...10.9
> 1000s : (7.4...13.4)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2560
Measuring
temperature °C : 61
Fuel delivery cm³/ : 43.5...57.5
> 1000s : (39.5...61.5)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 1000
Checkbk. volt mV : 3400
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description
K mm :
KF mm : 6.5...6.9
SVS max. mm :
FH mm :
TS : 1 467 010 494

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : Renault
 Date of manufacture :
 Edition : 22.05.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/11E2000R672
 Type No. : 0 460 414 993
 Customer Ident.No. :

Customer-specific details
 Customer : Renault

Engine : F 9 Q 730

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 434
 (fuel-delivery
 actuator) : (KDEP 1865/5)

Test line : 0 986 612 435
 (solenoid valve
 start of injection) : (KDEP 1865/6)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 4 and 7
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground, Mohms min. : 1.0
 Connections 2 and 7
 Mohms min. : 1.0
 Connections 4 and 6
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 3
 Ohm : 4.9...6.5
 Connections 2 and 3
 Ohm : 4.9...6.5
 Connections 1 and 2
 Ohm : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 5 and 6
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 500
Checkbk. volt.
mV : 2100
Setting value, bar : 6.9...8.1

Timing device travel:
Speed 1/min : 500
Checkbk. volt
mV : 2100
Setting value, mm : 10.9...11.1

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 35.8...36.2
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 3670
Supply pump
pressure > bar : 9.4...10.6
> bar :

2st speed 1/min : 200
Checkbk. volt
mV : 2100
Supply pump
pressure > bar : 5.0...7.0
> bar :

Timing device variations:

1st speed 1/min : 200
Checkbk. volt. mV : 2100
Timing device
travel mm : 4.9...8.9
> mm : (3.9...9.9)

2nd speed 1/min : 2000
Checkbk. volt. mV : 3670
Timing device
travel mm : 11.8...12.8
> mm : (11.5...13.1)

3rd speed 1/min : 1500
Checkbk. volt. mV : 1500
Timing device
travel mm : max. 1.0
> mm : (max. 1.2)

Solenoid valve
Start of
injection, volts : 12

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt. mV : 3670
Measuring
temperature °C : 53
Overflow : 118...202
> cm³/10 :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 2000
Checkbk. volt mV : 3670
Meßtemperatur °C : 53
Fuel delivery cm³/ : 44.7...47.3
> 1000s : (44.0...48.0)
Dispersion cm³/ : 3.0
> 1000s :

2nd temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 1500
Checkbk. volt mV : 3490
Measuring
temperature °C : 53
Fuel delivery cm³/ : 46.8...19.8
> 1000s : (46.0...50.6)
Dispersion cm³/ : 3.0
> 1000s :

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2480
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (34.5...37.5)
Dispersion cm³/ :
> 1000s : (3.0)

4th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2100
Measuring
temperature °C : 57
Fuel delivery cm³/ : 26.9...30.9
> 1000s : (25.9...31.9)
Dispersion cm³/ : 3.0
> 1000s :

Idle delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 550
Checkbk. volt mV : 1800
Meßtemperatur °C : 57
Fuel delivery cm³/ : 15.0...16.0
> 1000s : (12.5...18.5)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2640
Measuring
temperature °C : 61
Fuel delivery cm³/ : 42.0...58.0
> 1000s : (36.0...64.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 900
Checkbk. volt mV : 3490
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions

"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description
K mm :
KF mm :
SVS max. mm :
FH mm :

BOSCH INJECTION PUMP TEST SPECIFICATIONS

ELECTRICAL TEST

Observe notes in remark column

Test sheet : ROW
 Date of manufacture :
 Edition : 08.07.1994
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE4/11E2250L580
 Type No. : 0 460 414 995
 Customer Ident.No. :

Customer-specific details
 Customer : ROVER

Engine : TCIE

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve :

Test line : 0 986 612 437
 (fuel-delivery actuator)

Test line : 0 986 612 438
 (solenoid valve
 start of injection)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohm : 4.9...6.5
 Connections 2 and 3
 Ohm : 4.9...6.5
 Connections 1 and 3
 Ohm : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:

Speed 1/min : 1000
Checkbk. volt. : 3400
mV : 3400
Setting value, bar : 6.9...7.7

Timing device travel:

Speed 1/min : 1000
Checkbk. volt : 3400
mV : 3400
Setting value, mm : 7.8...8.0

Full-load delivery :

1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt : 2500
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt : 2450
mV : 2450
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 38.5...38.7
Dispersion cm³/
> 1000s :

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2250
Checkbk. volt : 3400
mV : 3400
Supply pump
pressure > bar : 8.8...9.6
> bar :

2st speed 1/min : 500
Checkbk. volt : 3400
mV : 3400
Supply pump
pressure > bar : 6.2...7.0
> bar :

3st speed 1/min : 150
Checkbk. volt : 2560
mV : 2560
Supply pump
pressure > bar : 3.5...10.5
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3400
Timing device
travel mm : 5.2...7.6
> mm : (4.4...8.4)

2nd speed 1/min : 2250
Checkbk. volt. mV : 3400
Timing device
travel mm : 9.4...10.2
> mm : (9.2...10.4)

3rd speed 1/min : 1500
Checkbk. volt. mV : 1650
Timing device
travel mm : max. 1.0
> mm : (max. 3.5)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 1000
Checkbk. volt. mV : 3400
Timing device
travel mm :
> mm : (6.9...8.9)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 2250
Checkbk. volt. mV : 3400
Measuring
temperature °C : 53
Overflow : 83...167
> cm³/10 :

Fuel delivery variations:

1st temperature-conditioning
 revolution 1/min : 100
 Checkbk. volt mV : 2500
 Output
 temperature °C : 51
 Speed 1/min : 2250
 Checkbk. volt mV : 3400
 Meßtemperatur °C : 53
 Fuel delivery cm³/ : 42.3...44.9
 > 1000s : (41.6...45.6)
 Dispersion cm³/ : 2.5
 > 1000s :

2nd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 60
 Speed 1/min : 1250
 Checkbk. volt mV : 3200
 Measuring
 temperature °C : 56
 Fuel delivery cm³/ : 49.2...52.2
 > 1000s : (48.4...53.0)
 Dispersion cm³/ : 3.0
 > 1000s :

3rd temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 750
 Checkbk. volt mV : 2450
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ :
 > 1000s : (37.1...40.1)
 Dispersion cm³/ :
 > 1000s : (3.0)

4th temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 2450
 Measuring
 temperature °C : 57
 Fuel delivery cm³/ : 44.4...47.0
 > 1000s : (43.7...47.7)
 Dispersion cm³/ : 2.0
 > 1000s :

Idle delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 61
 Speed 1/min : 500
 Checkbk. volt mV : 1600
 Meßtemperatur °C : 57
 Fuel delivery cm³/ : 9.5...12.9
 > 1000s : (8.2...14.2)
 Solenoid valve
 Start of
 injection, volts : 12
 Dispersion cm³/ : 3.0
 > 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning
 revolution 1/min : 2000
 Checkbk. volt mV : 2500
 Output
 temperature °C : 65
 Speed 1/min : 100
 Checkbk. volt mV : 2560
 Measuring
 temperature °C : 61
 Fuel delivery cm³/ : 43.5...57.5
 > 1000s : (39.5...61.5)
 Solenoid valve
 Start of
 injection, volts : 12

Stop test:

Speed 1/min : 1000
 Checkbk. volt mV : 3400
 ELAB volts : 0
 Fuel delivery cm³/ :
 max. 1000s : 3.0

Shutoff solenoid:

Cut-in voltage
 min.> volts : 10.0
 Rated voltage,
 volts : 12.0

Notes:

High-pressure compressor sensor
 Testing only possible with ballast
 EPS 910

Take note of test instructions
 "Distributor pump for direct
 injectors"!

Dimensions for mounting and setting:

Description		
K	mm	:
KF	mm	: 6.5...6.9
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 494

BOSCH INJECTION PUMP TEST SPECIFICATIONS | ELECTRICAL TEST

Observe notes in remark column

Test sheet : VW
 Date of manufacture :
 Edition : 12.06.1996
 Replaces :
 Test oil : ISO 4113
 Injection pump : VE5/11E1750L714
 Type No. : 0 460 415 986
 Customer Ident.No. :

Customer-specific details
 Customer : VW

Engine : 2.5 TDI

Output kW :
 Speed 1/min :

TEST BENCH PREREQUISITES

Inlet pressure, bar : 0.30...0.40

Calibrating nozzle-
 holder assembly > : 1 688 901 114

Opening
 pressure > bar : 207...210

Test pressure line : 1 680 750 085

Outer diameter : 6.00
 x wall thickness > : 2.20
 x length > mm : 350

Overflow valve : 2 467 413 018

Test line : 0 986 612 444
 (fuel-delivery
 actuator) :

Test line : 1 687 011 208
 (solenoid valve
 start of injection): (Test cable set)

TEST PRECONDITIONS

Test oil
 return temp. > °C
 with thermometer : 55

Test oil supply
 temperature > °C : 42...47

Hold-up
 revolutions >1/min : 1200
 Feedback
 voltage mV : 2500

Actuator
 Connections 5 and 6
 Test temperature:
 15°...30°C, ohms : 0.4...1.0
 50°...70°C, ohms : 0.45...1.1

Connections 5 and
 ground, Mohms min. : 1.0
 Connections 6 and
 ground, Mohms min. : 1.0
 Connections 3 and 5
 Mohms min. : 1.0
 Connections 6 and 7
 Mohms min. : 1.0

High-pressure compressor sensor
 Sensor coils
 Connections 1 and 2
 Ohms : 4.9...6.5
 Connections 2 and 3
 Ohms : 4.9...6.5
 Connections 1 and 3
 Ohms : 9.8...13.0

Connections 1 and
 ground, Mohms min. : 1.0
 Connections 2 and
 ground, Mohms min. : 1.0
 Connections 3 and
 ground, Mohms min. : 1.0

Temperature sensor, fuel
 Connections 4 and 7
 Test temperature:
 15°...30°C, kohms : 1.2...4.0
 50°...70°C, kohms : 0.3...1.2

Connections 4 and
 ground, Mohms min. : 1.0
 Connections 7 and
 ground Mohms min. : 1.0

Solenoid valve, start of injection
 Connections 1 and 2
 Test temperature :
 15°...30°C, ohms : 14.3...17.3
 50°...70°C, ohms : 15.5...21.0

Starting stop mV : 4120...4650

Shutoff stop mV : 650...850

Setting values of injection pump
Check values in brackets

Supply pump pressure:
Speed 1/min : 750
Checkbk. volt.
mV : 3900
Setting value, bar : 6.0...7.0

Timing device travel:
Speed 1/min : 750
Checkbk. volt
mV : 3900
Setting value, mm : 8.5...8.7

Full-load delivery :
1st temperature-conditioning
revolution 1/min : 2000
Checkbk. volt
mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt
mV : 2400
Measuring
temperature °C : 57
Fuel delivery cm³/
> 1000s : 36.4...36.8
Dispersion cm³/
> 1000s : 2.5

Test specifications of injection pump
Check values in brackets

Supply pump pressure variations:

1st speed 1/min : 2000
Checkbk. volt
mV : 3790
Supply pump
pressure > bar : 7.4...8.4
> bar :

Timing device variations:

1st speed 1/min : 500
Checkbk. volt. mV : 3900
Timing device
travel mm : 6.6...9.0
> mm : (6.3...9.3)

2nd speed 1/min : 1750
Checkbk. volt. mV : 3670
Timing device
travel mm : 11.6...12.6
> mm : (11.5...12.7)

3rd speed 1/min : 1200
Checkbk. volt. mV : 1800
Timing device
travel mm : max. 0.3
> mm : (max. 2.5)

Solenoid valve
Start of
injection, volts : 12

4.th speed 1/min : 750
Checkbk. volt. mV : 3900
Timing device
travel mm :
> mm : (7.4...9.8)

Overflow at overflow valve:

1st temperature-conditioning
revolution 1/min : 100
Checkbk. volt. mV : 2500
Output
temperature °C : 51
Speed 1/min : 1750
Checkbk. volt. mV : 3670
Measuring
temperature °C : 53
Overflow : 97...181
> cm³/10s :

Fuel delivery variations:

1st temperature-conditioning

revolution 1/min : 100
Checkbk. volt mV : 2500
Output
temperature °C : 51
Speed 1/min : 1750
Checkbk. volt mV : 3670
Meßtemperatur °C : 53
Fuel delivery cm³/ : 52.3...54.9
> 1000s : (51.6...55.6)
Dispersion cm³/ : 3.0
> 1000s : (3.0)

2nd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 750
Checkbk. volt mV : 2400
Measuring
temperature °C : 57
Fuel delivery cm³/ :
> 1000s : (35.3...37.9)
Dispersion cm³/ :
> 1000s : (2.5)

3rd temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 1000
Checkbk. volt mV : 3210
Measuring
temperature °C : 57
Fuel delivery cm³/ : 55.9...58.5
> 1000s : (55.2...59.2)
Dispersion cm³/ : 2.00
> 1000s : (2.5)

4th temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 2320
Measuring
temperature °C : 57
Fuel delivery cm³/ : 39.5...42.1
> 1000s : (38.8...42.8)
Dispersion cm³/ : 3.0
> 1000s : (3.0)

Idle delivery:

1st temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 61
Speed 1/min : 500
Checkbk. volt mV : 1520
Meßtemperatur °C : 57
Fuel delivery cm³/ : 6.9...10.9
> 1000s : (5.9...11.9)
Solenoid valve
Start of
injection, volts : 12
Dispersion cm³/ : 3.0
> 1000s : (4.0)

Starting fuel delivery:

1st temperature-conditioning

revolution 1/min : 2000
Checkbk. volt mV : 2500
Output
temperature °C : 65
Speed 1/min : 100
Checkbk. volt mV : 2960
Measuring
temperature °C : 61
Fuel delivery cm³/ : 72.0...86.0
> 1000s : (69.0...91.0)
Solenoid valve
Start of
injection, volts : 12

Stop test:

Speed 1/min : 1000
Checkbk. volt mV : 2460
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 5.0
Speed 1/min : 1500
Checkbk. volt mV : 4100
ELAB volts : 0
Fuel delivery cm³/ :
max. 1000s : 3.0

Solenoid valve

Start of
injection, volts : 12

Shutoff solenoid:

Cut-in voltage
min.> volts : 10.0
Rated voltage,
volts : 12.0

Notes:

High-pressure compressor sensor
Testing only possible with ballast
EPS 910

Take note of test instructions
"Distributor pump for direct
injectors"!

Dimensions for mounting and setting:

Description

K	mm	: 2.7...2.9
KF	mm	: 8.2...8.6
SVS max.	mm	:
FH	mm	:
TS		: 1 467 010 495